

McCrae Landslide - Evacuation Order Area

Geotechnical Factual Report

PSM5665-GFR REV0 9 April 2025

PRIVILEGED AND CONFIDENTIAL




Table of Contents

1. Introduction.....	4
1.1 Site Description	4
1.2 Purpose	4
2. Site Conditions	6
2.1 Access	6
2.2 Geology	6
3. Geotechnical Investigation.....	7
3.1 Introduction.....	7
3.2 Health and Safety	7
3.3 Survey	7
4. Site Walk Over.....	7
5. Geotechnical Drilling.....	8
5.1 Detail	8
5.2 Groundwater.....	8
6. Non-Destructive Testing	9
6.1 Detail	9
6.1.1 NDT	9
6.1.2 RD	9
6.2 Groundwater.....	10
6.2.1 NDT	10
6.2.2 RD	10
7. Cone Penetration Testing (CPT)	10
8. Laboratory Testing	11
8.1.1 Soil	11
8.1.2 Surface Water	12
9. Groundwater Monitoring.....	13

List of Tables

Table 1 – List of definitions and acronyms	5
Table 2 – Borehole summary.....	8
Table 3 – NDT and RD summary	9
Table 4 – CPT summary	11
Table 5 – Laboratory testing summary	11
Table 6 – Surface water testing summary	12

List of Insets

Inset 1:	EO area established in response to the McCrae Landslide.....	4
Inset 2:	Mapped geology from the published Sorrento 1:63,360 geological map.....	6

List of Figures

Figure 1	Geotechnical and Groundwater Investigation Plan
Figure 2	Geotechnical and Groundwater Investigation Plan (Zoomed)

List of Appendices

Appendix A	Geotechnical Logs
Appendix B	Point Load Strength Index Test Results
Appendix C	Piezometer Construction Records
Appendix D	CPT Results
Appendix E	Laboratory Testing – Material Test Reports
Appendix F	Surface Water Testing – Detailed Laboratory Reports
Appendix G	Piezometer Monitoring Results

The information will be used to separately develop a ground and groundwater model for the Site to infer landslide mechanisms, slope stability and landslide risk.

A list of abbreviations and definitions of terms used throughout the report is shown in Table 1.

Table 1 – List of definitions and acronyms

Acronym	Abbreviation
AHD	Australian Height Datum
As	Arsenic
BH	Borehole
BYDA	Before You Dig Australia
Ca	Calcium
CaCO ₃	Calcium Carbonate
Cd	Cadmium
Cl	Chlorine
CO ₃	Carbonate
CPT	Cone Penetration Testing
Cr	Chromium
Cu	Copper
DO	Dissolved Oxygen
EC	Electrical Conductivity
F	Fluorine
GNSS RTK	Global Navigation Satellite System Real Time Kinematic
GPS	Global Positioning System
HCO ₃	Hydrogen Carbonate
Hg	Mercury
K	Potassium
Mg	Magnesium
MPSC	Mornington Peninsula Shire Council
N	Nitrogen
Na	Sodium
NDT	Non-Destructive Testing
NH ₃	Ammonia
Ni	Nickel
NO ₃	Nitrate
Pb	Lead
pH	Potential of Hydrogen
PLT	Point Load Strength Index Testing
SES	State Emergency Services
SO ₄	Sulphate
TDS	Total Dissolved Solids
VWP	Vibrating Wire Piezometer
Zn	Zinc

2. Site Conditions

2.1 Access

Site access is constrained by the escarpment and urban development.

The Site has been progressively occupied since the early 20th century and is now significantly developed with numerous buildings and underground/overhead utilities. Further, access to the escarpment itself to carry out conventional site investigations is difficult due to the very steep slopes. The Investigation was therefore planned around these constraints.

2.2 Geology

The Sorrento 1:63,360 geological map is shown in Inset 2. This indicates the Site is underlain by:

- Quaternary raised coastal deposits comprising siliceous and calcareous sand, shell beds, guano (Mud Islands) at the base of the escarpment (shown as R3 in Inset 2)
- Palaeozoic granodiorite and granite comprising the elevated terrain of and behind the escarpment (shown as Dg in Inset 2).

A major regional thrust fault, the Selwyn Fault is mapped at a scale of 1:250,000 to strike WSW-ENE and crossing immediately north of the Site (ref Inset 2).



Inset 2: Mapped geology from the published Sorrento 1:63,360 geological map.

3. Geotechnical Investigation

3.1 Introduction

The Investigation was carried out between 21 January 2025 to 3 March 2025 comprising:

- Site walk over
- Geotechnical drilling
- Non-destructive testing
- Cone penetration testing
- Laboratory soil testing
- Groundwater monitoring which is ongoing.

The area covered by the investigations including the individual site investigation and sampling locations are shown in Figure 1.

A literature review was carried out for the Site by review of existing records such as:

- Geological maps
- Previous site investigations
- Topographic information
- Historical photographs
- Aerial photography
- Geohazards maps
- Construction records
- Historical newspaper articles.

The above information and a Site inspection were used to plan the Investigation including the type, location, depth and instrumentation.

3.2 Health and Safety

A Safe Work Method Statement was developed and implemented for the Investigation. All locations involving subsurface investigations were cleared of utilities by carrying out BYDA and a physical services search by Precision Pipe and Cable Locations prior to the works.

3.3 Survey

All investigation locations were set out by handheld GPS. All as built collar locations were measured using a GNSS RTK (GPS) by a registered surveyor to an approximate accuracy of ± 20 mm. The exception to this is the two hand auger locations, RD1 and RD2, Figure 1, which were measured off known and recently surveyed features and boreholes.

The coordinate system and datum adopted for the Investigation is GDA2020 MGA zone 55 and AHD.

4. Site Walk Over

Site walkovers were carried out by Mr Dane Pope of PSM between 15 to 17 January 2025 and 24 January 2025 to inspect the landslide and surrounding terrain. A further inspection was carried out over two days by Mr Tim Nash of PSM between 21 and 22 January 2025 to inspect the landslide and surrounding escarpment. The results of the inspections were used to plan the Investigation and to record the landslide characteristics. The latter will be reported separately.

5. Geotechnical Drilling

5.1 Detail

Eight vertical boreholes were drilled using a track mounted Geoprobe 7822 DT drilling rig.

BH01 to BH05 used a direct push DT22 continuous sampling method to collect soil samples from the collar up to depths of approximately 14 m below ground level (**bgl**) followed by triple tube HQ coring methods to a maximum depth of 30 m bgl. The remaining boreholes BH01A, BH03A and BH04A were drilled adjacent to the continuous sampled and cored boreholes using augering methods to drill to the target depth as these were intended for groundwater monitoring and sampling.

Rock and soil samples were collected at various depths for laboratory testing and point load strength index testing (PLT).

Geotechnical logs for the eight boreholes are presented in Appendix A.

Point load strength index tests were performed on some of the recovered rock samples, and these results are presented in Appendix B.

5.2 Groundwater

All eight boreholes were completed by installing either VWP or standpipe piezometers. Standpipe piezometer and VWP construction records including VWP calibration sheets are presented in Appendix C and summarised in Table 2.

The VWP data at BH01, BH02 and BH03 are recorded via five-channel dataloggers at a frequency of three hours.

Hobo data loggers were installed within the standpipes at BH03A and BH04 recording at a frequency of three hours.

All standpipe piezometers were constructed under the groundwater bore construction licence ID WLE089520 in the Victorian Water Register with the following Works ID:

- WRK147484
- WRK147485
- WRK147486
- WRK147487
- WRK147709.

Water observed in the boreholes following drilling completion are presented where applicable on each geotechnical log, Appendix A. Note that these observations may not reflect actual groundwater levels as they are likely to have been influenced by the fluids introduced during drilling.

Table 2 – Borehole summary

ID	Location	Easting	Northing	Collar RL	Drilled depth (m)	Standpipe piezometer/VWP summary
BH01	Carport of 10-12 View Point Road	319565.8	5753704.4	31.57	30.0	Nested VWP1A, VWP1B and VWP1C installed 4.5 m, 14.5 m and 29 m bgl.
BH01A	Adjacent to BH01	319565.7	5753703.3	31.69	6.0	Standpipe STP1A screened between 3 m and 6 m bgl.
BH02	Verge in front of 5 View Point Road	319562.3	5753681.9	31.87	30.0	Nested VWP2A, VWP2B and VWP2C installed at 6.5 m, 14.5 m and 28.5 m bgl.
BH03	10-12 View Point Road Front Lawn	319533.0	5753715.6	28.62	29.5	VWPs VWP3A and VWP3B installed 13 m and 28 m bgl.
BH03A	Adjacent to BH03	319533.7	5753716.7	28.70	6.0	Standpipe STP3A screened between 1.5 m and 6 m bgl with a hobo data

ID	Location	Easting	Northing	Collar RL	Drilled depth (m)	Standpipe piezometer/VWP summary
						logger installed at 6 m bgl. VWP VWP3C installed 6 m bgl, connected to BH03 datalogger.
BH04	Middle of View Point Road Cul-de-sac	319498.1	5753665.8	26.82	30.0	Standpipe STP4 screened between 14.7 m and 29.7 m bgl with a hobo data logger installed at 29.7 m bgl.
BH04A	Adjacent to BH04	319499.2	5753666.0	26.86	6.0	Standpipe STP4A screened between 1 m and 6 m bgl.
BH05	3 Penny Lane Driveway	319500.7	5753775.2	1.98	5.0	VWP VWP5A installed 4.8 m bgl.

6. Non-Destructive Testing

6.1 Detail

6.1.1 NDT

Two Non-Destructive Testing (**NDT**) holes (NDT01 and NDT02) were excavated to a depth between 3.5 and 5.0 m bgl to investigate sewer trench backfill. NDT01 was excavated to 5.0 m bgl, or approximately 1.8 m below the sewer trench invert. NDT02 was excavated to 3.2 m bgl. This hole terminated prior to the target depth due to excavation difficulty and inferred cave in, this being approximately 0.5 m above the design sewer trench invert level.

Both NDTs were excavated using a vacuum excavation truck with a hydrojet. The exception is with NDT01, which had the final 1.0 m excavated using a continuous flight auger.

A downhole video was taken using a GoPro to view the soil profile and identify any groundwater table / water seepage within the hole. Geotechnical logs were prepared to record the hole detail for both, but insufficient information was available from the video to provide material descriptions other than basic observations, Appendix A.

6.1.2 RD

Two hand auger holes (RD1 and RD2) were excavated to a depth of 0.7 to 0.9 m bgl to identify the ReIn Drains (**RD**) located in the front lawn of 10-12 View Point Road, and were excavated 0.4 m below the base of the ReIn Drain.

Both RDTs were excavated using a 100 mm diameter hand auger.

Geotechnical logs are presented in Appendix A.

Table 3 – NDT and RD summary

Borehole	Location	Easting	Northing	Collar RL	Total drilled depth bgl (m)
NDT01	Front yard of 6 View Point Road	319571.8	5753700.6	32.3	5
NDT02	Verge in front of 6 View Point Road	319575.4	5753696.0	32.7	3.2
RD1	10-12 View Point Road Front Lawn	319531.9	5753714.4	28.6	0.9
RD2	10-12 View Point Road Front Lawn	319534.8	5753717.7	28.8	0.7

6.2 Groundwater

6.2.1 NDT

Groundwater was not observed in both NDT holes however, water introduced from the NDT process made it difficult to distinguish between groundwater and introduced water.

The NDTs were subjected to dye tracing using red and green plumber's tracing dye to identify downstream seepage from the water source. Note that water mixed with dye was added to each NDT. The results of the dye tracing will be reported separately.

Both NDTs had standpipe piezometers installed to monitor long term groundwater levels:

- NDT01
 - 50 mm diameter PVC standpipe installed to 5.0 m depth
 - Screened between 1.5 m and 5 m below ground level
 - Backfilling comprised gravel pack to 1 m below ground level, bentonite seal to the surface and flush mounted concrete encased gatic cover installed.
- NDT02
 - VWP installed 3.2 m below ground level
 - the instrument was enveloped in 0.4 m of sand with gravel pack to 0.9 m below ground level, then a bentonite plug to around 50-100 mm below the surface, then topped with gravel and topsoil.

Appendix C presents the standpipe piezometer and VWP construction records.

6.2.2 RD

Groundwater was not observed in both RD holes. No piezometers were installed within these holes.

Upon completion of excavation, both holes were backfilled with a bentonite plug and topped with site won materials.

7. Cone Penetration Testing (CPT)

Seven CPTs were pushed to approximately 15 m depth bgl using a track mounted drilling rig ('The Pagani') and a truck mounted drilling rig ('The Trakker'), Table 4.

All CPTs included pore pressure readings (CPTu) and were performed adjacent to the boreholes from Section 5.

Predrilling was undertaken using the track mounted drilling rig at CPT01B, CPT04, CPT04A, and CPT05.

Five CPTs terminated prior to the target depth on inferred dense gravels or cobbles/boulders due to refusal of the CPT rod. Two of these (CPT01 and CPT04) were relocated and retested within a few metres of the refused location, to reach target depths.

Dissipation testing (DT) was performed for CPT01B, CPT03, CPT04A and CPT05 at various depths.

CPT03, CPT04 and CPT04A were located at the same location as their corresponding boreholes (BH03A, BH04 and BH04A, respectively) and were converted to standpipes. The other CPTs were backfilled with spoil to the surface and only CPT05 was capped with a concrete plug.

Appendix D presents data from the CPT testing. It also includes the interpreted normalised soil behaviour types in accordance with Robertson & Cabal (2022)² assuming an N_{kt} of 14.

² Robertson, P. K., and K. Cabal. 2022, *Guide to Cone Penetration Testing* Seventh edition.

Table 4 – CPT summary

CPT	Location	Easting	Northing	Collar RL	Tested depth bgl (m) ⁽¹⁾	Dissipation testing depths (m)
CPT01	Carport of 10-12 View Point Road	319564.8	5753703.8	31.63	2.78 (t)	N/A
CPT01A	Adjacent to CPT01	319565.0	5753702.3	31.69	3.39 (t)	N/A
CPT01B	Adjacent to CPT01A	319565.7	5753702.1	31.70	15.53	6.35 m and 12 m
CPT03	Backyard of 10-12 View Point Road	319533.7	5753716.7	28.70	3.03 (t)	3.03 m
CPT04	Middle of View Point Road Cul-de-sac	319499.2	5753666.1	26.86	1.89 (t)	N/A
CPT04A					13.91	9.1 m and 13.9 m
CPT05	3 Penny Lane Driveway	319501.3	5753776.9	1.91	2.27 (t)	2.26 m

(1) (t) terminated early due to refusal

8. Laboratory Testing

8.1.1 Soil

Soil samples were collected during the Site walkover on 24 January 2025 from the escarpment and flanks of the McCrae Landslide, Figure 1. Soil samples were also taken from boreholes BH01 to BH05 during the February 2025 site investigations. All were tested in a NATA accredited laboratory for moisture content, particle size distribution and Atterberg limits, Table 5. Laboratory testing certificates are presented in Appendix E.

Table 5 – Laboratory testing summary

Sample ID	Sample depth (m)	Location	Testing		
			Natural moisture content	Particle size distribution	Atterberg limits
S1	At surface	Rill/consolidated waste on slope	X	X	
S2	At surface	LHS/NE slope	X	X	
S3	At surface	Lower flank of rill on RHS/SW slope	X	X	
S4	At surface	Upper RHS/SW slope, gum tree/scarp	X	X	X
S5	At surface	S4 upper	X	X	
S6	At surface	SW flank 2022 landslide	X	X	X
BH01	1.4 - 2.3	BH01	X ⁽¹⁾	X	
BH01	7.2 - 8.0	BH01	X ⁽¹⁾	X	X
BH01	17.8 - 17.9	BH01	X		
BH01	22.9 - 23.0	BH01	X		
BH02	1.6 - 2.6	BH02	X ⁽¹⁾	X	
BH02	4.2 - 5.0	BH02	X ⁽¹⁾	X	X
BH02	6.7 – 7.5	BH02	X ⁽¹⁾	X	X
BH03	2.7 - 4.0	BH03	X ⁽¹⁾	X	
BH03	7.2 - 8.0	BH03	X ⁽¹⁾	X	X

Sample ID	Sample depth (m)	Location	Testing		
			Natural moisture content	Particle size distribution	Atterberg limits
BH03	10.8 - 11.5	BH03	X ⁽¹⁾	X	X
BH03	14.75 - 14.85	BH03	X	X	
BH03	15.5 - 15.6	BH03	X		
BH03	21.4 - 21.55	BH03	X	X	
BH03	23.3 - 23.4	BH03	X	X	
BH04	3.1 - 3.6	BH04			X
BH04	5.0 - 5.8	BH04			X
BH04	15.0 - 15.1	BH04	X		
BH05	1.6 - 2.3	BH05	X ⁽¹⁾		
BH05	2.6 - 3.6	BH05	X ⁽¹⁾	X	

(1) Sample was tested for moisture content in error. Moisture content not to be relied upon.

8.1.2 Surface Water

Surface water was sampled on 20 January 2025 by JBS&G in the presence of PSM staff. The sampling was conducted at five locations for field water quality testing and laboratory testing, Figure 1. A calibrated water quality meter was used in the field to measure pH, temperature, dissolved oxygen (DO), electrical conductivity (EC) and redox potential, Table 6. Each of these samples were then tested in a NATA accredited laboratory for the following:

- Cations & Anions [Alkali Metals (Na, K, Ca, Mg), Alkalinity (CO₃, HCO₃) (as CaCO₃), Cl, SO₄]
- Ionic Balance [pH, EC]
- Total Dissolved Solids (TDS)
- Non-Metallic Inorganics [NH₃ (as N), F, NO₃ (as N)]
- Metals [As, Cd, Cr, Cu, Ni, Pb, Zn, Hg].

Appendix F presents the results of the water sample laboratory testing.

Table 6 – Surface water testing summary

ID	Location	Sample Date and Time	pH	Temp (°C)	DO (mg/L)	EC (us/cm)	Redox Potential (mV)	Comment
SW01	Flowing water from 5 Prospect Hill Road into gutter	20/01/2025 9:30am	7.47	22.7	5.92	125.0	91.7	No odour, no sheen, clear, no colour
SW02	Flowing water from 7 Prospect Hill Road into private stormwater pit	20/01/2025 9:55am	6.50	20.6	7.26	332.5	99.0	No odour, no sheen, high turbidity, brown
SW03	Flowing drain around 4 View Point Road	20/01/2025 10:20am	7.19	21.7	6.48	359.5	80.9	No odour, no sheen, high turbidity, brown
SW04	Flowing drain at View Point Road Cul-de-sac	20/01/2025 10:40am	7.74	22.9	8.91	360.6	75.8	No odour, no sheen, high turbidity, brown
SW05	Flowing water along east side of Penny Lane	20/01/2025 1:05pm	7.97	24.2	6.30	1051.0	79.3	No odour, no sheen, very high turbidity, brown

9. Groundwater Monitoring

Piezometric monitoring data for the following VWPs and hobo data loggers are presented in the hydrographs in Appendix G:

- BH01: VWP1A to VWP1C between 20 February 2025 to 25 March 2025
- BH02: VWP2A to VWP2C between 24 February 2025 to 25 March 2025
- BH03: VWP3A to VWP3B between 18 February 2025 to 7 March 2025
- BH03A:
 - VWP3C between 25 February 2025 to 25 March 2025
 - Hobo data logger on 20 March 2025
- BH04: Hobo data logger between 20 March 2025 to 25 March 2025
- BH05: VWP5A on 26 February 2025 and 20 March 2025
- NDT02: VWP2D between 3 March 2025 to 25 March 2025.

Yours Sincerely

Irrelevant & Sensitive

DANE POPE
PRINCIPAL

Brisbane

Level 6, 500 Queen Street
Brisbane QLD 4000
+61 7 3220 8300

Sydney

G3-56 Delhi Road
North Ryde NSW 2113
+61 2 9812 5000


Melbourne

Office 16
Level 4, 60 Moorabool Street
Geelong VIC 3220
+61 3 7068 5699

Perth

Level 3 22 Delhi Street
West Perth WA 6005
+61 8 9462 8400





Legend

Site Investigation Locations

- BH
- NDT
- CPT
- RD
- Soil Sampling Locations 24/01/2025
- Surface Water Sampling Locations 20/01/2025

Cadastral

- Cadastral Boundaries

Surface Contours 5/02/2025

- 1m Contours
- 5m Contours

NOTES:

1. Aerial imagery is taken on 6 February 2025 (Source: Nearmap.com, 2025).

2. Surface contours based on Diospatial survey (Ref. 250205_25010_McCrae_LargerArea_DTM25cm, dated 5 February 2025).

3. CPT03 and BH03A are at the same location. CPT03 was pushed and then BH03A was augered.

Scale 1:750

0 20 40 m


Map Projection:
Horizontal Datum:
Grid: EPSG:7855

Created By:	JW	Revision:	A
Date:	27 Mar 2025	Paper Size:	A3

PSM

MORNINGTON PENINSULA
SHIRE COUNCIL
MCCRAE LANDSLIDE
GEOTECHNICAL
AND GROUNDWATER
INVESTIGATION PLAN

PSM5665-GFR	FIGURE 1
-------------	----------




- Legend
- Site Investigation Locations
- BH
 - NDT
 - CPT
 - RD
 - Soil Sampling Locations 24/01/2025
 - Surface Water Sampling Locations 20/01/2025
- Cadastral
- Cadastral Boundaries
- Surface Contours 16/01/2025
- 1m Contours
 - 5m Contours

NOTES:

1. Aerial imagery is based on Diospatial survey undertaken on 16 January 2025 (Ref. 250116_25010_McCrae Landslip_Ortho2cm)

2. Surface contours based on Diospatial survey (Ref. 250116_25010_McCrae Landslip_Ortho2cm, dated 16 January 2025).

3. CPT03 and BH03A are at the same location. CPT03 was pushed and then BH03A was augered.



MORNINGTON PENINSULA
SHIRE COUNCIL
MCCRAE LANDSLIDE
GEOTECHNICAL
AND GROUNDWATER
INVESTIGATION PLAN (ZOOMED)

PSM5665-GFR

FIGURE 2

Appendix A

Geotechnical Logs

GEOTECHNICAL LOGGING EXPLANATION SHEET



This explanation document presents the definitions and details used on PSM borehole logs. It is not intended to replace the details in AS 1726: 2017.

Geotechnical logs are shown as either non-cored, for the soil component, or cored for the rock interval.

The document is divided into three parts: drilling information, soil logging and rock logging.


Drilling Information

General

Method	AD/T	Auger drilling TC bit
	AD/V	Auger drilling V bit
	WB	Washbore
	PT	Push tube
	DT	Diatube
	E	Excavator
	CS	Continuous sampling
	NQ3	Wireline triple tube core (45.1 mm)
	HQ3	Wireline triple tube core (61.1 mm)
	NMLC	Triple barrel large core (51.2mm)
Core Quality	RQD	Rock Quality Designation (%)
Water	 Inflow	Indicates inflow of groundwater through the base of the borehole observed as net excess drilling fluid return.
	 Partial loss	Indicates an outflow of drilling fluid from the closed drilling system through the base of the borehole observed as net loss of drilling fluid return.
	 Complete loss	Indicates zero drilling fluid return from the borehole. Losses into the soil or rock mass through the base of the borehole.

Penetration

Penetration is a qualitative measure of how easily the auger advances. This varies from no resistance to refusal.



Support

Borehole wall support during drilling will either be listed as casing (C) or where no casing as was required no support (N) or left blank.

Water

Observations of water down the borehole as observed, not observed, not encountered or return as a percentage of the drilling fluid. If not noted then return was 100%.

Sampling and Field Testing

	Abbreviation	Description
Sample	U	Undisturbed tube sample
	D	Disturbed sample
	ES	Environmental sample
	TW	Thin walled
	LB	Large disturbed sample
	B	Bulk disturbed sample
Test	Is(50) – a	Axial point load test result (MPa)
	Is(50) – d	Diametral point load test result (MPa)
	SPT	Standard penetration test
	RW	Rod Weight
	HW	Hammer Weight
	HB	Hammer Bouncing

Hole Positioning

The following geodetic conventions are adopted.

- Map Grid of Australia 1994 (MGA94)
- Geocentric Datum of Australia 1994 (GDA94)
- Australian Height Datum (AHD)
- Bearings relate to magnetic north. Where required, magnetic values have been converted from grid using a magnetic declination of -12°.

Hole location relates to the street or project area the borehole was drilled on.

Depth is the downhole depth in metres below the borehole collar (i.e. surface level).

RL shows the elevation relative to AHD.

WPT (Lugeon)

The Water Pressure Test (usually using packers) measures water pressure and flow rate over time to assess the Lugeon value - an empirical measure of the hydraulic conductivity.

RQD

Rock quality designation is a measure of the quality of cored rock. The sum of intact intervals more than 100 mm in length are given as a percentage of the total drill run recovered.

Termination Details

Hole terminated means the hole was discontinued at a depth that corresponds to the downhole depth in metres. How the borehole was completed is also stated. This includes the following main categories:

- Grouted to surface using a cement grout mix.
- Instrumented by construction of groundwater (open standpipe, screened piezometer, grout in place vibrating wire piezometer (VWP)) or geotechnical (inclinometer, extensometer).
- Any other details such as if a hole was abandoned.

Soil Logging

General

In engineering terms, soil includes every type of uncemented, or partially cemented inorganic or organic material found in the ground. In practice, if the material can be remoulded or disintegrated by hand in its field condition or in water it is described as a soil. Other materials are described using rock description terms

Classification Symbol

Soil name is described in accordance with the Unified Soil Classification System (USCS) with the following prefix

O	organic soils
C	inorganic fine-grained soils behaving as clays
M	inorganic fine-grained soils behaving as silts
G	coarse grained soils behaving as gravel
S	coarse grained soils behaving as sand

These are defined by the particle size limits shown in the grading table below.

The above group symbols are appended with minor component modifiers, for coarse grained soils.

W	well graded, little or no fines
P	poorly graded, little or no fines
G	gap graded
M	silty mixtures
C	clayey mixtures

For fine grained soils, with plasticity or liquid limit

L	low plasticity or liquid limit
I	medium plasticity or liquid limit
H	high plasticity or liquid limit.

Material Description

Soil Name

Soil name is based on the identifiable primary component of the soil and is given in block letters, thereafter is a description based on secondary components.

Plasticity

Non-plastic	3 mm thread cannot be rolled at any moisture content (cannot conduct toughness or dry strength tactile tests), slow to rapid dilatancy.
Low plasticity silt/clay mixtures	A 3 mm thread can barely be rolled; lump cannot be formed when drier than plastic limit (PL); low to medium dry strength, medium toughness; none to slow dilatant behaviour
Medium plasticity silt/clay mixtures	3 mm thread is easy to roll, little time required to reach PL; thread cannot be rerolled after reaching PL; lump crumbles when drier than PL; medium to high dry strength, medium toughness; no to slow dilatant behaviour; slightly tacky feel when wet
High plasticity clays	It takes considerable time rolling and kneading to reach PL; thread can be rolled several times after reaching PL; high toughness, high to very high dry strength; non-dilatant; tacky/sticky feel when moisture content >PL.

Particle Size Descriptive Terms

Fraction	Coarse-Grained									Fine-grained		Organic
	Boulders	Cobbles	Gravel			Sand			Silt	Clay		Organic soils
			Coarse	Medium	Fine	Coarse	Medium	Fine				
Particle size limits [mm]	200	60	20	6.0	2.0	0.6	0.2	0.06	0.002			
AS Sieve equivalent [mm]	-	63	19	6.7	2.36	0.6	0.15	0.075	-			

Graphic Log

	ASPHALT
	CONCRETE
	FILL
	CH High plasticity CLAY
	CI Medium plasticity CLAY
	CL Low plasticity CLAY
	GC clayey GRAVEL
	GP Poorly graded GRAVEL
	MH High liquid limit SILT
	ML Low liquid limit SILT
	OH High plasticity ORGANIC CLAY and SILTS
	OL Low plasticity ORGANIC CLAY and SILTS
	SC Clayey SAND
	SM Silty SAND
	SP Poorly graded SAND
	SW Well graded SAND

Grading (coarse grained soils)

Where possible for coarse grained soils, include particle shape: equidimensional - rounded, sub-rounded, sub-angular, angular; two-dimensional - flaky/ platy; one dimensional - elongated.

Well graded	Having good representation of all particle sizes from largest to smallest
Poorly graded	One or more intermediate sizes poorly represented
Gap graded	Absence of one or more intermediate sizes
Uniform	Most particles are about the same size

Colour

Described in a moist condition, using simple colour terms such as green, red, orange, etc. These may have been modified using 'pale', 'dark' or 'mottled'. 'Light' is avoided as it can be confused with mass.

Secondary Component Modifiers

Term	Coarse grained soil		Fine grained soil
	Percentage of fines in a granular soil	Percentage of coarse in a granular soil (i.e. other than the primary component)	Percentage of coarse grained component (sand or gravel) in a fine-grained soil
Add trace	≤ 5	≤ 15	≤ 15
Add with	> 5 and ≤ 12	> 15 and ≤ 30	> 15 and ≤ 30
Add prefix to name	> 12	> 30	> 30

Moisture Condition

Coarse grained soil	
Dry (D)	Looks and feels dry; dusty; dry to the touch, non-cohesive, free running
Moist (M)	Soil feels cool; soil tends to stick together; damp but no visible water, darkened in colour
Wet (W)	Visible free water when handled, soil feels cool, darkened in colour
Fine grained soil	
Judge based on the soil's moisture condition relative to the plastic limit or liquid limit for soils with high moisture contents, refer to plasticity table above	

Consistency/Relative Density

Consistency - Cohesive soils (fine grained)

Consistency	Field Guide to Consistency	Indicative Undrained Shear Strength (Su, kPa)
Very soft (VS)	Exudes between the fingers when squeezed in hand	≤ 12
Soft (S)	Moulded by light finger pressure	> 12 & ≤ 25
Firm (F)	Moulded by strong finger pressure	>25 & ≤ 50
Stiff (St)	Cannot be moulded by fingers	>50 & ≤ 100
Very stiff (VSt)	Readily indented by thumb nail	>100 & ≤ 200
Hard (H)	Indented with difficulty by thumbnail	>200
Friable (Fr)	Easily crumbled by hand	-
Weakly Cemented (WCe)	Material easily disaggregated by hand in air or water	-
Moderately Cemented (MCe)	Material requires effort to disaggregate by hand in air or water	-

Relative density - Non-cohesive soils (coarse grained)

Term	Symbol	Density Index %
Very Loose	VL	<15
Loose	L	>15 & ≤ 35
Medium Dense	MD	>35 & ≤ 65
Dense	D	>65 & ≤ 85
Very Dense	VD	>85

The relative density of coarse-grained soils is inherently difficult to assess by visual or tactile means. Relative density assessment should be carried out using penetration test procedures.

Hand Penetrometer

Refers to pocket penetrometer tests, results shown in kPa.

Structure, Zoning

Soil *in situ* or in samples may consist of separate zones differing in colour, grain size or other properties.

Zoning ¹	Cementing ²
Layer Continuous across exposure or sample	Weakly Soil fractured by hand in air/water
Lens Discontinuous layer with lenticular shape	Strongly Difficulty fracturing by hand in air/water
Pocket Irregular inclusion	
Homogenous Same colour/texture/structure throughout	

¹ Record the orientation, contact character (sharp regular/irregular, gradual/gradational). Use interlaminated or inter-bedded if too thin to describe individually

² If unable to be disaggregated, treat as rock. Note cementing agent by appearance, strength or reaction to water/acid.

Origin, Additional Observations

Where there is doubt, the terms 'possibly' or 'probably' are used (as per AS1726:2017).

Origin		
Anthropogenic	Fill	placed by human activity (controlled versus uncontrolled)
Formed in place	Topsoil	upper surface layer of soil with high proportion of organic material
Transported	Alluvial	deposited by streams and rivers
	Colluvial	deposited on slopes chiefly by gravity
	Aeolian	deposited by wind
	Lacustrine	deposited in lakes/still bodies of water
	Marine	deposited in oceans, bays, beaches & estuaries
Formed in place	Residual soils	structure and fabric of parent rock not visible
	Extremely weathered	structure and fabric of parent rock visible

Rock Logging

General

Rock Substance is defined in engineering terms as any naturally occurring aggregate of minerals and organic material which cannot be disintegrated or remoulded by hand in air or water. Other material is described using soil descriptive terms. Effectively homogenous material may be isotropic or anisotropic.

Defects are defined as discontinuities or breaks in the continuity of a substance or substances

Rock mass is defined as a body of material that is not effectively homogeneous. It can consist of two or more substances without defects, or one or more substances with one or more defects

Rock substance and mass characteristics are shown on the logs as rock substance and rock mass defect categories and are presented in this document in the same order

Rock substance

Graphic Log



BRECCIA



CONCRETE



CONGLOMERATE



NO CORE



DOLERITE



INTERBEDDED SILTSTONE & SANDSTONE



SANDSTONE



SHALE



SHALE BRECCIA



SILTSTONE

Material Description

Rock Name	Simple rock names are used rather than precise geological classification		
Particle/grain Characteristics	Grains of rock described in terms of type, size and shape;		
	sedimentary rocks:	Coarse	0.6 - 2 mm
		Medium	0.2 - 0.6 mm
		Fine	0.06 - 0.2 mm
	igneous rocks	Coarse	>2 mm
		Medium	0.06 – 2 mm
		Fine	<0.06 mm (just visible)
Colour	Simple terms such as white, red, orange etc. modify using pale of sark; describe in moist condition; use combinations of these when necessary		
Inclusions/ Minor components	Record isolated inclusions within the rock substance such as vesicles, nodules, phenocrysts, concretions, veins, ironstone bands; Indicate proportion – trace or minor (include thickness)		

Texture/Fabric

Term	Description	Spacing
Massive	No stratification visible	-
Bedded	Very thickly bedded	>2 m
	Thickly bedded	0.6 m to 2 m
	Medium bedded	0.2 m to 0.6 m
	Thinly bedded	60 mm to 200 mm
	Very thinly bedded	20 mm to 60 mm
Laminated	Laminated	6 mm to 20 mm
	Thinly laminated	<6 mm

Bedding Development

Term	Description
Massive / poorly	No obvious development; rock homogeneous
Developed	Barely obvious; faint mineralogical layering or banding; planes poorly defined
Well developed	Apparent in outcrops or drill core as distinct layers/lines marked by mineralogical or grain-size layering
Very well developed	Often marked by distinct colour banding or mineralogical /grain size layering

Weathering

Term	Description
Residual Soil (RS)	Soil derived from insitu weathering of rock; structure and substance fabric of parent rock no longer evident; soil has not been transported; log using soil descriptive terms
Extremely Weathered (XW)	Rock exhibits soil properties; mass texture/structure of original rock still visible; log using soil descriptive terms
Highly weathered (HW)	(DW) ¹ Iron staining or bleaching affects the entire rock substance and parent rock colour no longer recognisable; porosity may be increased or less than original rock substance by leaching or deposition of minerals; substance strength altered by weathering. Primary minerals may have weathered to clay
Moderately weathered (MW)	
Slightly weathered (SW)	Partial staining or bleaching along joints; colour and texture of fresh rock is recognisable; little or no change of strength from fresh rock
Fresh (FR)	No sign of mineral decomposition or colour change

¹ The terms Highly weathered (HW) or Moderately weathered (MW) are preferred to Distinctly weathered (DW).

Strength

Rock strength is based on UCS (MPa), point load strength index testing (Is(50) in MPa) and field estimated strengths. Is(50) values from axial and/or diametral point load tests and field estimated strengths are plotted in the strength column.

Term / Abbreviation	Point load index, Is(50) (UCS (MPa))	Field guide to strength
Very low	VL	0.03 to ≤0.1; (0.6-2)
Low	L	>0.1 to ≤0.3; (2-6)
Medium	M	>0.3 to ≤1.0; (6-20)
High	H	>1 to ≤3; (20-60)
Very high	VH	>3 to ≤10 (60-200)
Extremely high	EH	> 10 (>200)

Rock Mass Defects

General

Sequence of terms: defect type, orientation, shape, roughness, infill type/width, number, spacing/length/aperture.

Defect Description

Symbol	Description
BF	bedding fabric
BP	Bedding parting – surface crack across which there is little to no tensile strength, parallel to bedding fabric, maybe open or closed
BSH	Bedding Shear
CO	Contact – surface between two lithologies
CZ	Crushed Zone – zone with roughly parallel, planar boundaries (commonly slickensided) containing disoriented usually angular rock fragments of variable size often in a soil matrix
DB	Drilling Break – breaks caused by the drilling process, including handling breaks when boxing core
FL	Foliation
FT	Fault – fracture along which displacement is recognisable, may be open or closed
FZ	Fractured Zone – a zone of closely spaced defects comprising core lengths < 50 mm

Symbol	Description
IS	Infilled Seam – seam of soil substance formed by migration of soil into an open cavity or defect
JT	Joint – a single fracture across which rock has little or no tensile strength, is not obviously related to rock fabric and no shearing, maybe open or closed
SM	XW seam of soil material formed by weathering of the parent rock material in situ
SS	Sheared seam– fracture along which movement has taken place; no displacement recognisable; slickensides, polishing and/or clay gouge may suggest movement
SZ	Sheared Zone – zone of multiple closely spaced shears
VN	Vein – intrusion of tabular or sheet-like minerals
VO	void

Orientation

Field mapping: defect dip/dip direction recorded in degrees, noting datum.

Infill

CN	Clean	RF	Rock fragments
CA	Calcite	G	Gravel
X	Carbonaceous	S	Sand
FE	Iron	Z	Silt
QZ	Quartz	CL	Clay

For infills <1 mm thick:

Stained (SN) – no visible coating but defect surfaces are discoloured

Veneer (VR) – visible uniform or patchy coating too thin to measure

Coating (CO)

Shape

Planar (PR)	No variation in orientation
Curved (CU)	Gradual change in orientation
Undulating (UN)	Wavy surface shape
Stepped (ST)	One or more well defined steps
Irregular (IR)	Many sharp changes of orientation

Surface Roughness

Slickensided (SL)	Grooved or striated surface, usually polished
Polished (POL)	Shiny smooth surface
Smooth (S)	Smooth to touch, few or no surface irregularities
Rough (RF)	Many small surface irregularities (ampl. <1mm) feels like fine to coarse sandpaper
Very rough (VR)	Many large small surface irregularities (ampl. >1mm) feels like (or coarser than) very coarse sandpaper



Borehole ID

BH01

Page 1 of 7

Geotechnical Log



Project No.: PSM5665

Client:	Mornington Peninsula Shire Council	Commenced:	19/02/2025
Project Name:	McCrae Landslide Geotechnical Investigation	Completed:	20/02/2025
Hole Location:	10-12 View Point Road Driveway	Logged By:	JW/LL
Hole Position:	319565.8 m E 5753704.4 m N GDA2020 / MGA Zone 55	Checked By:	TN
Drill Model and Mounting:	Geoprobe 7822 DT	Inclination:	-90°
Hole Diameter:	CS - 57 mm, HQ3 - 96 mm	RL Surface:	31.57 m
		Bearing:	-
		Datum:	AHD
		Operator:	SW Drilling

Drilling Information							Soil Description								Observations																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																															
Method	Penetration	Support	Water	Samples Tests Remarks	Recovery	RL (m)	Depth (m)	Graphic Log	Classification Symbol	Material Description	Moisture Condition	Consistency / Relative Density	Hand Penetrometer UCS (kPa)				Structure, Zoning, Origin, Additional Observations																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													
CS		N		PP 0.70 m >600 kPa		30.6	1		OL	FILL: Gravelly SAND: fine to coarse grained; gravel fine to medium grained.	D					0.00: Roadbase																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																														
										TOPSOIL: Sandy SILT: low plasticity, brown; sand fine grained.	D				0.10: Topsoil																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																															
									SM	FILL: Silty SAND: fine to medium grained, low plasticity, grey.	D				0.30: Possibly Fill																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																															
									CL	CLAY trace sand: low plasticity, brown; sand fine grained.	w > PL	H		* 0.70: Possibly Colluvium or Fill to 5.75 m																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																
										No recovery.																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																				
				D 1.40-2.30 m		29.6	2		SM	Silty SAND trace gravel: fine to coarse grained, brown; silt low plasticity; gravel fine to medium grained.	M																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																			
									SW	Gravelly SAND: fine to coarse grained, brown; gravel fine grained.	M																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																			
									SW	No recovery.	M																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																			
									SW	Gravelly SAND: fine to coarse grained, brown; gravel fine grained.	M																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																			
								PP 2.90 m =280 - 320 kPa	28.6	3		CL	CLAY with sand: low plasticity, grey mottled orange; sand fine grained.	w < PL	VSt		✖																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													
						SW	SAND with gravel trace clay: fine to coarse grained, brown; gravel subangular, fine to coarse grained.				M																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																			
						SC	Clayey SAND: fine to medium grained, brown; clay low plasticity.				M																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																			
						27.6	4					SM	Silty SAND: fine grained, grey; silt low plasticity.	M																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																

Method

AD/T - Auger drilling TC bit
 AD/V - Auger drilling V bit
 WB - Washbore
 SPT - Standard penetration test
 PT - Push tube
 AS - Auger screwing
 CS - Continuous sampling (DT22)
 NDD - Non destructive drilling
 CC - Concrete coring
 HA - Hand Auger

Penetration**Water****Samples and Tests**

U - Undisturbed Sample
 D - Disturbed Sample
 SPT - Standard Penetration Test
 ES - Environmental Sample
 TW - Thin Walled
 LB - Large Disturbed Sample

Moisture Condition

D - Dry
 M - Moist
 W - Wet

Consistency/Relative Density

VS - Very soft
 S - Soft
 F - Firm
 St - Stiff
 VSt - Very stiff
 H - Hard
 VL - Very loose
 L - Loose
 MD - Medium dense
 D - Dense
 VD - Very dense
 Ce - Cemented
 C - Compact



Borehole ID

BH01

Page 2 of 7

Geotechnical Log

Project No.: PSM5665

Client: Mornington Peninsula Shire Council				Commenced: 19/02/2025													
Project Name: McCrae Landslide Geotechnical Investigation				Completed: 20/02/2025													
Hole Location: 10-12 View Point Road Driveway				Logged By: JW/LL													
Hole Position: 319565.8 m E 5753704.4 m N GDA2020 / MGA Zone 55				Checked By: TN													
Drill Model and Mounting: Geoprobe 7822 DT				Inclination: -90°		RL Surface: 31.57 m											
Hole Diameter: CS - 57 mm, HQ3 - 96 mm				Bearing: -		Datum: AHD Operator: SW Drilling											
Drilling Information							Soil Description							Observations			
Method	Penetration	Support	Water	Samples Tests Remarks	Recovery	RL (m)	Depth (m)	Graphic Log	Classification Symbol	Material Description	Moisture Condition	Consistency / Relative Density	Hand Penetrometer UCS (kPa)				Structure, Zoning, Origin, Additional Observations
CS				PP 5.75 m =260 kPa PP 5.85 m =340 kPa PP 5.95 m =520 kPa PP 6.05 m =380 kPa PP 6.15 m =300 kPa		25.6	6		SM	Silty SAND: fine grained, grey; silt low plasticity. (continued)	W					5.75: Possibly Residual or Extremely Weathered Granite	
									SP	Gravelly SAND: fine to coarse grained, grey; gravel fine to coarse grained.	W						
									CL	(RS/XW GRANITE) Sandy CLAY trace gravel: low plasticity, grey; sand fine to medium grained; gravel medium grained.							
				D 7.20-8.00 m		24.6	7				VSt to H						
						23.6	8			Varies from Sandy CLAY to Clayey SAND.	w > PL						
				PP 8.80 m =380 kPa PP 8.95 m =550 kPa PP 9.00 m >600 kPa		22.6	9				H						
Method		Penetration		Water		Samples and Tests		Moisture Condition		Consistency/Relative Density							
AD/T - Auger drilling TC bit AD/V - Auger drilling V'bit WB -Washbore SPT -Standard penetration test PT - Push tube AS - Auger screwing CS - Continuous sampling (DT22) NDD - Non destructive drilling CC - Concrete coring HA - Hand Auger		No resistance Refusal		Inflow Partial Loss Complete Loss		U - Undisturbed Sample D - Disturbed Sample SPT - Standard Penetration Test ES - Environmental Sample TW - Thin Walled LB - Large Disturbed Sample		D - Dry M - Moist W - Wet		VS - Very soft S - Soft F - Firm St - Stiff VSt - Very stiff H - Hard VL - Very loose L - Loose MD - Medium dense D - Dense VD - Very dense Ce - Cemented C - Compact							
Logged in accordance with AS 1726:2017 Geotechnical site investigations																	

PSM 3.02.2 LIB - MOD FOR 5665 GLOB Log PSM AU NONCORE BH NZ AU PSM5665.GPJ <<DrawingFile>> 26/02/2025 22:40 10.03.00.09 Dagle Fence and Map Tool Lib: PSM 3.02.1 2018-03-06 Pj: PSM 3.02.1 2018-03-06

Method	Penetration	Water	Samples and Tests	Moisture Condition	Consistency/Relative Density
AD/T - Auger drilling TC bit AD/V - Auger drilling V bit WB - Washbore SPT - Standard penetration test PT - Push tube AS - Auger screwing CS - Continuous sampling (DT22) NDD - Non destructive drilling CC - Concrete coring HA - Hand Auger	No resistance Refusal	▽ Inflow △ Partial Loss ▲ Complete Loss	U - Undisturbed Sample D - Disturbed Sample SPT - Standard Penetration Test ES - Environmental Sample TW - Thin Walled LB - Large Disturbed Sample	D - Dry M - Moist W - Wet	VS - Very soft S - Soft F - Firm St - Stiff Vst - Very stiff H - Hard VL - Very loose L - Loose MD - Medium dense D - Dense VD - Very dense Ce - Cemented C - Compact

Logged in accordance with AS 1726:2017 Geotechnical site investigations

BH01

Geotechnical Log

Project No.: PSM5665

Log PSM AU NONCORE BH NZ AU PSM5665.GPJ 26/03/2025 22:40 10.03.00.09 Datgel Fence and Map Tool Lib: PSM 3.02.1 2019-03-06 Proj: PSM 3.02.1 2019-03-06



Borehole ID

BH01

Page 4 of 7

Geotechnical Log

Project No.: PSM5665

Client:	Mornington Peninsula Shire Council	Commenced:	19/02/2025
Project Name:	McCrae Landslide Geotechnical Investigation	Completed:	20/02/2025
Hole Location:	10-12 View Point Road Driveway	Logged By:	JW/LL
Hole Position:	319565.8 m E 5753704.4 m N GDA2020 / MGA Zone 55	Checked By:	TN
Drill Model and Mounting:	Geoprobe 7822 DT	Inclination:	-90°
Hole Diameter:	CS - 57 mm, HQ3 - 96 mm	RL Surface:	31.57 m
		Bearing:	-
		Datum:	AHD
		Operator:	SW Drilling

Drilling Information							Soil Description							Observations		
Method	Penetration	Support	Water	Samples Tests Remarks	Recovery	RL (m)	Depth (m)	Graphic Log	Classification Symbol	Material Description SOIL NAME: Plasticity, behaviour or particle characteristics of primary component, colour, secondary components, additional observations	Moisture Condition	Consistency / Relative Density	Hand Penetrometer UCS (kPa) 100 200 300 400 500	Structure, Zoning, Origin, Additional Observations		
HQ3									CL		M	H				
						15.6	16		SC	(XW GRANITE) Clayey SAND: fine to coarse grained, yellow mottled grey; clay low plasticity. MW granite inclusions at 15.3 - 15.5 m. Becomes brown at 15.7 m.	M					
						14.6	17		SW-SC	(XW GRANITE) SAND with clay trace gravel: fine to coarse grained, brown grey; clay low plasticity; gravel fine grained.	M					
										NO CORE: 17.0 - 17.1 m						
						13.6	18		SW-SC	(XW GRANITE) SAND with clay trace gravel: fine to coarse grained, brown grey; clay low plasticity; gravel fine grained. FELDSPAR inclusions at 17.25 m.	M					
									SW-SC	(XW GRANITE) SAND with clay trace gravel: fine to coarse grained, brown; clay low plasticity; gravel fine grained.	M					
					PP 18.45 m =400 kPa PP 18.55 m =300 kPa PP 18.65 m =300 kPa PP 18.75 m =420 kPa PP 18.85 m =400 kPa		12.6	19		CL	(XW GRANITE) Sandy CLAY trace gravel: low plasticity, grey; sand fine grained; gravel fine grained.	w > PL	H	x x x x		
					PP 19.60 m =500 kPa PP 19.70 m =700 kPa PP 19.80 m				CL	(XW GRANITE) CLAY trace sand: low plasticity, grey; sand fine grained.	w > PL	H	x x x x			

Method

AD/T - Auger drilling TC bit
AD/V - Auger drilling V bit
WB - Washbore
SPT - Standard penetration test
PT - Push tube
AS - Auger screwing
CS - Continuous sampling (DT22)
NDD - Non destructive drilling
CC - Concrete coring
HA - Hand Auger

Penetration

No resistance
 Refusal

Water

Inflow
 Partial Loss
 Complete Loss

Samples and Tests

U - Undisturbed Sample
D - Disturbed Sample
SPT - Standard Penetration Test
ES - Environmental Sample
TW - Thin Walled
LB - Large Disturbed Sample

Moisture Condition

D - Dry
M - Moist
W - Wet

Consistency/Relative Density

VS - Very soft
S - Soft
F - Firm
St - Stiff
VSt - Very stiff
H - Hard
VL - Very loose
L - Loose
MD - Medium dense
D - Dense
VD - Very dense
Ce - Cemented
C - Compact



Borehole ID

BH01

Page 5 of 7

Geotechnical Log


Project No.: PSM5665

Client:	Mornington Peninsula Shire Council	Commenced:	19/02/2025
Project Name:	McCrae Landslide Geotechnical Investigation	Completed:	20/02/2025
Hole Location:	10-12 View Point Road Driveway	Logged By:	JW/LL
Hole Position:	319565.8 m E 5753704.4 m N GDA2020 / MGA Zone 55	Checked By:	TN
Drill Model and Mounting:	Geoprobe 7822 DT	Inclination:	-90°
Hole Diameter:	CS - 57 mm, HQ3 - 96 mm	RL Surface:	31.57 m
		Bearing:	-
		Datum:	AHD
		Operator:	SW Drilling

Drilling Information							Soil Description							Observations			
Method	Penetration	Support	Water	Samples Tests Remarks	Recovery	RL (m)	Depth (m)	Graphic Log	Classification Symbol	Material Description SOIL NAME: Plasticity, behaviour or particle characteristics of primary component, colour, secondary components, additional observations	Moisture Condition	Consistency / Relative Density	Hand Penetrometer UCS (kPa)				Structure, Zoning, Origin, Additional Observations
HQ3		N	NOT ENCOUNTERED	>700 kPa PP 19.95 m =380 - 500 kPa <													

Method

AD/T - Auger drilling TC bit
AD/V - Auger drilling V bit
WB - Washbore
SPT - Standard penetration test
PT - Push tube
AS - Auger screwing
CS - Continuous sampling (DT22)
NDD - Non destructive drilling
CC - Concrete coring
HA - Hand Auger

Penetration**Water**

▽ Inflow
△ Partial Loss
▲ Complete Loss

Samples and Tests

U - Undisturbed Sample
D - Disturbed Sample
SPT - Standard Penetration Test
ES - Environmental Sample
TW - Thin Walled
LB - Large Disturbed Sample

Moisture Condition

D - Dry
M - Moist
W - Wet

Consistency/Relative Density

VS - Very soft
S - Soft
F - Firm
St - Stiff
VSt - Very stiff
H - Hard
VL - Very loose
L - Loose
MD - Medium dense
D - Dense
VD - Very dense
Ce - Cemented
C - Compact

BH01

Page 6 of 7

Project No.: PSM5665

SM 3.02.2 UIR - MOD FOR 5665 GIB Log PSM AU NONCORE BH NZ AU 10.03.00.09 Datagel Fence and Map Tool Lib: PSM 3.02.1 2019-03-06 Pri: PSM 3.02.1 2019-03-06



Borehole ID

BH01

Page 7 of 7

Geotechnical Log

Project No.: PSM5665

Client: Mornington Peninsula Shire Council		Commenced: 19/02/2025	
Project Name: McCrae Landslide Geotechnical Investigation		Completed: 20/02/2025	
Hole Location: 10-12 View Point Road Driveway		Logged By: JW/LL	
Hole Position: 319565.8 m E 5753704.4 m N GDA2020 / MGA Zone 55		Checked By: TN	
Drill Model and Mounting: Geoprobe 7822 DT		Inclination: -90°	
Hole Diameter: CS - 57 mm, HQ3 - 96 mm		RL Surface: 31.57 m	
		Bearing: -	
		Datum: AHD	
		Operator: SW Drilling	

Drilling Information						Soil Description						Observations		
Method	Penetration	Support	Water	Samples Tests Remarks	Recovery	RL (m)	Depth (m)	Graphic Log	Classification Symbol	Material Description SOIL NAME: Plasticity, behaviour or particle characteristics of primary component, colour, secondary components, additional observations	Moisture Condition	Consistency / Relative Density	Hand Penetrometer UCS (kPa)	Structure, Zoning, Origin, Additional Observations
													100 200 300 400 500	
										Hole Terminated at 30.00 m Target depth. Nested VWP's grouted and sand packed in place at various depths.				
							31							
							32							
							33							
							34							

Method AD/T - Auger drilling TC bit AD/V - Auger drilling V bit WB - Washbore SPT - Standard penetration test PT - Push tube AS - Auger screwing CS - Continuous sampling (DT22) NDD - Non destructive drilling CC - Concrete coring HA - Hand Auger	Penetration No resistance Refusal	Water Inflow Partial Loss Complete Loss	Samples and Tests U - Undisturbed Sample D - Disturbed Sample SPT - Standard Penetration Test ES - Environmental Sample TW - Thin Walled LB - Large Disturbed Sample	Moisture Condition D - Dry M - Moist W - Wet	Consistency/Relative Density VS - Very soft S - Soft F - Firm St - Stiff VSt - Very stiff H - Hard VL - Very loose L - Loose MD - Medium dense D - Dense VD - Very dense Ce - Cemented C - Compact
---	--	---	---	--	--



PointID : BH01 Depth Range: 0.00 - 4.00 m



TITLE

Mornington Peninsula Shire Council
McCrae Landslide Geotechnical Investigation
Core Photo - BH01: 0.00 m - 4.00 m

DRAWN

BTA

DATE

6/03/2025

CHECKED

TN

DATE

6/03/2025

SCALE

Not To Scale

A4

PROJECT No

PSM5665

FIGURE No

1/8



PointID : BH01 Depth Range: 4.00 - 8.00 m



TITLE

Mornington Peninsula Shire Council
 McCrae Landslide Geotechnical Investigation
 Core Photo - BH01: 4.00 m - 8.00 m

DRAWN	BTA	DATE	6/03/2025
CHECKED	TN	DATE	6/03/2025
SCALE	Not To Scale		A4
PROJECT No	PSM5665	FIGURE No	2/8

PSM 3.02.2 LIB - MOD FOR 5665.GLB GrfcTbl DG PHOTO CORE PHOTO 1 PER PAGE A4L PSM5665.GPJ <<DrawingFile>> 06/03/2025 14:31 10.03.00.09 Datgel Fence and Map Tool | Lib: PSM 3.02.1 2019-03-06 Pj: PSM 3.02.1 2019-03-06



PointID : BH01 Depth Range: 8.00 - 12.00 m

	TITLE Mornington Peninsula Shire Council McCrae Landslide Geotechnical Investigation Core Photo - BH01: 8.00 m - 12.00 m	DRAWN BTA	DATE 6/03/2025
		CHECKED TN	DATE 6/03/2025
		SCALE Not To Scale	A4
		PROJECT No PSM5665	FIGURE No 3/8

PSM 3.02.2 LIB - MOD FOR 5665.GLB GrfcTbl DG PHOTO CORE PHOTO 1 PER PAGE A4L PSM5665.GPJ <<DrawingFile>> 06/03/2025 14:31 10.03.00.09 Datgel Fence and Map Tool | Lib: PSM 3.02.1 2019-03-06 Pj: PSM 3.02.1 2019-03-06



PointID : BH01 Depth Range: 12.00 - 16.00 m

	TITLE Mornington Peninsula Shire Council McCrae Landslide Geotechnical Investigation Core Photo - BH01: 12.00 m - 16.00 m	DRAWN BTA	DATE 6/03/2025
		CHECKED TN	DATE 6/03/2025
		SCALE Not To Scale	A4
		PROJECT No PSM5665	FIGURE No 4/8



PointID : BH01 Depth Range: 16.00 - 20.00 m



TITLE

Mornington Peninsula Shire Council
McCrae Landslide Geotechnical Investigation
Core Photo - BH01: 16.00 m - 20.00 m

DRAWN

BTA

DATE

6/03/2025

CHECKED

TN

DATE

6/03/2025

SCALE

Not To Scale

A4

PROJECT No

PSM5665

FIGURE No

5/8



PointID : BH01 Depth Range: 20.00 - 24.00 m


	TITLE Mornington Peninsula Shire Council McCrae Landslide Geotechnical Investigation Core Photo - BH01: 20.00 m - 24.00 m		DRAWN BTA	DATE 6/03/2025
			CHECKED TN	DATE 6/03/2025
			SCALE Not To Scale	A4
			PROJECT No PSM5665	FIGURE No 6/8

PSM 3.02.2 LIB - MOD FOR 5665.GLB GrfcTbl DG PHOTO CORE PHOTO 1 PER PAGE A4L PSM5665.GPJ <<DrawingFile>> 06/03/2025 14:31 10.03.00.09 Datgel Fence and Map Tool | Lib: PSM 3.02.1 2019-03-06 Proj: PSM 3.02.1 2019-03-06



PointID : BH01 Depth Range: 24.00 - 28.00 m

	TITLE Mornington Peninsula Shire Council McCrae Landslide Geotechnical Investigation Core Photo - BH01: 24.00 m - 28.00 m		DRAWN BTA	DATE 6/03/2025
			CHECKED TN	DATE 6/03/2025
			SCALE Not To Scale	A4
			PROJECT No PSM5665	FIGURE No 7/8



PointID : BH01 Depth Range: 28.00 - 30.00 m



TITLE

Mornington Peninsula Shire Council
McCrae Landslide Geotechnical Investigation
Core Photo - BH01: 28.00 m - 30.00 m

DRAWN

BTA

DATE

6/03/2025

CHECKED

TN

DATE

6/03/2025

SCALE

Not To Scale

A4

PROJECT No

PSM5665

FIGURE No

8/8



Borehole ID

BH01A

Page 1 of 2

Geotechnical Log

Project No.: PSM5665

Client: Mornington Peninsula Shire Council		Commenced: 25/02/2025	
Project Name: McCrae Landslide Geotechnical Investigation		Completed: 25/02/2025	
Hole Location: 10-12 View Point Road Driveway		Logged By: LL	
Hole Position: 319565.7 m E 5753703.3 m N GDA2020 / MGA Zone 55		Checked By: TN	
Drill Model and Mounting: Geoprobe 7822 DT		Inclination: -90°	RL Surface: 31.69 m
Hole Diameter: 150 mm		Bearing: -	Datum: AHD Operator: SW Drilling

Drilling Information						Soil Description						Observations		
Method	Penetration	Support	Water	Samples Tests Remarks	Recovery	RL (m)	Depth (m)	Graphic Log	Classification Symbol	Material Description SOIL NAME: Plasticity, behaviour or particle characteristics of primary component, colour, secondary components, additional observations	Moisture Condition	Consistency / Relative Density	Hand Penetrometer UCS (kPa)	Structure, Zoning, Origin, Additional Observations
AD/V			N			30.7	1			Refer to BH01 for Lithology.				
						29.7	2							
						28.7	3							
						27.7	4							

Method
AD/T - Auger drilling TC bit
AD/V - Auger drilling V bit
WB - Washbore
SPT - Standard penetration test
PT - Push tube
AS - Auger screwing
CS - Continuous sampling (DT22)
NDD - Non destructive drilling
CC - Concrete coring
HA - Hand Auger

Penetration
 No resistance
 Refusal

Water
 Inflow
 Partial Loss
 Complete Loss

Samples and Tests
U - Undisturbed Sample
D - Disturbed Sample
SPT - Standard Penetration Test
ES - Environmental Sample
TW - Thin Walled
LB - Large Disturbed Sample

Moisture Condition
D - Dry
M - Moist
W - Wet

Consistency/Relative Density
VS - Very soft
S - Soft
F - Firm
St - Stiff
VSt - Very stiff
H - Hard
VL - Very loose
L - Loose
MD - Medium dense
D - Dense
VD - Very dense
Ce - Cemented
C - Compact



Borehole ID

BH01A

Page 2 of 2

Geotechnical Log

Project No.: PSM5665

Client: Mornington Peninsula Shire Council		Commenced: 25/02/2025	
Project Name: McCrae Landslide Geotechnical Investigation		Completed: 25/02/2025	
Hole Location: 10-12 View Point Road Driveway		Logged By: LL	
Hole Position: 319565.7 m E 5753703.3 m N GDA2020 / MGA Zone 55		Checked By: TN	
Drill Model and Mounting: Geoprobe 7822 DT		Inclination: -90°	
Hole Diameter: 150 mm		RL Surface: 31.69 m	
		Bearing: -	
		Datum: AHD	
		Operator: SW Drilling	

Drilling Information						Soil Description						Observations		
Method	Penetration	Support	Water	Samples Tests Remarks	Recovery	RL (m)	Depth (m)	Graphic Log	Classification Symbol	Material Description SOIL NAME: Plasticity, behaviour or particle characteristics of primary component, colour, secondary components, additional observations	Moisture Condition	Consistency / Relative Density	Hand Penetrometer UCS (kPa)	Structure, Zoning, Origin, Additional Observations
													100 200 300 400 500	
AD/V		N				25.7	6							
						24.7	7			Hole Terminated at 6.00 m Target depth. Standpipe Installed, and sand, gravel and bentonite packed in place.				
						23.7	8							
						22.7	9							

Method AD/T - Auger drilling TC bit AD/V - Auger drilling V bit WB - Washbore SPT - Standard penetration test PT - Push tube AS - Auger screwing CS - Continuous sampling (DT22) NDD - Non destructive drilling CC - Concrete coring HA - Hand Auger	Penetration No resistance Refusal	Water Inflow Partial Loss Complete Loss	Samples and Tests U - Undisturbed Sample D - Disturbed Sample SPT - Standard Penetration Test ES - Environmental Sample TW - Thin Walled LB - Large Disturbed Sample	Moisture Condition D - Dry M - Moist W - Wet	Consistency/Relative Density VS - Very soft S - Soft F - Firm St - Stiff VSt - Very stiff H - Hard VL - Very loose L - Loose MD - Medium dense D - Dense VD - Very dense Ce - Cemented C - Compact
---	--	---	---	--	--



Borehole ID

BH02

Page 1 of 6

Geotechnical Log

Project No.: PSM5665

Client: Mornington Peninsula Shire Council		Commenced: 20/02/2025	
Project Name: McCrae Landslide Geotechnical Investigation		Completed: 21/02/2025	
Hole Location: 5 View Point Road Verge		Logged By: JW/LL	
Hole Position: 319562.3 m E 5753681.9 m N GDA2020 / MGA Zone 55		Checked By: TN	
Drill Model and Mounting: Geoprobe 7822 DT		Inclination: -90°	
Hole Diameter: CS - 57 mm, HQ3 - 96 mm		RL Surface: 31.87 m	
		Bearing: -	
		Datum: AHD	
		Operator: SW Drilling	

Drilling Information				Soil Description				Observations						
Method	Penetration	Support	Water	Samples Tests Remarks	Recovery	RL (m)	Depth (m)	Graphic Log	Classification Symbol	Material Description	Moisture Condition	Consistency / Relative Density	Hand Penetrometer UCS (kPa)	Structure, Zoning, Origin, Additional Observations
CS	N	Not Encountered	N	D 1.60-2.60 m	30.9	1	30.9	OL SM		TOPSOIL: Sandy SILT: low plasticity, brown; sand fine.	w < PL	F	100	0.00: Topsoil
										FILL: Silty SAND: fine grained, grey; silt low plasticity.				
										No recovery.				
CS	N	Not Encountered	N	D 4.20-5.00 m	27.9	4	27.9	CL		Sandy CLAY trace gravel: low plasticity, grey; sand fine to coarse grained; gravel fine grained.	w < PL	H		1.50: Possibly Colluvium
SPT	N	Not Encountered	N	SPT 2.80-2.87 m 25/70mm N=R SPT01 2.80m 25 N=25 70/150mm SPT02 3.50-3.95m 9,15,16 N=31 400/450mm	28.9	3	28.9	SC		Clayey SAND trace gravel: fine to coarse grained, grey; clay low to medium plasticity; gravel subangular, fine to medium grained.		D to VD		

Method AD/T - Auger drilling TC bit AD/V - Auger drilling V bit WB - Washbore SPT - Standard penetration test PT - Push tube AS - Auger screwing CS - Continuous sampling (DT22) NDD - Non destructive drilling CC - Concrete coring HA - Hand Auger	Penetration No resistance Refusal	Water Inflow Partial Loss Complete Loss	Samples and Tests U - Undisturbed Sample D - Disturbed Sample SPT - Standard Penetration Test ES - Environmental Sample TW - Thin Walled LB - Large Disturbed Sample	Moisture Condition D - Dry M - Moist W - Wet	Consistency/Relative Density VS - Very soft S - Soft F - Firm St - Stiff VSt - Very stiff H - Hard VL - Very loose L - Loose MD - Medium dense D - Dense VD - Very dense Ce - Cemented C - Compact
---	--	---	---	--	--



Borehole ID

BH02

Page 2 of 6

Geotechnical Log

Project No.: PSM5665

Client: Mornington Peninsula Shire Council			Commenced: 20/02/2025																			
Project Name: McCrae Landslide Geotechnical Investigation			Completed: 21/02/2025																			
Hole Location: 5 View Point Road Verge			Logged By: JW/LL																			
Hole Position: 319562.3 m E 5753681.9 m N GDA2020 / MGA Zone 55			Checked By: TN																			
Drill Model and Mounting: Geoprobe 7822 DT			Inclination: -90°		RL Surface: 31.87 m																	
Hole Diameter: CS - 57 mm, HQ3 - 96 mm			Bearing: -		Datum: AHD Operator: SW Drilling																	
Drilling Information							Soil Description							Observations								
Method	Penetration	Support	Water	Samples Tests Remarks	Recovery	RL (m)	Depth (m)	Graphic Log	Classification Symbol	Material Description	Moisture Condition	Consistency / Relative Density	Hand Penetrometer UCS (kPa)				Structure, Zoning, Origin, Additional Observations					
CS		N	Not Encountered	PP 6.30 m >450 kPa D 6.70-7.50 m PP 6.70 m >450 kPa PP 8.10 m >500 kPa PP 9.10 m >500 kPa		25.9	6		CL	Sandy CLAY trace gravel: low plasticity, grey; sand fine to coarse grained; gravel fine grained. (continued)	w < PL	H				5.40: Possibly Residual Soil or Extremely Weathered Granite						
									CL-CI	(RS/XW GRANITE) Sandy CLAY: low to medium plasticity, mottled grey brown; sand fine to coarse grained.												
										As above but no sand at 6.5 m.	w > PL	H		x								
										As above but with pale grey, fine grained sand at 7.1 m.				x								
									CL	(RS/XW GRANITE) Sandy CLAY: low plasticity, red brown; sand fine grained.	w > PL	H		x								
CS		N	Not Encountered			23.9	8		CL	(RS/XW GRANITE) CLAY trace sand: low plasticity, grey brown; sand fine grained.						x						
CS		N	Not Encountered			22.9	9				w > PL	H				x						
							Method															
							Penetration															
							Water															
							Samples and Tests															
							Moisture Condition															
							Consistency/Relative Density															
AD/T - Auger drilling TC bit																						
AD/V - Auger drilling V bit																						
WB - Washbore																						
SPT - Standard penetration test																						
PT - Push tube																						
AS - Auger screwing																						
CS - Continuous sampling (DT22)																						
NDD - Non destructive drilling																						
CC - Concrete coring																						
HA - Hand Auger																						
Legend																						
No resistance																						
Refusal																						
Inflow																						
Partial Loss																						
Complete Loss																						
U - Undisturbed Sample																						
D - Disturbed Sample																						
SPT - Standard Penetration Test																						
ES - Environmental Sample																						
TW - Thin Walled																						
LB - Large Disturbed Sample																						
D - Dry																						
M - Moist																						
W - Wet																						
VS - Very soft																						
S - Soft																						
F - Firm																						
St - Stiff																						
VSt - Very stiff																						
H - Hard																						
VL - Very loose																						
L - Loose																						
MD - Medium dense																						
D - Dense																						
VD - Very dense																						
Ce - Cemented																						
C - Compact																						



Borehole ID

BH02

Page 3 of 6

Geotechnical Log

Project No.: PSM5665

Client: Mornington Peninsula Shire Council				Commenced: 20/02/2025												
Project Name: McCrae Landslide Geotechnical Investigation				Completed: 21/02/2025												
Hole Location: 5 View Point Road Verge				Logged By: JW/LL												
Hole Position: 319562.3 m E 5753681.9 m N GDA2020 / MGA Zone 55				Checked By: TN												
Drill Model and Mounting: Geoprobe 7822 DT				Inclination: -90°		RL Surface: 31.87 m										
Hole Diameter: CS - 57 mm, HQ3 - 96 mm				Bearing: -		Datum: AHD Operator: SW Drilling										
Drilling Information				Soil Description						Observations						
Method	Penetration	Support	Water	Samples Tests Remarks	Recovery	RL (m)	Depth (m)	Graphic Log	Classification Symbol	Material Description SOIL NAME: Plasticity, behaviour or particle characteristics of primary component, colour, secondary components, additional observations	Moisture Condition	Consistency / Relative Density	Hand Penetrometer UCS (kPa)	Structure, Zoning, Origin, Additional Observations		
CS		N	Not Encountered	PP 10.10 m >500 kPa					CL	(RS/XW GRANITE) CLAY trace sand trace gravel: low plasticity, brown; sand fine grained; gravel fine grained.	w > PL	H		11.80: Extremely Weathered Granite		
				PP 11.10 m >500 kPa		20.9	11									
										No recovery.						
						19.9	12		CL	(XW GRANITE) Sandy CLAY: low plasticity, grey brown; sand fine grained.	w > PL	H				
									CL	(XW GRANITE) Sandy CLAY trace gravel: low plasticity, brown; sand fine to coarse grained; gravel fine to medium grained. Gravels becomes angular, coarse grained at 12.15 m.	w > PL	H				
						18.9	13									
									CL	(XW GRANITE) Sandy CLAY trace gravel trace cobbles: low plasticity, brown; sand fine to medium grained; gravel angular, fine to medium grained; cobbles granite, coarse grained, red brown, angular, high strength.	w > PL	VSt to H				
						17.9	14		SP	(XW GRANITE) Gravelly SAND: medium to coarse grained, yellow brown; gravel fine to medium grained.	M					
									SC	(XW GRANITE) Clayey SAND: fine to coarse grained, brown; clay low plasticity.	M					
Method AD/T - Auger drilling TC bit AD/V - Auger drilling V bit WB - Washbore SPT - Standard penetration test PT - Push tube AS - Auger screwing CS - Continuous sampling (DT22) NDD - Non destructive drilling CC - Concrete coring HA - Hand Auger Penetration  No resistance  Refusal Water  Inflow  Partial Loss  Complete Loss Samples and Tests U - Undisturbed Sample D - Disturbed Sample SPT - Standard Penetration Test ES - Environmental Sample TW - Thin Walled LB - Large Disturbed Sample Moisture Condition D - Dry M - Moist W - Wet Consistency/Relative Density VS - Very soft S - Soft F - Firm St - Stiff VSt - Very stiff H - Hard VL - Very loose L - Loose MD - Medium dense D - Dense VD - Very dense Ce - Cemented C - Compact																

Logged in accordance with AS 1726:2017 Geotechnical site investigations

BH02

Page 4 of 6

Project No.: PSM5665

SM 3.02.2 UIR - MOD FOR 5665 GIB Log PSM AU NONCORE BH NZ AU 10.03.00.09 Datagel Fence and Map Tool Lib: PSM 3.02.1 2019-03-06 Pri: PSM 3.02.1 2019-03-06



Borehole ID

BH02

Page 5 of 6

Geotechnical Log

Project No.: PSM5665

Client: Mornington Peninsula Shire Council		Commenced: 20/02/2025	
Project Name: McCrae Landslide Geotechnical Investigation		Completed: 21/02/2025	
Hole Location: 5 View Point Road Verge		Logged By: JW/LL	
Hole Position: 319562.3 m E 5753681.9 m N GDA2020 / MGA Zone 55		Checked By: TN	
Drill Model and Mounting: Geoprobe 7822 DT		Inclination: -90°	
Hole Diameter: CS - 57 mm, HQ3 - 96 mm		RL Surface: 31.87 m	
		Bearing: -	
		Datum: AHD	
		Operator: SW Drilling	

Drilling Information				Soil Description				Observations							
Method	Penetration	Support	Water	Samples Tests Remarks	Recovery	RL (m)	Depth (m)	Graphic Log	Classification Symbol	Material Description	Moisture Condition	Consistency / Relative Density	Hand Penetrometer UCS (kPa)	Structure, Zoning, Origin, Additional Observations	
HQ3		N	Not Encountered	PP 21.10 m = 300 kPa Is(50): 3.12 MPa C 21.30-21.40 m		10.9	21			NO CORE: 20.00 - 21.15 m				21.30: PLT carried out on an granite cobble clast	
						9.9	22		CL	(XW GRANITE) Sandy CLAY trace gravel: low plasticity, grey; sand fine to coarse grained; gravel fine to medium grained, granite source.	w > PL	VSt			
									SC	(XW GRANITE) Clayey SAND with gravel: fine to coarse grained, grey brown; clay low plasticity; gravel fine to medium grained.					
						8.9	23								
									SP-SC	(XW GRANITE) Gravelly SAND with clay: medium to coarse grained, grey brown; gravel subangular to angular, fine to medium grained; clay low plasticity.					
						7.9	24			Gravel 40mm diameter, angular, high strength. Becomes trace Clay at 24.5 m.					

Method AD/T - Auger drilling TC bit AD/V - Auger drilling V bit WB - Washbore SPT - Standard penetration test PT - Push tube AS - Auger screwing CS - Continuous sampling (DT22) NDD - Non destructive drilling CC - Concrete coring HA - Hand Auger	Penetration No resistance Refusal	Water Inflow Partial Loss Complete Loss	Samples and Tests U - Undisturbed Sample D - Disturbed Sample SPT - Standard Penetration Test ES - Environmental Sample TW - Thin Walled LB - Large Disturbed Sample	Moisture Condition D - Dry M - Moist W - Wet	Consistency/Relative Density VS - Very soft S - Soft F - Firm St - Stiff VSt - Very stiff H - Hard VL - Very loose L - Loose MD - Medium dense D - Dense VD - Very dense Ce - Cemented C - Compact
---	--	---	---	--	--



Borehole ID


BH02

Page 6 of 6

Geotechnical Log

Project No.: PSM5665

Client:		Mornington Peninsula Shire Council				Commenced:		20/02/2025																																																																
Project Name:		McCrae Landslide Geotechnical Investigation				Completed:		21/02/2025																																																																
Hole Location:		5 View Point Road Verge				Logged By:		JW/LL																																																																
Hole Position:		319562.3 m E 5753681.9 m N GDA2020 / MGA Zone 55				Checked By:		TN																																																																
Drill Model and Mounting:		Geoprobe 7822 DT		Inclination:		-90°		RL Surface:		31.87 m																																																														
Hole Diameter:		CS - 57 mm, HQ3 - 96 mm		Bearing:		-		Datum:		AHD Operator: SW Drilling																																																														
Drilling Information							Soil Description						Observations																																																											
Method	Penetration	Support	Water	Samples Tests Remarks	Recovery	RL (m)	Depth (m)	Graphic Log	Classification Symbol	Material Description SOIL NAME: Plasticity, behaviour or particle characteristics of primary component, colour, secondary components, additional observations	Moisture Condition	Consistency / Relative Density	Hand Penetrometer UCS (kPa)				Structure, Zoning, Origin, Additional Observations																																																							
													100	200	300	400		500																																																						
HQ3			N	Not Encountered					SP-SC	(XW GRANITE) CLAY: low plasticity, mottled grey, brown and white.	M	H																																																												
																					CL	(XW GRANITE) CLAY trace gravel trace sand: low plasticity, grey; gravel fine to medium grained; sand fine grained.	w > PL	VSt	x																																															
																										CL	(XW GRANITE) Sandy CLAY: low plasticity, grey; sand fine to coarse grained.	w > PL	St to VSt	x																																										
																															NO CORE: 27.50 - 28.45 m																																									
																																			CL	(XW GRANITE) Sandy CLAY with gravel trace cobbles: low plasticity, brown; sand coarse grained; gravel fine grained; cobbles isolated, angular, high strength, slightly weathered granite, >70 mm diameter.	w > PL	St	x																																	
																																								NO CORE: 29.00 - 29.37 m																																
																																												SC	(XW GRANITE) Clayey SAND with gravel: medium to coarse grained, brown; clay low plasticity; gravel fine grained.	M		x																								
																																																	Hole Terminated at 30.00 m Target depth. Nested VWPs grouted in place at various depths.																							
																																																					PP 25.90 m =300 kPa	5.9	26																	
																																																									PP 26.40 m =310 kPa															
																																																													PP 26.80 m =320 kPa	4.9	27									



PointID : BH02 Depth Range: 0.00 - 4.00 m



TITLE

Mornington Peninsula Shire Council
McCrae Landslide Geotechnical Investigation
Core Photo - BH02: 0.00 m - 4.00 m

DRAWN

BTA

DATE

6/03/2025

CHECKED

TN

DATE

6/03/2025

SCALE

Not To Scale

A4

PROJECT No

PSM5665

FIGURE No

1/8



PointID : BH02 Depth Range: 4.00 - 8.00 m

	TITLE Mornington Peninsula Shire Council McCrae Landslide Geotechnical Investigation Core Photo - BH02: 4.00 m - 8.00 m	DRAWN BTA	DATE 6/03/2025
		CHECKED TN	DATE 6/03/2025
		SCALE Not To Scale	A4
		PROJECT No PSM5665	FIGURE No 2/8



PointID : BH02 Depth Range: 8.00 - 12.00 m



TITLE

Mornington Peninsula Shire Council
McCrae Landslide Geotechnical Investigation
Core Photo - BH02: 8.00 m - 12.00 m

DRAWN

BTA

DATE

6/03/2025

CHECKED

TN

DATE

6/03/2025

SCALE

Not To Scale

A4

PROJECT No

PSM5665

FIGURE No

3/8



PointID : BH02 Depth Range: 12.00 - 16.00 m

	TITLE Mornington Peninsula Shire Council McCrae Landslide Geotechnical Investigation Core Photo - BH02: 12.00 m - 16.00 m	DRAWN BTA	DATE 6/03/2025
		CHECKED TN	DATE 6/03/2025
		SCALE Not To Scale	A4
		PROJECT No PSM5665	FIGURE No 4/8



PointID : BH02 Depth Range: 16.00 - 20.00 m



TITLE

Mornington Peninsula Shire Council
McCrae Landslide Geotechnical Investigation
Core Photo - BH02: 16.00 m - 20.00 m

DRAWN

BTA

DATE

6/03/2025

CHECKED

TN

DATE

6/03/2025

SCALE

Not To Scale


A4

PROJECT No

PSM5665

FIGURE No

5/8




PointID : BH02 Depth Range: 20.00 - 24.00 m

	TITLE Mornington Peninsula Shire Council McCrae Landslide Geotechnical Investigation Core Photo - BH02: 20.00 m - 24.00 m	DRAWN BTA	DATE 6/03/2025
		CHECKED TN	DATE 6/03/2025
		SCALE Not To Scale	A4
		PROJECT No PSM5665	FIGURE No 6/8



PointID : BH02 Depth Range: 24.00 - 28.00 m

	TITLE Mornington Peninsula Shire Council McCrae Landslide Geotechnical Investigation Core Photo - BH02: 24.00 m - 28.00 m	DRAWN BTA	DATE 6/03/2025
		CHECKED TN	DATE 6/03/2025
		SCALE Not To Scale	A4
		PROJECT No PSM5665	FIGURE No 7/8



PointID : BH02 Depth Range: 28.00 - 30.00 m



TITLE

Mornington Peninsula Shire Council
 McCrae Landslide Geotechnical Investigation
 Core Photo - BH02: 28.00 m - 30.00 m

DRAWN

BTA

DATE

6/03/2025

CHECKED

TN

DATE

6/03/2025

SCALE

Not To Scale

A4

PROJECT No

PSM5665

FIGURE No

8/8



Borehole ID

BH03

Page 1 of 6

Geotechnical Log

Project No.: PSM5665

Client:	Mornington Peninsula Shire Council	Commenced:	17/02/2025
Project Name:	McCrae Landslide Geotechnical Investigation	Completed:	18/02/2025
Hole Location:	10-12 View Point Road Front Lawn	Logged By:	JW/LL
Hole Position:	319533.0 m E 5753715.6 m N GDA2020 / MGA Zone 55	Checked By:	TN
Drill Model and Mounting:	Geoprobe 7822 DT	Inclination:	-90°
Hole Diameter:	CS - 57 mm, HQ3 - 96 mm	RL Surface:	28.62 m
		Bearing:	-
		Datum:	AHD
		Operator:	SW Drilling

Drilling Information							Soil Description							Observations
Method	Penetration	Support	Water	Samples Tests Remarks	Recovery	RL (m)	Depth (m)	Graphic Log	Classification Symbol	Material Description SOIL NAME: Plasticity, behaviour or particle characteristics of primary component, colour, secondary components, additional observations	Moisture Condition	Consistency / Relative Density	Hand Penetrometer UCS (kPa)	Structure, Zoning, Origin, Additional Observations
CS			Water level observed at 2.5m bgl.	D 2.70-4.00 m		27.6	1		OL	TOPSOIL: Sandy SILT: low plasticity, brown; sand fine grained.	w < PL			0.00: Topsoil
									SP-SM	FILL: SAND with silt trace gravel: fine to medium grained, poorly graded, pale brown; gravel fine to medium grained, subangular gravel.	D		0.20: Possibly Fill 0.30: Rootlets observed down to 0.3 m	
										No recovery.				
									SP	SAND with gravel trace silt: fine to medium grained, poorly graded, pale brown; gravel fine to coarse grained, subangular gravel.	D		1.60: Possibly Colluvium	
									SW	SAND trace silt: fine to coarse grained, well graded, yellow brown; silt low plasticity.	M			
										No recovery.			2.50: Water level inferred based on soil becoming wet	
									SM	Silty SAND trace gravel: fine to coarse grained, well graded, yellow brown; silt low plasticity; gravel fine grained. Becomes dark brown with granite gravels at 3 m. Becomes yellow brown at 3.5 m.	M			
									SC	(RS/XW GRANITE) Clayey SAND: fine to coarse grained, well graded, sub-angular to angular, mottled brown and pale brown; clay low plasticity.	M		4.30: Probably Residual Soil or Extremely Weathered Granite	
										No recovery.				
												PP 4.70 m =420 kPa		24.6

Method

AD/T - Auger drilling TC bit
AD/V - Auger drilling V bit
WB - Washbore
SPT - Standard penetration test
PT - Push tube
AS - Auger screwing
CS - Continuous sampling (DT22)
NDD - Non destructive drilling
CC - Concrete coring
HA - Hand Auger

Penetration

No resistance
 Refusal

Water

Inflow
 Partial Loss
 Complete Loss

Samples and Tests

U - Undisturbed Sample
D - Disturbed Sample
SPT - Standard Penetration Test
ES - Environmental Sample
TW - Thin Walled
LB - Large Disturbed Sample

Moisture Condition

D - Dry
M - Moist
W - Wet

Consistency/Relative Density


VS - Very soft
S - Soft
F - Firm
St - Stiff
VSt - Very stiff
H - Hard
VL - Very loose
L - Loose
MD - Medium dense
D - Dense
VD - Very dense
Ce - Cemented
C - Compact

BH03

Geotechnical Log

Project No.: PSM5665

Drill Model and Mounting:	Geoprobe 7822 DT	Inclination:	-90°	RL Surface:	28.62 m	
Hole Diameter:	CS - 57 mm, HQ3 - 96 mm	Bearing:	-	Datum:	AHD	Operator: SW Drilling

Method	Penetration	Water	Samples and Tests	Moisture Condition	Consistency/Relative Density
AD/T - Auger drilling TC bit		▷ Inflow	D - Undisturbed Sample	D - Dry	VS - Very soft
AD/V - Auger drilling V bit		▽ Partial Loss	U - Disturbed Sample	M - Moist	S - Soft
WB - Washbore		◀ Complete Loss	SPT - Standard Penetration Test	W - Wet	F - Firm
SPT - Standard penetration test			ES - Environmental Sample		St - Stiff
PT - Push tube			TW - Thin Walled		VSt - Very stiff
AS - Auger screwing		LB - Large Disturbed Sample		H - Hard	
CS - Continuous sampling (DT22)				VL - Very loose	
NDD - Non destructive drilling				L - Loose	
CC - Concrete coring				MD - Medium dense	
HA - Hand Auger				D - Dense	
				VD - Very dense	
				Ce - Cemented	
				C - Compact	

BH03

Page 3 of 6

Project No.: PSM5665

SM 3.02.2 UIR - MOD FOR 5665 GIB Log PSM AU NONCORE BH NZ AU 10.03.00.09 Datrel Fence and Map Tool 11.b PSM 3.02.1 2019-03-06 Pri: PSM 3.02.1 2019-03-06
 <<DrawingFile>> 26/03/2025 22:40 PSM5665.GPJ



Borehole ID

BH03

Page 4 of 6

Geotechnical Log

Project No.: PSM5665

Client:	Mornington Peninsula Shire Council	Commenced:	17/02/2025				
Project Name:	McCrae Landslide Geotechnical Investigation	Completed:	18/02/2025				
Hole Location:	10-12 View Point Road Front Lawn	Logged By:	JW/LL				
Hole Position:	319533.0 m E 5753715.6 m N GDA2020 / MGA Zone 55	Checked By:	TN				
Drill Model and Mounting:	Geoprobe 7822 DT	Inclination:	-90°	RL Surface:	28.62 m		
Hole Diameter:	CS - 57 mm, HQ3 - 96 mm	Bearing:	-	Datum:	AHD	Operator:	SW Drilling

Drilling Information							Soil Description							Observations
Method	Penetration	Support	Water	Samples Tests Remarks	Recovery	RL (m)	Depth (m)	Graphic Log	Classification Symbol	Material Description SOIL NAME: Plasticity, behaviour or particle characteristics of primary component, colour, secondary components, additional observations	Moisture Condition	Consistency / Relative Density	Hand Penetrometer UCS (kPa) 100 200 300 400 500	Structure, Zoning, Origin, Additional Observations
HQ3				14.75-14.85 m					CL	(XW GRANITE) Sandy CLAY trace gravel: low plasticity, grey brown to brown; sand fine to coarse grained; no structure; gravel fine grained. (continued)	w > PL	VSt to H		
				Is(50): 0.02 MPa C 15.50-15.60 m		12.6	16		SW	(XW GRANITE) SAND trace clay: fine to coarse grained, yellow brown; clay low plasticity.	M			
				PP 16.40 m =320 kPa					CL	(XW GRANITE) Gravelly Sandy CLAY: low plasticity, grey; sand fine to coarse grained; gravel fine to medium grained subangular.	w > PL	VSt	x	
						11.6	17		SW-SC	(XW GRANITE) SAND with clay trace gravel: fine to coarse grained, brown; clay low plasticity; gravel fine grained, subangular gravel.	M			
										NO CORE: 17.45 - 19.0 m				
						10.6	18							
						9.6	19		SP	(XW GRANITE) SAND trace gravel: medium to coarse grained, brown; gravel fine grained, subangular gravel.	M		x	
				PP 19.30 m =280 kPa PP 19.40 m =400 kPa					CL	(XW GRANITE) Sandy CLAY: low plasticity, brown; sand fine grained.	w > PL	VSt	x	
											NO CORE: 19.50 - 20.15 m			

Method	Penetration	Water	Samples and Tests	Moisture Condition	Consistency/Relative Density
AD/T - Auger drilling TC bit AD/V - Auger drilling V bit WB - Washbore SPT - Standard penetration test PT - Push tube AS - Auger screwing CS - Continuous sampling (DT22) NDD - Non destructive drilling CC - Concrete coring HA - Hand Auger	No resistance Refusal	▽ Inflow ▽ Partial Loss ▲ Complete Loss	U - Undisturbed Sample D - Disturbed Sample SPT - Standard Penetration Test ES - Environmental Sample TW - Thin Walled LB - Large Disturbed Sample	D - Dry M - Moist W - Wet	VS - Very soft S - Soft F - Firm St - Stiff VSt - Very stiff H - Hard VL - Very loose L - Loose MD - Medium dense D - Dense VD - Very dense Ce - Cemented C - Compact

BH03

Page 5 of 6

Project No.: PSM5665

Drilling Information							Soil Description							Observations
Method	Penetration	Support	Water	Samples Tests Remarks	Recovery	RL (m)	Depth (m)	Graphic Log	Classification Symbol	Material Description SOIL NAME: Plasticity, behaviour or particle characteristics of primary component, colour, secondary components, additional observations	Moisture Condition	Consistency / Relative Density	Hand Penetrometer UCS (kPa)	Structure, Zoning, Origin, Additional Observations
										NO CORE: 19.50 - 20.15 m (continued)			100 200 300 400 500	
									CL	(XW GRANITE) Sandy CLAY: low plasticity, brown; sand fine grained.	w > PL	VSt		
				PP 20.88 m =600 - 900 kPa PP 21.00 m =450 - 500 kPa		7.6	21		CL-CI	(XW GRANITE) Sandy CLAY trace gravel: low to medium plasticity, grey; sand fine to coarse grained; gravel fine grained, subangular gravel.	w > PL	H		>>> xx
				Is(50): 0.02 MPa C 21.40-21.55 m										
						6.6	22			NO CORE: 22.00 - 22.65 m				
						5.6	23		SC	(XW GRANITE) Clayey SAND trace gravel: fine to coarse grained, grey; clay low to medium plasticity; gravel fine grained, subangular gravel.				
				Is(50): 0.02 MPa C 23.30-23.40 m							M			
						4.6	24							
									SM	(XW GRANITE) Silty SAND: fine grained, brown; silt low plasticity.	M			
									SW-SC	(XW GRANITE) SAND with clay trace gravel: fine to coarse grained, grey; clay low plasticity; gravel fine grained, subangular gravel.	M			

SM 3.02.2 LIB - MOD FOR 5665.GLB Log PSM AU NONCORE BH NZ AU PSM 5665.GPJ <<DrawingFile>> 26/03/2025 22:40 10.03.00.09 Datgel Fence and Map Tool | Lib: PSM 3.02.1 2019-03-06 Proj: PSM 3.02.1 2019-03-06

Logged in accordance

VD - Very dense
Ce - Cemented



Borehole ID

BH03

Page 6 of 6

Geotechnical Log

Project No.: PSM5665

Client:	Mornington Peninsula Shire Council	Commenced:	17/02/2025
Project Name:	McCrae Landslide Geotechnical Investigation	Completed:	18/02/2025
Hole Location:	10-12 View Point Road Front Lawn	Logged By:	JW/LL
Hole Position:	319533.0 m E 5753715.6 m N GDA2020 / MGA Zone 55	Checked By:	TN
Drill Model and Mounting:	Geoprobe 7822 DT	Inclination:	-90°
Hole Diameter:	CS - 57 mm, HQ3 - 96 mm	RL Surface:	28.62 m
		Bearing:	-
		Datum:	AHD
		Operator:	SW Drilling

Drilling Information							Soil Description							Observations
Method	Penetration	Support	Water	Samples Tests Remarks	Recovery	RL (m)	Depth (m)	Graphic Log	Classification Symbol	Material Description SOIL NAME: Plasticity, behaviour or particle characteristics of primary component, colour, secondary components, additional observations	Moisture Condition	Consistency / Relative Density	Hand Penetrometer UCS (kPa)	Structure, Zoning, Origin, Additional Observations
HQ3				PP 25.35 m =540 kPa PP 25.45 m =700 kPa PP 25.55 m =420 kPa PP 25.65 m =500 kPa		2.6	26		CL	NO CORE: 25.00 - 25.30 m	w > PL	H	100 200 300 400 500	x >>x x x 25.70: Possible Clay Seam, 700 mm thick
										(XW GRANITE) Sandy CLAY: low plasticity, grey; sand fine grained.				
										NO CORE: 26.50 - 26.95 m				
										(XW GRANITE) Gravelly Sandy CLAY: low plasticity, grey; sand fine to coarse grained; gravel fine grained; no structure.				
				PP 27.50 m =380 - 400 kPa		1.6	27		CL		w > PL	H	✱	
						0.6	28		SP-SC	(XW GRANITE) Gravelly SAND with clay: medium to coarse grained, grey; gravel fine grained, subangular gravel; clay low plasticity.	M			
						-0.4	29			Hole Terminated at 29.50 m Target depth. Nested VVPs grouted in place at various depths.				

PSM 3.02.2 LIB - MOD FOR 5665 GJB Log PSM AU NONCORE BH NZ AU PSM5665 GJPJ <<DrawingFile>> 26/02/2025 22:40 10.03.00.09 Dagle Fence and Map Tool [Lib: PSM 3.02.1 2018-03-06 Pij: PSM 3.02.1 2018-03-06]

Method

AD/T - Auger drilling TC bit
AD/V - Auger drilling V bit
WB - Washbore
SPT - Standard penetration test
PT - Push tube
AS - Auger screwing
CS - Continuous sampling (DT22)
NDD - Non destructive drilling
CC - Concrete coring
HA - Hand Auger

Penetration

No resistance
 Refusal

Water

▽ Inflow
△ Partial Loss
▲ Complete Loss

Samples and Tests

U - Undisturbed Sample
D - Disturbed Sample
SPT - Standard Penetration Test
ES - Environmental Sample
TW - Thin Walled
LB - Large Disturbed Sample

Moisture Condition


D - Dry
M - Moist
W - Wet

Consistency/Relative Density

VS - Very soft
S - Soft
F - Firm
St - Stiff
VSt - Very stiff
H - Hard
VL - Very loose
L - Loose
MD - Medium dense
D - Dense
VD - Very dense
Ce - Cemented
C - Compact

Logged in accordance with AS 1726:2017 Geotechnical site investigations

PSM 3.02.2 LIB - MOD FOR 5665.GLB Grfctbl DG PHOTO CORE PHOTO 1 PER PAGE A4L PSM5665.GPJ <<DrawingFile>> 06/03/2025 14:32 10.03.00.09 Datgel Fence and Map Tool | Lib: PSM 3.02.1 2019-03-06 Proj: PSM 3.02.1 2019-03-06



PointID : BH03 Depth Range: 0.00 - 4.00 m

	TITLE Mornington Peninsula Shire Council McCrae Landslide Geotechnical Investigation Core Photo - BH03: 0.00 m - 4.00 m	DRAWN BTA	DATE 6/03/2025
		CHECKED TN	DATE 6/03/2025
		SCALE Not To Scale	A4
		PROJECT No PSM5665	FIGURE No 1/8




PointID : BH03 Depth Range: 4.00 - 8.00 m



TITLE

Mornington Peninsula Shire Council
 McCrae Landslide Geotechnical Investigation
 Core Photo - BH03: 4.00 m - 8.00 m

DRAWN	BTA	DATE	6/03/2025
CHECKED	TN	DATE	6/03/2025
SCALE	Not To Scale		A4
PROJECT No	PSM5665	FIGURE No	2/8



PointID : BH03 Depth Range: 8.00 - 12.00 m



TITLE

Mornington Peninsula Shire Council
 McCrae Landslide Geotechnical Investigation
 Core Photo - BH03: 8.00 m - 12.00 m

DRAWN

BTA

DATE

6/03/2025

CHECKED

TN

DATE

6/03/2025

SCALE

Not To Scale


A4

PROJECT No

PSM5665

FIGURE No

3/8



PointID : BH03 Depth Range: 12.00 - 16.00 m

	TITLE Mornington Peninsula Shire Council McCrae Landslide Geotechnical Investigation Core Photo - BH03: 12.00 m - 16.00 m	DRAWN BTA	DATE 6/03/2025
		CHECKED TN	DATE 6/03/2025
		SCALE Not To Scale	A4
		PROJECT No PSM5665	FIGURE No 4/8



PointID : BH03 Depth Range: 16.00 - 20.00 m



TITLE

Mornington Peninsula Shire Council
McCrae Landslide Geotechnical Investigation
Core Photo - BH03: 16.00 m - 20.00 m

DRAWN

BTA

DATE

6/03/2025

CHECKED

TN

DATE

6/03/2025

SCALE

Not To Scale

A4

PROJECT No

PSM5665

FIGURE No

5/8



PointID : BH03 Depth Range: 20.00 - 24.00 m



TITLE

Mornington Peninsula Shire Council
 McCrae Landslide Geotechnical Investigation
 Core Photo - BH03: 20.00 m - 24.00 m

DRAWN

BTA

DATE

6/03/2025

CHECKED

TN

DATE

6/03/2025

SCALE

Not To Scale

A4

PROJECT No

PSM5665

FIGURE No

6/8



PointID : BH03 Depth Range: 24.00 - 28.00 m

	TITLE Mornington Peninsula Shire Council McCrae Landslide Geotechnical Investigation Core Photo - BH03: 24.00 m - 28.00 m	DRAWN BTA	DATE 6/03/2025
		CHECKED TN	DATE 6/03/2025
		SCALE Not To Scale	A4
		PROJECT No PSM5665	FIGURE No 7/8



PointID : BH03 Depth Range: 28.00 - 29.50 m



TITLE

Mornington Peninsula Shire Council
 McCrae Landslide Geotechnical Investigation
 Core Photo - BH03: 28.00 m - 29.50 m

DRAWN

BTA

DATE

6/03/2025

CHECKED

TN

DATE

6/03/2025

SCALE

Not To Scale

A4

PROJECT No

PSM5665

FIGURE No

8/8



Borehole ID

BH03A

Page 1 of 2

Geotechnical Log

Project No.: PSM5665

Client: Mornington Peninsula Shire Council		Commenced: 25/02/2025	
Project Name: McCrae Landslide Geotechnical Investigation		Completed: 25/02/2025	
Hole Location: 10-12 View Point Road Front Lawn		Logged By: LL	
Hole Position: 319533.7 m E 5753716.7 m N GDA2020 / MGA Zone 55		Checked By: TN	
Drill Model and Mounting: Geoprobe 7822 DT		Inclination: -90°	RL Surface: 28.70 m
Hole Diameter: 150 mm		Bearing: -	Datum: AHD Operator: SW Drilling

Drilling Information						Soil Description						Observations		
Method	Penetration	Support	Water	Samples Tests Remarks	Recovery	RL (m)	Depth (m)	Graphic Log	Classification Symbol	Material Description SOIL NAME: Plasticity, behaviour or particle characteristics of primary component, colour, secondary components, additional observations	Moisture Condition	Consistency / Relative Density	Hand Penetrometer UCS (kPa)	Structure, Zoning, Origin, Additional Observations
													100 200 300 400 500	
AD/V			N			27.7	1			Refer to BH03 for Lithology.				
						26.7	2							
						25.7	3							
						24.7	4							

Method
AD/T - Auger drilling TC bit
AD/V - Auger drilling V bit
WB - Washbore
SPT - Standard penetration test
PT - Push tube
AS - Auger screwing
CS - Continuous sampling (DT22)
NDD - Non destructive drilling
CC - Concrete coring
HA - Hand Auger

Penetration
 No resistance
 Refusal

Water
 Inflow
 Partial Loss
 Complete Loss

Samples and Tests
U - Undisturbed Sample
D - Disturbed Sample
SPT - Standard Penetration Test
ES - Environmental Sample
TW - Thin Walled
LB - Large Disturbed Sample

Moisture Condition
D - Dry
M - Moist
W - Wet

Consistency/Relative Density
VS - Very soft
S - Soft
F - Firm
St - Stiff
VSt - Very stiff
H - Hard
VL - Very loose
L - Loose
MD - Medium dense
D - Dense
VD - Very dense
Ce - Cemented
C - Compact



Borehole ID

BH03A

Page 2 of 2

Geotechnical Log

Project No.: PSM5665

Client: Mornington Peninsula Shire Council		Commenced: 25/02/2025	
Project Name: McCrae Landslide Geotechnical Investigation		Completed: 25/02/2025	
Hole Location: 10-12 View Point Road Front Lawn		Logged By: LL	
Hole Position: 319533.7 m E 5753716.7 m N GDA2020 / MGA Zone 55		Checked By: TN	
Drill Model and Mounting: Geoprobe 7822 DT		Inclination: -90°	
Hole Diameter: 150 mm		RL Surface: 28.70 m	
		Bearing: -	
		Datum: AHD	
		Operator: SW Drilling	

Drilling Information						Soil Description						Observations		
Method	Penetration	Support	Water	Samples Tests Remarks	Recovery	RL (m)	Depth (m)	Graphic Log	Classification Symbol	Material Description SOIL NAME: Plasticity, behaviour or particle characteristics of primary component, colour, secondary components, additional observations	Moisture Condition	Consistency / Relative Density	Hand Penetrometer UCS (kPa)	Structure, Zoning, Origin, Additional Observations
													100 200 300 400 500	
AD/V		N				22.7	6			Hole Terminated at 6.00 m Target depth. Standpipe and VWP Installed, and sand, gravel and bentonite packed in place.				
						21.7	7							
						20.7	8							
						19.7	9							

Method AD/T - Auger drilling TC bit AD/V - Auger drilling V bit WB - Washbore SPT - Standard penetration test PT - Push tube AS - Auger screwing CS - Continuous sampling (DT22) NDD - Non destructive drilling CC - Concrete coring HA - Hand Auger	Penetration No resistance Refusal	Water Inflow Partial Loss Complete Loss	Samples and Tests U - Undisturbed Sample D - Disturbed Sample SPT - Standard Penetration Test ES - Environmental Sample TW - Thin Walled LB - Large Disturbed Sample	Moisture Condition D - Dry M - Moist W - Wet	Consistency/Relative Density VS - Very soft S - Soft F - Firm St - Stiff VSt - Very stiff H - Hard VL - Very loose L - Loose MD - Medium dense D - Dense VD - Very dense Ce - Cemented C - Compact
---	--	---	---	--	--

BH04

Geotechnical Log

Project No.: PSM5665

Log PSM AU NONCORE BH NZ AU PSM5665.GPJ 26/03/2025 22:41 10.03.00.09 Datgel Fence and Map Tool | Lib: PSM 3.02.1 2019-03-06 Proj: PSM 3.02.1 2019-03-06



Borehole ID

BH04

Page 2 of 7

Geotechnical Log

Project No.: PSM5665

Client:		Mornington Peninsula Shire Council				Commenced:		26/02/2025							
Project Name:		McCrae Landslide Geotechnical Investigation				Completed:		27/02/2025							
Hole Location:		Middle of View Point Road Cul-de-sac				Logged By:		LL							
Hole Position:		319498.1 m E 5753665.8 m N GDA2020 / MGA Zone 55				Checked By:		TN							
Drill Model and Mounting:		Geoprobe 7822 DT		Inclination:		-90°		RL Surface:		26.82 m					
Hole Diameter:		CS - 57 mm, HQ3 - 96 mm		Bearing:		-		Datum:		AHD Operator: SW Drilling					
Drilling Information				Soil Description								Observations			
Method	Penetration	Support	Water	Samples Tests Remarks	Recovery	RL (m)	Depth (m)	Graphic Log	Classification Symbol	Material Description	Moisture Condition	Consistency / Relative Density	Hand Penetrometer UCS (kPa)	Structure, Zoning, Origin, Additional Observations	
CS		N	Not Encountered	D 5.00-5.80 m					CL	(RS) Sandy CLAY: low plasticity, mottled brown and grey; sand fine to medium grained. (continued)	w ≈ PL	VSt to H		5.80: Possibly Extremely Weathered Granite to EOH	
				PP 6.00 m >600 kPa		20.8	6		CL	(XW GRANITE) CLAY trace sand: low plasticity, grey mottled orange; sand fine grained; rock fabric observed.					*
				PP 7.00 m >600 kPa		19.8	7								*
				PP 8.00 m >600 kPa		18.8	8								*
HQ3		N		PP 9.00 m >600 kPa		17.8	9				w > PL to w ≈ PL	H		*	
															*
									CL	NO CORE: 9.50 - 9.60 m					
										(XW GRANITE) CLAY trace sand trace gravel: low plasticity, grey mottled orange; sand fine grained; rock fabric observed; gravel fine grained, angular.		H			
Method		Penetration		Water		Samples and Tests		Moisture Condition		Consistency/Relative Density					
AD/T - Auger drilling TC bit				▷ Inflow		U - Undisturbed Sample		D - Dry		VS - Very soft					
AD/V - Auger drilling V bit				▷ Partial Loss		D - Disturbed Sample		M - Moist		S - Soft					
WB - Washbore				◄ Complete Loss		SPT - Standard Penetration Test		W - Wet		F - Firm					
SPT - Standard penetration test						ES - Environmental Sample				St - Stiff					
PT - Push tube						TW - Thin Walled				VSt - Very stiff					
AS - Auger screwing						LB - Large Disturbed Sample				H - Hard					
CS - Continuous sampling (DT22)										VL - Very loose					
NDD - Non destructive drilling										L - Loose					
CC - Concrete coring										MD - Medium dense					
HA - Hand Auger										D - Dense					
										VD - Very dense					
										Ce - Cemented					
										C - Compact					

Logged in accordance with AS 1726:2017 Geotechnical site investigations



Borehole ID

BH04

Page 3 of 7

Geotechnical Log

Project No.: PSM5665

Client:	Mornington Peninsula Shire Council	Commenced:	26/02/2025
Project Name:	McCrae Landslide Geotechnical Investigation	Completed:	27/02/2025
Hole Location:	Middle of View Point Road Cul-de-sac	Logged By:	LL
Hole Position:	319498.1 m E 5753665.8 m N GDA2020 / MGA Zone 55	Checked By:	TN
Drill Model and Mounting:	Geoprobe 7822 DT	Inclination:	-90°
Hole Diameter:	CS - 57 mm, HQ3 - 96 mm	RL Surface:	26.82 m
		Bearing:	-
		Datum:	AHD
		Operator:	SW Drilling

Drilling Information							Soil Description							Observations
Method	Penetration	Support	Water	Samples Tests Remarks	Recovery	RL (m)	Depth (m)	Graphic Log	Classification Symbol	Material Description SOIL NAME: Plasticity, behaviour or particle characteristics of primary component, colour, secondary components, additional observations	Moisture Condition	Consistency / Relative Density	Hand Penetrometer UCS (kPa) 100 200 300 400 500	Structure, Zoning, Origin, Additional Observations
HQ3				PP 12.10 m =310 kPa PP 12.50 m =320 kPa PP 12.70 m =370 kPa		15.8	11		CL	(XW GRANITE) CLAY trace sand trace gravel: low plasticity, grey mottled orange; sand fine grained; rock fabric observed; gravel fine grained, angular. (continued)	w > PL to w = PL	H		
		SW	(XW GRANITE) SAND with gravel: fine to coarse grained, orange; gravel fine grained.					M						
		CL	(XW GRANITE) CLAY: low plasticity, grey.					w > PL	H					
		SC	(XW GRANITE) Clayey SAND: fine to medium grained, grey yellow; clay low plasticity.					M						
		CL	(XW GRANITE) Sandy CLAY trace gravel: low plasticity, grey; sand fine to coarse grained; gravel fine grained.					w > PL	VSt	x				
		SW	(XW GRANITE) Gravelly SAND: fine to coarse grained, yellow brown; gravel fine to medium grained.					M		x				
		CL	(XW GRANITE) Sandy CLAY trace gravel: low plasticity, grey yellow; sand fine to coarse grained; gravel fine to coarse grained, red brown angular moderately weathered granite clasts.					w > PL		x				
		NO CORE: 14.00 - 14.52 m												
		SP	(XW GRANITE) Gravelly SAND trace clay: fine to coarse grained, yellow brown; gravel fine to coarse grained red brown high to very high strength moderately weathered; clay low plasticity.					M						

PSM 3.02.2 LIB - MOD FOR 5665 GJB Log PSM AU NONCORE BH NZ AU PSM5665 GPJ <<DrawingFile>> 26/02/2025 22:41 10.03.00.09 Dagle Fence and Map Tool Lib: PSM 3.02.1 2018-03-06 Pj: PSM 3.02.1 2018-03-06

Method

AD/T - Auger drilling TC bit
AD/V - Auger drilling V bit
WB - Washbore
SPT - Standard penetration test
PT - Push tube
AS - Auger screwing
CS - Continuous sampling (DT22)
NDD - Non destructive drilling
CC - Concrete coring
HA - Hand Auger

Penetration

No resistance
Refusal

Water

▽ Inflow
△ Partial Loss
▲ Complete Loss

Samples and Tests

U - Undisturbed Sample
D - Disturbed Sample
SPT - Standard Penetration Test
ES - Environmental Sample
TW - Thin Walled
LB - Large Disturbed Sample

Moisture Condition

D - Dry
M - Moist
W - Wet

Consistency/Relative Density

VS - Very soft
S - Soft
F - Firm
St - Stiff
VSt - Very stiff
H - Hard
VL - Very loose
L - Loose
MD - Medium dense
D - Dense
VD - Very dense
Ce - Cemented
C - Compact

Logged in accordance with AS 1726:2017 Geotechnical site investigations



Borehole ID

BH04

Page 4 of 7

Geotechnical Log

Project No.: PSM5665

Client: Mornington Peninsula Shire Council		Commenced: 26/02/2025	
Project Name: McCrae Landslide Geotechnical Investigation		Completed: 27/02/2025	
Hole Location: Middle of View Point Road Cul-de-sac		Logged By: LL	
Hole Position: 319498.1 m E 5753665.8 m N GDA2020 / MGA Zone 55		Checked By: TN	
Drill Model and Mounting: Geoprobe 7822 DT		Inclination: -90°	
Hole Diameter: CS - 57 mm, HQ3 - 96 mm		RL Surface: 26.82 m	
		Bearing: -	
		Datum: AHD	
		Operator: SW Drilling	

Drilling Information				Soil Description				Observations										
Method	Penetration	Support	Water	Samples Tests Remarks	Recovery	RL (m)	Depth (m)	Graphic Log	Classification Symbol	Material Description	Moisture Condition	Consistency / Relative Density	Hand Penetrometer UCS (kPa)	Structure, Zoning, Origin, Additional Observations				
HQ3		N	Not Encountered	Is(50) = 0.11 MPa C 15.00-15.10 m		10.8	16		CL	(XW GRANITE) CLAY trace gravel trace sand: low plasticity, red brown; gravel fine to medium grained; sand fine grained.	w > PL	Vst		15.00: PLT carried out on an MW granite clast				
																GP	(XW GRANITE) Sandy GRAVEL trace clay: fine to medium grained, brown; sand fine to coarse grained; clay low plasticity.	M
																SC	(XW GRANITE) Clayey SAND trace gravel: fine to medium grained, grey brown; clay low plasticity; gravel fine grained, angular.	M
NO CORE: 18.50 - 20.50 m																		
						9.8	17											
						8.8	18											
						7.8	19											

Method AD/T - Auger drilling TC bit AD/V - Auger drilling V bit WB - Washbore SPT - Standard penetration test PT - Push tube AS - Auger screwing CS - Continuous sampling (DT22) NDD - Non destructive drilling CC - Concrete coring HA - Hand Auger	Penetration No resistance Refusal	Water Inflow Partial Loss Complete Loss	Samples and Tests U - Undisturbed Sample D - Disturbed Sample SPT - Standard Penetration Test ES - Environmental Sample TW - Thin Walled LB - Large Disturbed Sample	Moisture Condition D - Dry M - Moist W - Wet	Consistency/Relative Density VS - Very soft S - Soft F - Firm St - Stiff VSt - Very stiff H - Hard VL - Very loose L - Loose MD - Medium dense D - Dense VD - Very dense Ce - Cemented C - Compact
---	--	---	---	--	--



Borehole ID

BH04

Page 5 of 7

Geotechnical Log

Project No.: PSM5665

Client:	Mornington Peninsula Shire Council	Commenced:	26/02/2025
Project Name:	McCrae Landslide Geotechnical Investigation	Completed:	27/02/2025
Hole Location:	Middle of View Point Road Cul-de-sac	Logged By:	LL
Hole Position:	319498.1 m E 5753665.8 m N GDA2020 / MGA Zone 55	Checked By:	TN
Drill Model and Mounting:	Geoprobe 7822 DT	Inclination:	-90°
Hole Diameter:	CS - 57 mm, HQ3 - 96 mm	RL Surface:	26.82 m
		Bearing:	-
		Datum:	AHD
		Operator:	SW Drilling

Drilling Information							Soil Description							Observations
Method	Penetration	Support	Water	Samples Tests Remarks	Recovery	RL (m)	Depth (m)	Graphic Log	Classification Symbol	Material Description SOIL NAME: Plasticity, behaviour or particle characteristics of primary component, colour, secondary components, additional observations	Moisture Condition	Consistency / Relative Density	Hand Penetrometer UCS (kPa) 100 200 300 400 500	Structure, Zoning, Origin, Additional Observations
HQ3										NO CORE: 18.50 - 20.50 m (continued)				
				PP 21.00 m =380 kPa		5.8	21		SW	(XW GRANITE) SAND trace gravel: fine to coarse grained, grey; gravel occasional granite gravels red brown, very low to low strength, moderately weathered.	M			
				PP 21.40 m =420 kPa					CL	NO CORE: 20.75 - 20.80 m	M			
				PP 21.60 m =370 kPa						(XW GRANITE) Sandy CLAY trace gravel: low plasticity, grey; sand fine to coarse grained; gravel fine to medium grained.				
											w > PL	VSt to H		
						4.8	22							
										NO CORE: 22.50 - 22.95 m				
						3.8	23		CL	(XW GRANITE) CLAY trace gravel trace sand: low plasticity, grey; gravel fine grained; sand coarse grained.	w > PL	H		

Method	Penetration	Water	Samples and Tests	Moisture Condition	Consistency/Relative Density
AD/T - Auger drilling TC bit AD/V - Auger drilling V bit WB - Washbore SPT - Standard penetration test PT - Push tube AS - Auger screwing CS - Continuous sampling (DT22) NDD - Non destructive drilling CC - Concrete coring HA - Hand Auger	No resistance Refusal	Inflow Partial Loss Complete Loss	U - Undisturbed Sample D - Disturbed Sample SPT - Standard Penetration Test ES - Environmental Sample TW - Thin Walled LB - Large Disturbed Sample	D - Dry M - Moist W - Wet	VS - Very soft S - Soft F - Firm St - Stiff VSt - Very stiff H - Hard VL - Very loose L - Loose MD - Medium dense D - Dense VD - Very dense Ce - Cemented C - Compact



Borehole ID

BH04

Page 6 of 7

Geotechnical Log

Project No.: PSM5665

Client:	Mornington Peninsula Shire Council	Commenced:	26/02/2025
Project Name:	McCrae Landslide Geotechnical Investigation	Completed:	27/02/2025
Hole Location:	Middle of View Point Road Cul-de-sac	Logged By:	LL
Hole Position:	319498.1 m E 5753665.8 m N GDA2020 / MGA Zone 55	Checked By:	TN
Drill Model and Mounting:	Geoprobe 7822 DT	Inclination:	-90°
Hole Diameter:	CS - 57 mm, HQ3 - 96 mm	RL Surface:	26.82 m
		Bearing:	-
		Datum:	AHD
		Operator:	SW Drilling

Drilling Information							Soil Description							Observations				
Method	Penetration	Support	Water	Samples Tests Remarks	Recovery	RL (m)	Depth (m)	Graphic Log	Classification Symbol	Material Description SOIL NAME: Plasticity, behaviour or particle characteristics of primary component, colour, secondary components, additional observations	Moisture Condition	Consistency / Relative Density	Hand Penetrometer UCS (kPa)	Structure, Zoning, Origin, Additional Observations				
HQ3				PP 27.10 m >450 kPa PP 27.40 m >450 kPa PP 27.80 m =380 kPa		0.8	26			NO CORE: 24.00 - 25.50 m (<i>continued</i>)								

PSM 3.02.2 LIB - MOD FOR 5665 GLOB Log PSM AU NONCORE BH NZ AU PSM5665.GPJ <-DrawingFile>> 26/02/2025 22:41 10.03.00.09 D:\globe\Fence and Map Tool Lib\PSM 3.02.1 2019-03-06

Method	Penetration	Water	Samples and Tests	Moisture Condition	Consistency/Relative Density
AD/T - Auger drilling TC bit AD/V - Auger drilling V bit WB - Washbore SPT - Standard penetration test PT - Push tube AS - Auger screwing CS - Continuous sampling (DT22) NDD - Non destructive drilling CC - Concrete coring HA - Hand Auger	No resistance Refusal	▽ Inflow △ Partial Loss ▲ Complete Loss	U - Undisturbed Sample D - Disturbed Sample SPT - Standard Penetration Test ES - Environmental Sample TW - Thin Walled LB - Large Disturbed Sample	D - Dry M - Moist W - Wet	VS - Very soft S - Soft F - Firm St - Stiff VSt - Very stiff H - Hard VL - Very loose L - Loose MD - Medium dense D - Dense VD - Very dense Ce - Cemented C - Compact

Logged in accordance with AS 1726:2017 Geotechnical site investigations



Borehole ID

BH04

Page 7 of 7


Geotechnical Log

Project No.: PSM5665

Client: Mornington Peninsula Shire Council		Commenced: 26/02/2025	
Project Name: McCrae Landslide Geotechnical Investigation		Completed: 27/02/2025	
Hole Location: Middle of View Point Road Cul-de-sac		Logged By: LL	
Hole Position: 319498.1 m E 5753665.8 m N GDA2020 / MGA Zone 55		Checked By: TN	
Drill Model and Mounting: Geoprobe 7822 DT		Inclination: -90°	
Hole Diameter: CS - 57 mm, HQ3 - 96 mm		RL Surface: 26.82 m	
		Bearing: -	
		Datum: AHD	
		Operator: SW Drilling	


Drilling Information						Soil Description						Observations		
Method	Penetration	Support	Water	Samples Tests Remarks	Recovery	RL (m)	Depth (m)	Graphic Log	Classification Symbol	Material Description	Moisture Condition	Consistency / Relative Density	Hand Penetrometer UCS (kPa)	Structure, Zoning, Origin, Additional Observations
									CL	(XW GRANITE) CLAY with sand: low plasticity grey brown; sand fine to coarse grained. Hole Terminated at 30.00 m Target depth. Standpipe Installed, and sand, gravel and bentonite packed in place.	w > PL St to VSt		100 200 300 400 500	
						-4.2	31							
						-5.2	32							
						-6.2	33							
						-7.2	34							

Method AD/T - Auger drilling TC bit AD/V - Auger drilling V bit WB - Washbore SPT - Standard penetration test PT - Push tube AS - Auger screwing CS - Continuous sampling (DT22) NDD - Non destructive drilling CC - Concrete coring HA - Hand Auger	Penetration No resistance Refusal	Water Inflow Partial Loss Complete Loss	Samples and Tests U - Undisturbed Sample D - Disturbed Sample SPT - Standard Penetration Test ES - Environmental Sample TW - Thin Walled LB - Large Disturbed Sample	Moisture Condition D - Dry M - Moist W - Wet	Consistency/Relative Density VS - Very soft S - Soft F - Firm St - Stiff VSt - Very stiff H - Hard VL - Very loose L - Loose MD - Medium dense D - Dense VD - Very dense Ce - Cemented C - Compact
---	--	---	---	--	--



PointID : BH04 Depth Range: 0.00 - 4.00 m

	TITLE Mornington Peninsula Shire Council McCrae Landslide Geotechnical Investigation Core Photo - BH04: 0.00 m - 4.00 m	DRAWN BTA	DATE 6/03/2025
		CHECKED TN	DATE 6/03/2025
		SCALE Not To Scale	A4
		PROJECT No PSM5665	FIGURE No 1/8



PointID : BH04 Depth Range: 4.00 - 8.00 m



TITLE

Mornington Peninsula Shire Council
McCrae Landslide Geotechnical Investigation
Core Photo - BH04: 4.00 m - 8.00 m

DRAWN

BTA

DATE

6/03/2025

CHECKED

TN

DATE

6/03/2025

SCALE

Not To Scale

A4

PROJECT No

PSM5665

FIGURE No

2/8



PointID : BH04 Depth Range: 8.00 - 12.00 m



TITLE

Mornington Peninsula Shire Council
 McCrae Landslide Geotechnical Investigation
 Core Photo - BH04: 8.00 m - 12.00 m

DRAWN	BTA	DATE	6/03/2025
CHECKED	TN	DATE	6/03/2025
SCALE	Not To Scale		A4
PROJECT No	PSM5665	FIGURE No	3/8



PointID : BH04 Depth Range: 12.00 - 16.00 m



TITLE

Mornington Peninsula Shire Council
 McCrae Landslide Geotechnical Investigation
 Core Photo - BH04: 12.00 m - 16.00 m

DRAWN

BTA

DATE

6/03/2025

CHECKED

TN

DATE

6/03/2025

SCALE

Not To Scale


A4

PROJECT No

PSM5665

FIGURE No

4/8



PointID : BH04 Depth Range: 16.00 - 20.00 m



TITLE

Mornington Peninsula Shire Council
 McCrae Landslide Geotechnical Investigation
 Core Photo - BH04: 16.00 m - 20.00 m

DRAWN

BTA

DATE

6/03/2025

CHECKED

TN

DATE

6/03/2025

SCALE

Not To Scale

A4

PROJECT No

PSM5665

FIGURE No

5/8



PointID : BH04 Depth Range: 20.00 - 24.00 m



TITLE

Mornington Peninsula Shire Council
McCrae Landslide Geotechnical Investigation
Core Photo - BH04: 20.00 m - 24.00 m

DRAWN

BTA

DATE

6/03/2025

CHECKED

TN

DATE

6/03/2025

SCALE

Not To Scale


A4

PROJECT No

PSM5665


FIGURE No

6/8



PointID : BH04 Depth Range: 24.00 - 28.00 m

	TITLE Mornington Peninsula Shire Council McCrae Landslide Geotechnical Investigation Core Photo - BH04: 24.00 m - 28.00 m	DRAWN BTA	DATE 6/03/2025
		CHECKED TN	DATE 6/03/2025
		SCALE Not To Scale	A4
		PROJECT No PSM5665	FIGURE No 7/8



PointID : BH04 Depth Range: 28.00 - 30.00 m



TITLE

Mornington Peninsula Shire Council
McCrae Landslide Geotechnical Investigation
Core Photo - BH04: 28.00 m - 30.00 m

DRAWN

BTA

DATE

6/03/2025

CHECKED

TN

DATE

6/03/2025

SCALE

Not To Scale

A4

PROJECT No

PSM5665

FIGURE No

8/8



Borehole ID

BH04A

Page 1 of 2

Geotechnical Log

Project No.: PSM5665

Client: Mornington Peninsula Shire Council		Commenced: 27/02/2025	
Project Name: McCrae Landslide Geotechnical Investigation		Completed: 27/02/2025	
Hole Location: Middle of View Point Road Cul-de-sac		Logged By: LL	
Hole Position: 319499.2 m E 5753666.1 m N GDA2020 / MGA Zone 55		Checked By: TN	
Drill Model and Mounting: Geoprobe 7822 DT		Inclination: -90°	RL Surface: 26.86 m
Hole Diameter: 150 mm		Bearing: -	Datum: AHD Operator: SW Drilling

Drilling Information						Soil Description						Observations		
Method	Penetration	Support	Water	Samples Tests Remarks	Recovery	RL (m)	Depth (m)	Graphic Log	Classification Symbol	Material Description SOIL NAME: Plasticity, behaviour or particle characteristics of primary component, colour, secondary components, additional observations	Moisture Condition	Consistency / Relative Density	Hand Penetrometer UCS (kPa)	Structure, Zoning, Origin, Additional Observations
													100 200 300 400 500	
AD/V			N			25.9	1			Refer to BH04 for Lithology.				
						24.9	2							
						23.9	3							
						22.9	4							

Method AD/T - Auger drilling TC bit AD/V - Auger drilling V bit WB - Washbore SPT - Standard penetration test PT - Push tube AS - Auger screwing CS - Continuous sampling (DT22) NDD - Non destructive drilling CC - Concrete coring HA - Hand Auger	Penetration No resistance Refusal	Water Inflow Partial Loss Complete Loss	Samples and Tests U - Undisturbed Sample D - Disturbed Sample SPT - Standard Penetration Test ES - Environmental Sample TW - Thin Walled LB - Large Disturbed Sample	Moisture Condition D - Dry M - Moist W - Wet	Consistency/Relative Density VS - Very soft S - Soft F - Firm St - Stiff VSt - Very stiff H - Hard VL - Very loose L - Loose MD - Medium dense D - Dense VD - Very dense Ce - Cemented C - Compact
---	--	---	---	--	--



Borehole ID

BH04A

Page 2 of 2

Geotechnical Log

Project No.: PSM5665

Client: Mornington Peninsula Shire Council		Commenced: 27/02/2025	
Project Name: McCrae Landslide Geotechnical Investigation		Completed: 27/02/2025	
Hole Location: Middle of View Point Road Cul-de-sac		Logged By: LL	
Hole Position: 319499.2 m E 5753666.1 m N GDA2020 / MGA Zone 55		Checked By: TN	
Drill Model and Mounting: Geoprobe 7822 DT		Inclination: -90°	RL Surface: 26.86 m
Hole Diameter: 150 mm		Bearing: -	Datum: AHD Operator: SW Drilling

Drilling Information						Soil Description						Observations		
Method	Penetration	Support	Water	Samples Tests Remarks	Recovery	RL (m)	Depth (m)	Graphic Log	Classification Symbol	Material Description SOIL NAME: Plasticity, behaviour or particle characteristics of primary component, colour, secondary components, additional observations	Moisture Condition	Consistency / Relative Density	Hand Penetrometer UCS (kPa)	Structure, Zoning, Origin, Additional Observations
													100 200 300 400 500	
AD/V		N				20.9	6			Hole Terminated at 6.00 m Target depth. Standpipe Installed, and sand and bentonite packed in place.				
						19.9	7							
						18.9	8							
						17.9	9							

Method AD/T - Auger drilling TC bit AD/V - Auger drilling V bit WB - Washbore SPT - Standard penetration test PT - Push tube AS - Auger screwing CS - Continuous sampling (DT22) NDD - Non destructive drilling CC - Concrete coring HA - Hand Auger	Penetration No resistance Refusal	Water Inflow Partial Loss Complete Loss	Samples and Tests U - Undisturbed Sample D - Disturbed Sample SPT - Standard Penetration Test ES - Environmental Sample TW - Thin Walled LB - Large Disturbed Sample	Moisture Condition D - Dry M - Moist W - Wet	Consistency/Relative Density VS - Very soft S - Soft F - Firm St - Stiff VSt - Very stiff H - Hard VL - Very loose L - Loose MD - Medium dense D - Dense VD - Very dense Ce - Cemented C - Compact
---	--	---	---	--	--



Borehole ID

BH05

Page 1 of 2

Geotechnical Log

Project No.: PSM5665

Client: Mornington Peninsula Shire Council		Commenced: 26/02/2025	
Project Name: McCrae Landslide Geotechnical Investigation		Completed: 26/02/2025	
Hole Location: 3 Penny Lane Driveway		Logged By: LL	
Hole Position: 319500.7 m E 5753775.2 m N GDA2020 / MGA Zone 55		Checked By: TN	
Drill Model and Mounting: Geoprobe 7822 DT		Inclination: -90°	
Hole Diameter: CS - 57 mm		RL Surface: 1.98 m	
		Bearing: -	
		Datum: AHD	
		Operator: SW Drilling	

Drilling Information				Soil Description				Observations						
Method	Penetration	Support	Water	Samples Tests Remarks	Recovery	RL (m)	Depth (m)	Graphic Log	Classification Symbol	Material Description SOIL NAME: Plasticity, behaviour or particle characteristics of primary component, colour, secondary components, additional observations	Moisture Condition	Consistency / Relative Density	Hand Penetrometer UCS (kPa)	Structure, Zoning, Origin, Additional Observations
CC		N								Concrete				0.00: Concrete
										No recovery.				
							1.0		SP	Gravelly SAND: fine to medium grained, grey brown; gravel angular, fine grained.	M			0.50: Possibly Aeolian Dune or Marine
									SP	SAND: medium to coarse grained, pale yellow.	M			
										No recovery.				
				D 1.60-2.30 m		0.0	2		SW	SAND: fine to coarse grained, grey.	D			
											W			
				D 2.60-3.60 m		-1.0	3		SC	No recovery. Clayey SAND trace gravel: fine to coarse grained, grey; gravel fine grained.				
											W			
				PP 3.60 m = 180 kPa		-2.0	4		CL-CI	CLAY: low to medium plasticity, brown mottled grey.	D w > PL	St		
									SW	SAND: fine to coarse grained, angular, grey.				
											W			
									SC	Clayey SAND: fine to medium grained, grey; clay low to medium plasticity.				
											W			
									CL	(RS) CLAY trace sand: low plasticity, brown;	w >	St		4.90: Possibly Residual

Method	Penetration	Water	Samples and Tests	Moisture Condition	Consistency/Relative Density
AD/T - Auger drilling TC bit AD/V - Auger drilling V bit WB - Washbore SPT - Standard penetration test PT - Push tube AS - Auger screwing CS - Continuous sampling (DT22) NDD - Non destructive drilling CC - Concrete coring HA - Hand Auger	No resistance Refusal	▽ Inflow △ Partial Loss ▲ Complete Loss	U - Undisturbed Sample D - Disturbed Sample SPT - Standard Penetration Test ES - Environmental Sample TW - Thin Walled LB - Large Disturbed Sample	D - Dry M - Moist W - Wet	VS - Very soft S - Soft F - Firm St - Stiff VSt - Very stiff H - Hard VL - Very loose L - Loose MD - Medium dense D - Dense VD - Very dense Ce - Cemented C - Compact



Borehole ID

BH05

Page 2 of 2


Geotechnical Log

Project No.: PSM5665

Client: Mornington Peninsula Shire Council		Commenced: 26/02/2025	
Project Name: McCrae Landslide Geotechnical Investigation		Completed: 26/02/2025	
Hole Location: 3 Penny Lane Driveway		Logged By: LL	
Hole Position: 319500.7 m E 5753775.2 m N GDA2020 / MGA Zone 55		Checked By: TN	
Drill Model and Mounting: Geoprobe 7822 DT		Inclination: -90°	RL Surface: 1.98 m
Hole Diameter: CS - 57 mm		Bearing: -	Datum: AHD Operator: SW Drilling


Drilling Information						Soil Description						Observations		
Method	Penetration	Support	Water	Samples Tests Remarks	Recovery	RL (m)	Depth (m)	Graphic Log	Classification Symbol	Material Description SOIL NAME: Plasticity, behaviour or particle characteristics of primary component, colour, secondary components, additional observations	Moisture Condition	Consistency / Relative Density	Hand Penetrometer UCS (kPa)	Structure, Zoning, Origin, Additional Observations
										sand fine grained. Hole Terminated at 5.00 m Target depth. VWP grouted, and sand and bentonite packed in place.	PL			
						-4.0	6							
						-5.0	7							
						-6.0	8							
						-7.0	9							

Method AD/T - Auger drilling TC bit AD/V - Auger drilling V bit WB - Washbore SPT - Standard penetration test PT - Push tube AS - Auger screwing CS - Continuous sampling (DT22) NDD - Non destructive drilling CC - Concrete coring HA - Hand Auger	Penetration No resistance Refusal	Water Inflow Partial Loss Complete Loss	Samples and Tests U - Undisturbed Sample D - Disturbed Sample SPT - Standard Penetration Test ES - Environmental Sample TW - Thin Walled LB - Large Disturbed Sample	Moisture Condition D - Dry M - Moist W - Wet	Consistency/Relative Density VS - Very soft S - Soft F - Firm St - Stiff VSt - Very stiff H - Hard VL - Very loose L - Loose MD - Medium dense D - Dense VD - Very dense Ce - Cemented C - Compact
---	--	---	---	--	--



PointID : BH05 Depth Range: 0.00 - 4.00 m

	TITLE Mornington Peninsula Shire Council McCrae Landslide Geotechnical Investigation Core Photo - BH05: 0.00 m - 4.00 m	DRAWN BTA	DATE 6/03/2025
		CHECKED TN	DATE 6/03/2025
		SCALE Not To Scale	A4
		PROJECT No PSM5665	FIGURE No 1/2



PointID : BH05 Depth Range: 4.00 - 5.00 m

	TITLE Mornington Peninsula Shire Council McCrae Landslide Geotechnical Investigation Core Photo - BH05: 4.00 m - 5.00 m	DRAWN BTA	DATE 6/03/2025
		CHECKED TN	DATE 6/03/2025
		SCALE Not To Scale	A4
		PROJECT No PSM5665	FIGURE No 2/2



Borehole ID

NDT01

Page 1 of 1

Geotechnical Log

Project No.: PSM5665

Client: Mornington Peninsula Shire Council		Commenced: 12/02/2025	
Project Name: McCrae Landslide Geotechnical Investigation		Completed: 12/02/2025	
Hole Location: Front Yard of 6 View Point Road Driveway		Logged By: JW	
Hole Position: 319571.8 m E 5753700.6 m N GDA2020 / MGA Zone 55		Checked By: TN	
Drill Model and Mounting: Vacuum Truck		Inclination: -90°	RL Surface: 32.34 m
Hole Diameter: 400 mm		Bearing: -	Datum: AHD Operator: Fulton Hogan

Drilling Information				Soil Description					Observations					
Method	Penetration	Support	Water	Samples Tests Remarks	Recovery	RL (m)	Depth (m)	Graphic Log	Classification Symbol	Material Description	Moisture Condition	Consistency / Relative Density	Hand Penetrometer UCS (kPa)	Structure, Zoning, Origin, Additional Observations
NDD		N	Not Encountered			31.3	1		ML	TOPSOIL: Sandy SILT: low plasticity, dark grey; sand fine grained.	w > PL			0.00: Topsoil
						30.3	2			Insufficient information to provide a detailed material description, but inferred to be FILL sandy CLAY from observations of material near surface and video inspection.			0.20: Possibly FILL above sewer trench	
						29.3	3					1.30: Obstruction in hole, possibly a cobble that could not be excavated by the vacuum truck 1.50: Rootlets observed down 1.5 m		
						28.3	4			Insufficient information to provide a detailed material description, but inferred to be natural gravelly clayey SAND below the fill based on observed cuttings and video inspection.		2.60: Horizontal dark grey band/contact - possibly water level mark		
AD/V													3.20: Possibly Colluvium or Residual. Inferred to be insitu material below sewer invert level	
Hole Terminated at 5.00 m Target depth. Standpipe Installed, and sand, gravel and bentonite packed in place.														

Method	Penetration	Water	Samples and Tests	Moisture Condition	Consistency/Relative Density
AD/T - Auger drilling TC bit AD/V - Auger drilling V bit WB - Washbore SPT - Standard penetration test PT - Push tube AS - Auger screwing CS - Continuous sampling (DT22) NDD - Non destructive drilling CC - Concrete coring HA - Hand Auger	 	 	U - Undisturbed Sample D - Disturbed Sample SPT - Standard Penetration Test ES - Environmental Sample TW - Thin Walled LB - Large Disturbed Sample	D - Dry M - Moist W - Wet	VS - Very soft S - Soft F - Firm St - Stiff VSt - Very stiff Ht - Hard VL - Very loose L - Loose MD - Medium dense D - Dense VD - Very dense Ce - Cemented C - Compact



Borehole ID

NDT02

Page 1 of 1

Geotechnical Log

Project No.: PSM5665

Client: Mornington Peninsula Shire Council		Commenced: 03/03/2025	
Project Name: McCrae Landslide Geotechnical Investigation		Completed: 03/03/2025	
Hole Location: Verge in front of 6 View Point Road		Logged By: SD	
Hole Position: 319575.4 m E 5753696.0 m N GDA2020 / MGA Zone 55		Checked By: TN	
Drill Model and Mounting: Vacuum Truck		Inclination: -90°	RL Surface: 32.73 m
Hole Diameter: 200 mm		Bearing: -	Datum: AHD Operator: Fulton Hogan

Drilling Information						Soil Description						Observations			
Method	Penetration	Support	Water	Samples Tests Remarks	Recovery	RL (m)	Depth (m)	Graphic Log	Classification Symbol	Material Description SOIL NAME: Plasticity, behaviour or particle characteristics of primary component, colour, secondary components, additional observations	Moisture Condition	Consistency / Relative Density	Hand Penetrometer UCS (kPa)	Structure, Zoning, Origin, Additional Observations	
NDD		N	Not Encountered			31.7	1		ML	TOPSOIL: Sandy SILT: low plasticity, dark grey; sand fine grained.	w > PL				0.00: Topsoil
						30.7	2			Insufficient information to provide a detailed material description, but inferred to be FILL based on proximity to sewer trench.					0.20: Possibly FILL above sewer trench
						29.7	3								
						28.7	4				Hole Terminated at 3.20 m Target depth. VWP installed, and sand, gravel and bentonite packed in place.				

Method AD/T - Auger drilling TC bit AD/V - Auger drilling V bit WB - Washbore SPT - Standard penetration test PT - Push tube AS - Auger screwing CS - Continuous sampling (DT22) NDD - Non destructive drilling CC - Concrete coring HA - Hand Auger	Penetration No resistance Refusal	Water Inflow Partial Loss Complete Loss	Samples and Tests U - Undisturbed Sample D - Disturbed Sample SPT - Standard Penetration Test ES - Environmental Sample TW - Thin Walled LB - Large Disturbed Sample	Moisture Condition D - Dry M - Moist W - Wet	Consistency/Relative Density VS - Very soft S - Soft F - Firm St - Stiff VSt - Very stiff H - Hard VL - Very loose L - Loose MD - Medium dense D - Dense VD - Very dense Ce - Cemented C - Compact
---	--	---	---	--	--



Borehole ID

RD1

Page 1 of 1

Geotechnical Log


Project No.: PSM5665

Client:	Mornington Peninsula Shire Council	Commenced:	20/03/2025				
Project Name:	McCrae Landslide Geotechnical Investigation	Completed:	20/03/2025				
Hole Location:	10-12 View Point Road Front Lawn	Logged By:	DP				
Hole Position:	319531.9 m E 5753714.4 m N GDA2020 / MGA Zone 55	Checked By:	DP				
Drill Model and Mounting:	Hand Auger	Inclination:	-90°	RL Surface:	28.60 m		
Hole Diameter:	100 mm	Bearing:	-	Datum:	AHD	Operator:	N/A

Drilling Information							Soil Description							Observations			
Method	Penetration	Support	Water	Samples Tests Remarks	Recovery	RL (m)	Depth (m)	Graphic Log	Classification Symbol	Material Description SOIL NAME: Plasticity, behaviour or particle characteristics of primary component, colour, secondary components, additional observations	Moisture Condition	Consistency / Relative Density	Hand Penetrometer UCS (kPa)				Structure, Zoning, Origin, Additional Observations
HA		N	Not Encountered	D 0.00-0.10 m					ML	TOPSOIL: Clayey SILT trace sand: low plasticity, brown; sand fine grained; trace rootlets.	D		100			0.00: Topsoil	
									SM	FILL: Silty SAND: fine to medium grained, grey.			200			0.10: Fill	
				D 0.20-0.30 m		28.4	0.2		GM	FILL: Silty GRAVEL with sand: medium grained, sub-angular, brown; silt low plasticity; sand fine grained.			300			0.30: Top of ReIn Drain	
				D 0.50-0.70 m		28.2	0.4		SM	Silty SAND trace gravel: fine to medium grained, brown; silt low plasticity; gravel medium grained, angular.			400			0.50: Base of ReIn Drain, Possibly Colluvium	
						28.0	0.6										
						27.8	0.8										
										Hole Terminated at 0.90 m Target depth. ReIn drain backfilled with bentonite plug and topped with Site won materials.							

Method

AD/T - Auger drilling TC bit
AD/V - Auger drilling V bit
WB - Washbore
SPT - Standard penetration test
PT - Push tube
AS - Auger screwing
CS - Continuous sampling (DT22)
NDD - Non destructive drilling
CC - Concrete coring
HA - Hand Auger

Penetration**Water**

▽ Inflow
△ Partial Loss
▲ Complete Loss

Samples and Tests

U - Undisturbed Sample
D - Disturbed Sample
SPT - Standard Penetration Test
ES - Environmental Sample
TW - Thin Walled
LB - Large Disturbed Sample

Moisture Condition

D - Dry
M - Moist
W - Wet

Consistency/Relative Density

VS - Very soft
S - Soft
F - Firm
St - Stiff
VSt - Very stiff
H - Hard
VL - Very loose
L - Loose
MD - Medium dense
D - Dense
VD - Very dense
Ce - Cemented
C - Compact



RD1 - 1 Depth Range: 0.00 m - 0.90 m



RD1 - 2 Depth Range: 0.00 m - 0.90 m



TITLE

Mornington Peninsula Shire Council
McCrae Landslide Geotechnical Investigation
Photo - RD1

DRAWN	LL	DATE	21/03/2025
CHECKED	DP	DATE	21/03/2025
SCALE	Not To Scale		A4
PROJECT No	PSM5665	FIGURE No	1/1



Borehole ID

RD2

Page 1 of 1

Geotechnical Log

Project No.: PSM5665

Client: Mornington Peninsula Shire Council		Commenced: 20/03/2025	
Project Name: McCrae Landslide Geotechnical Investigation		Completed: 20/03/2025	
Hole Location: 10-12 View Point Road Front Lawn		Logged By: DP	
Hole Position: 319534.8 m E 5753717.7 m N GDA2020 / MGA Zone 55		Checked By: DP	
Drill Model and Mounting: Hand Auger		Inclination: -90°	RL Surface: 28.80 m
Hole Diameter: 100 mm		Bearing: -	Datum: AHD Operator: N/A

Drilling Information						Soil Description						Observations		
Method	Penetration	Support	Water	Samples Tests Remarks	Recovery	RL (m)	Depth (m)	Graphic Log	Classification Symbol	Material Description	Moisture Condition	Consistency / Relative Density	Hand Penetrometer UCS (kPa)	Structure, Zoning, Origin, Additional Observations
HA		N	Not Encountered	D 0.20-0.30 m		28.6	0.2		ML	TOPSOIL: Clayey SILT trace sand: low plasticity, brown; sand fine grained; trace rootlets.	D		100	0.00: Topsoil
								SM	FILL: Silty SAND: fine to medium grained, grey; trace rootlets.	200			0.10: Fill	
								GM	FILL: Silty GRAVEL with sand: medium grained, sub-angular, brown; silt low plasticity; sand fine grained.	300			0.30: Top of ReIn Drain	
								SW	SAND trace gravel: fine to medium grained, brown; gravel medium grained, angular.	400			0.50: Base of ReIn Drain, Possibly Colluvium	
			D 0.50-0.70 m		28.4	0.4								
						28.2	0.6							
						28.0	0.8			Hole Terminated at 0.70 m Target depth. ReIn drain backfilled with bentonite plug and topped with Site won materials.				

Method AD/T - Auger drilling TC bit AD/V - Auger drilling V bit WB - Washbore SPT - Standard penetration test PT - Push tube AS - Auger screwing CS - Continuous sampling (DT22) NDD - Non destructive drilling CC - Concrete coring HA - Hand Auger	Penetration No resistance Refusal	Water Inflow Partial Loss Complete Loss	Samples and Tests U - Undisturbed Sample D - Disturbed Sample SPT - Standard Penetration Test ES - Environmental Sample TW - Thin Walled LB - Large Disturbed Sample	Moisture Condition D - Dry M - Moist W - Wet	Consistency/Relative Density VS - Very soft S - Soft F - Firm St - Stiff VSt - Very stiff H - Hard VL - Very loose L - Loose MD - Medium dense D - Dense VD - Very dense Ce - Cemented C - Compact
---	--	---	---	--	--



RD2 - 1 Depth Range: 0.00 m - 0.70 m



TITLE


Mornington Peninsula Shire Council
McCrae Landslide Geotechnical Investigation
Photo - RD2

DRAWN	LL	DATE	21/03/2025
CHECKED	DP	DATE	21/03/2025
SCALE	Not To Scale		A4
PROJECT No	PSM5665	FIGURE No	1/1

Appendix B

Point Load Strength Index Test Results





Pells Sullivan Meynink

POINT LOAD STRENGTH INDEX TEST RESULTS

Job No.		PSM5665										Sheet		1	of	1	
Project		McCrae Landslide															
Test Method		AS 4133.4.1-2007 Methods of testing rocks for engineering purposes - Determination of point load strength index						Sampling Technique		HQ3				Sampling Date		17-28/02/2025	
								Storage History		Geelong office storage				Testing Date		3/03/2025	
Test Machine		GSA 6510-0311						Moisture Condition		Natural				Tested By		LL	
Calibration Date		11/9/2026						Loading Rate		< 30 seconds							
Rock Type		Location	Depth (m)	Diametral Tests					Axial Tests						AS 1726:2017 Strength Class		
				D (mm)	L (mm)	P (kN)	I _{s(50)} (MPa)	Failure Mode	W (mm)	D (mm)	P (kN)	I _s (MPa)	I _{s(50)} (MPa)	Failure Mode			
Granite Corestone		BH01	17.8-17.9	70	50	11.51	2.73	Through substance	-	-	#N/A	#N/A	#N/A	Through substance	H / #N/A		
Granite Corestone		BH01	22.9-23.0	70	90	0.61	0.14	Bad break	-	-	#N/A	#N/A	#N/A	Bad break	L / #N/A		
Granite Corestone		BH02	21.3-21.4	70	50	7.80	1.85	Through substance	-	-	#N/A	#N/A	#N/A	Through substance	H / #N/A		
XW Granite		BH03	23.3-23.4	70	110	0.17	0.04	Through substance	70	60	0.2	0.03	0.04	Through substance	VL		
XW Granite		BH03	15.5-15.6	70	100	0.16	0.04	Through substance	70	30	0.1	0.05	0.05	Through substance	VL		
XW Granite		BH03	14.75-14.85	70	110	0.14	0.03	Through substance	70	60	0.1	0.02	0.03	Through substance	<VL		
XW Granite		BH03	21.4-21.55	70	190	0.38	0.09	Through substance	70	70	0.3	0.04	0.06	Through substance	VL		
Granite Corestone		BH04	15-15.1	55	100	0.49	0.17	Through substance	55	50	0.2	0.04	0.05	Through substance	VL / L		
By:		LL	Checked:				JW	Date:								7/3/2025	

1. #N/A = axial test was not performed.

2. A conversion factor of 20 was adopted (UCS = 20 I_{s(50)})

Appendix C

Piezometer Construction Records



				Hole ID BH01	
CLIENT : Mornington Peninsula Shire Council		POSITION : Refer to BH01 Log		SHEET : 1 OF 4	
CONTRACTOR : SW Drilling		EASTING : 319565.8 m		STATUS :	
PROJECT : McCrae Landslide		NORTHING : 5753704.4 m		LOGGED BY : JW/LL	
LOCATION : McCrae, VIC		COORD. SYS. : GDA2020 / MGA Zone 55		DRILL DATE : 19/02/2025 -	
PROJECT No. : PSM5665		GROUND RL : 31.57 m AHD		20/02/2025	

Method	Drilling Water	Depth (m)	Elevation (m AHD)	Graphic Log	Soil / Rock Description	PIEZOMETER CONSTRUCTION DETAILS				
						ID	Type	Stick Up & RL	Tip Depth & RL	Installation Date
						VWP1A	Vibrating Wire Piezometer	5.50 m 26.07 m	20/02/2025	
						VWP1B	Vibrating Wire Piezometer	14.50 m 17.07 m	20/02/2025	
						VWP1C	Vibrating Wire Piezometer	29.00 m 2.57 m	20/02/2025	
										No Surface Completion
										Grout
										Sand

RIG : Geoprobe 7822 DT	CHECKED BY : TN	REMARK
INCLINATION : -90°	CHECKED DATE : 27/03/2025	
AZIMUTH : -	APPROVED BY : DP	
HOLE DIA. : CS - 57 mm, HQ3 - 96 mm	APPROVED DATE : 27/03/2025	

					Hole ID BH01						
CLIENT : Mornington Peninsula Shire Council CONTRACTOR : SW Drilling PROJECT : McCrae Landslide LOCATION : McCrae, VIC PROJECT No. : PSM5665			POSITION : Refer to BH01 Log EASTING : 319565.8 m NORTHING : 5753704.4 m COORD. SYS. : GDA2020 / MGA Zone 55 GROUND RL : 31.57 m AHD		SHEET : 2 OF 4 STATUS : LOGGED BY : JW/LL DRILL DATE : 19/02/2025 - 20/02/2025						
Method	Drilling Water	Depth (m)	Elevation (m AHD)	Graphic Log	Soil / Rock Description	PIEZOMETER CONSTRUCTION DETAILS					
						ID	Type	Stick Up & RL	Tip Depth & RL	Installation Date	Static Water Level
CS					(RS/XW GRANITE) Sandy CLAY trace gravel: low plasticity, grey; sand fine to medium grained; gravel medium grained.	VWP1A	Vibrating Wire Piezometer	5.50 m	26.07 m	20/02/2025	
						VWP1B	Vibrating Wire Piezometer	14.50 m	17.07 m	20/02/2025	
HQ3	NOT ENCOUNTERED				(XW GRANITE) Sandy CLAY: low plasticity, grey; sand fine to medium grained.	VWP1C	Vibrating Wire Piezometer	29.00 m	2.57 m	20/02/2025	
		21			(RS/XW GRANITE) SAND trace gravel: fine to coarse grained, brown; gravel fine grained.						
		11			(XW GRANITE) Sandy CLAY: low plasticity, grey; sand fine to medium grained.						
		20			(XW GRANITE) Clayey SAND trace gravel: fine to coarse grained, grey mottled orange; clay low plasticity; gravel subangular, fine grained.						
		12									
		19									
		13			(XW GRANITE) Gravelly SAND trace clay: medium to coarse grained, yellow brown; gravel fine to medium; clay low plasticity.						
		18			(XW GRANITE) Clayey SAND: medium to coarse grained, grey mottled brown; clay low plasticity.						
		14			Becomes gravelly; fine to medium gravels at 13.90 m. NO CORE: 14.0 - 14.4 m						
		17			(XW GRANITE) Sandy CLAY with gravel: low plasticity, grey mottled orange; sand medium to coarse grained; gravel fine grained.						
		15									
		16			(XW GRANITE) Clayey SAND: fine to coarse grained, yellow mottled grey; clay low plasticity. MW granite inclusions at 15.3 - 15.5 m.						
		16			Becomes brown at 15.7 m.						
		15			(XW GRANITE) SAND with clay trace gravel: fine to coarse grained, brown grey; clay low plasticity; gravel fine grained.						
		17			NO CORE: 17.0 - 17.1 m						
		14			(XW GRANITE) SAND with clay trace gravel: fine to coarse grained, brown grey; clay low plasticity; gravel fine grained. FELDSPAR inclusions at 17.25 m.						
		18			(XW GRANITE) SAND with clay trace gravel: fine to coarse grained, brown; clay low plasticity; gravel fine grained.						
		13			(XW GRANITE) Sandy CLAY trace gravel: low plasticity, grey; sand fine grained; gravel fine grained.						
		19									
		12			(XW GRANITE) CLAY trace sand: low plasticity, grey; sand fine grained.						
RIG : Geoprobe 7822 DT CHECKED BY : TN INCLINATION : -90° CHECKED DATE : 27/03/2025 AZIMUTH : - APPROVED BY : DP HOLE DIA. : CS - 57 mm, HQ3 - 96 mm APPROVED DATE : 27/03/2025						REMARK					

 Hole ID BH01									
CLIENT : Mornington Peninsula Shire Council CONTRACTOR : SW Drilling PROJECT : McCrae Landslide LOCATION : McCrae, VIC PROJECT No. : PSM5665		POSITION : Refer to BH01 Log EASTING : 319565.8 m NORTHING : 5753704.4 m COORD. SYS. : GDA2020 / MGA Zone 55 GROUND RL : 31.57 m AHD		SHEET : 3 OF 4 STATUS : LOGGED BY : JW/LL DRILL DATE : 19/02/2025 - 20/02/2025					
Method	Drilling Water	Depth (m)	Elevation (m AHD)	Graphic Log	Soil / Rock Description	PIEZOMETER CONSTRUCTION DETAILS			
HQ3	NOT ENCOUNTERED	11			(XW GRANITE) Sandy CLAY: low plasticity, grey; sand fine to coarse grained. Coarse grained MW granite gravel clast at 20.15 m.	ID VWP1A Vibrating Wire Piezometer VWP1B Vibrating Wire Piezometer VWP1C Vibrating Wire Piezometer Type Stick Up & RL Tip Depth & RL 5.50 m 26.07 m 14.50 m 17.07 m 29.00 m 2.57 m Installation Date 20/02/2025 20/02/2025 20/02/2025 Static Water Level			
		21			(XW GRANITE) SAND with clay trace gravel: fine to coarse grained, grey; clay low plasticity; gravel angular, fine grained.				
		10			NO CORE: 21.5 - 22.6 m				
		22							
		9			(XW GRANITE) Gravelly SAND with clay: fine to coarse grained, brown; gravel fine grained; clay low plasticity.				
		23			NO CORE: 23.05 - 23.2 m				
		8			(XW GRANITE) SAND: medium to coarse grained, brown.				
		24			(XW GRANITE) Gravelly SAND trace clay: fine to coarse grained, grey brown; gravel subangular to angular, fine grained; clay low plasticity.				
		7			(XW GRANITE) Clayey SAND: fine to medium grained, grey; clay low plasticity.				
		25			NO CORE: 24.5 - 24.85 m				
		6			(XW GRANITE) Gravelly SAND with clay: medium to coarse grained, brown; gravel fine grained; clay low plasticity.				
		26			NO CORE: 26.0 - 26.05 m				
		5			(XW GRANITE) CLAY with sand: low plasticity, grey; sand fine to medium grained.				
		27			NO CORE: 27.0 - 28.3 m				
		4							
28									
3			(XW GRANITE) SAND: fine to medium grained, brown.						
29			(XW GRANITE) Sandy CLAY: low plasticity, brown; sand fine to medium grained.						
2			(XW GRANITE) SAND with clay trace gravel: fine to medium grained, brown; clay low plasticity; gravel fine grained granite.						
			NO CORE: 29.2 - 29.7 m						
			(XW GRANITE) Sandy GRAVEL: fine grained, brown; sand fine to coarse grained granite.						
RIG : Geoprobe 7822 DT CHECKED BY : TN INCLINATION : -90° CHECKED DATE : 27/03/2025 AZIMUTH : - APPROVED BY : DP HOLE DIA. : CS - 57 mm, HQ3 - 96 mm APPROVED DATE : 27/03/2025						REMARK			

P S M					Hole ID BH01							
CLIENT : Mornington Peninsula Shire Council CONTRACTOR : SW Drilling PROJECT : McCrae Landslide LOCATION : McCrae, VIC PROJECT No. : PSM5665			POSITION : Refer to BH01 Log EASTING : 319565.8 m NORTHING : 5753704.4 m COORD. SYS. : GDA2020 / MGA Zone 55 GROUND RL : 31.57 m AHD		SHEET : 4 OF 4 STATUS : LOGGED BY : JW/LL DRILL DATE : 19/02/2025 - 20/02/2025							
Method	Drilling Water	Depth (m)	Elevation (m AHD)	Graphic Log	Soil / Rock Description	PIEZOMETER CONSTRUCTION DETAILS						
						ID	Type	Stick Up & RL	Tip Depth & RL	Installation Date	Static Water Level	
						VWP1A	Vibrating Wire Piezometer	5.50 m	26.07 m	20/02/2025		
						VWP1B	Vibrating Wire Piezometer	14.50 m	17.07 m	20/02/2025		
						VWP1C	Vibrating Wire Piezometer	29.00 m	2.57 m	20/02/2025		
					(XW GRANITE) SAND: fine grained, brown. Hole Terminated at 30.00 m Target depth. Nested VWPs grouted and sand packed in place at various depths.							
		1										
		31										
		0										
		32										
		-1										
		33										
		-2										
		34										
		-3										
		35										
		-4										
		36										
		-5										
		37										
		-6										
		38										
		-7										
		39										
		-8										
RIG : Geoprobe 7822 DT INCLINATION : -90° AZIMUTH : - HOLE DIA. : CS - 57 mm, HQ3 - 96 mm						CHECKED BY : TN CHECKED DATE : 27/03/2025 APPROVED BY : DP APPROVED DATE : 27/03/2025						REMARK

PSM 3.02.21.B - MOD FOR 5665.GLB Log MODA PIEZOMETER INSTALLATION LOG PSM5665.GPJ <<DrawingFile>> 28/03/2025 23:29 10.03.00.09 Dargal Fence and Map Tool Lib PSM 3.02.1 2019-05-06 Proj PSM 3.02.1 2019-05-06



PIEZOMETER INSTALLATION - FIELD SHEET

Date 20/02/2025 Time 4:00pm
 PSM staff LL/JW Drillers SW Drilling Others

Instrument

Piezometer model 350kPa HMA Model 1200 Piezometer serial number S18169
 Data logger model RST 5CH DT2055B Data logger serial number 19076
 Instrument ID (e.g. CSH-123-INC-1) VWP1A

Borehole

Borehole ID BH01
 Easting (m) 319565.8 Northing (m) 5753704.4
 Collar RL (m AHD) 31.57 Drilled depth (m) 30 Dipped depth prior to install (m) 1.4

Installation

Depth of instrument (m)	Tip direction	Screened rock mass unit (refer to borehole log)
5.5	☒ Up ☐ Down	Colluvium/Fill

Grout mix

Cement		Water		Bentonite	
Amount	Unit	Amount	Unit	Amount	Unit
N/A		N/A		N/A	

Comments

Sand packed between 1m to 6.5m
 Grouted with 25:1:0.3 mix between 0m to 1m

Zero reading (prior to sand packing)

Time	Reading (kHz ² x 10 ⁻³)	Temperature (°C)	Pressure (kPa)	Remarks
11:50am 20/02/2025	8573.5	25.0	2.9	above ground
4:00pm 20/02/2025	8590.7	22.3	1.3	0.4m above dipped depth at 1.4m
4:00pm 20/02/2025	8519.0	22.4	8.9	1.0m below dipped depth at 1.4m
4:45pm 20/02/2025	8105.2	20.5	53.3	at installation depth of 5.5m
7:20am 21/02/2025	8503.1	18.1	10.9	at installation depth of 5.5m

First readings (after sand packing)

#	Time	Reading (kHz ² x 10 ⁻³)	Temperature (°C)	Pressure (kPa)	Remarks
1					
2					



PIEZOMETER INSTALLATION - FIELD SHEET

Date 20/02/2025 Time 4:00pm

PSM staff LL/JW Drillers SW Drilling Others

Instrument

Piezometer model 350kPa HMA Model 1200 Piezometer serial number S18170

Data logger model RST 5CH DT2055B Data logger serial number 19076

Instrument ID (e.g. CSH-123-INC-1) VWP1B

Borehole

Borehole ID BH01

Easting (m) 319565.8 Northing (m) 5753704.4

Collar RL (m AHD) 31.57 Drilled depth (m) 30 Dipped depth prior to install (m) 1.4

Installation

Depth of instrument (m)	Tip direction	Screened rock mass unit (refer to borehole log)
14.5	☒ Up ☐ Down	XW Granite

Grout mix

Cement		Water		Bentonite	
Amount	Unit	Amount	Unit	Amount	Unit
Batch 1: 50	kg	Batch 1: 110	L	Batch 1: 12	kg
Batch 2: 20		Batch 2: 50		Batch 2: 1.5	

Comments

Batch 1: filled between ~12m to 30m Sand packed between 1m to 6.5m
 Batch 2: filled between ~6.5m to 12m Grouted with 25:1:0.3 mix between 0m to 1m

Zero reading (prior to grouting)

Time	Reading (kHz ² x 10 ⁻³)	Temperature (°C)	Pressure (kPa)	Remarks
12:10pm 20/02/2025	8496.9	25.1	2.4	above ground
4:00pm 20/02/2025	8505.5	22.0	1.8	0.4m above dipped depth at 1.4m
4:00pm 20/02/2025	8438.3	22.2	9.2	1.0m below dipped depth at 1.4m
4:45pm 20/02/2025	7227.6	19.4	143.1	at installation depth of 14.5m

First readings (after grouting)

#	Time	Reading (kHz ² x 10 ⁻³)	Temperature (°C)	Pressure (kPa)	Remarks
1	7:20am 21/02/2025	8511.8	17.8	1.5	Grout at 12m before batch 2 placed
2					
3					



PIEZOMETER INSTALLATION - FIELD SHEET

Date 20/02/2025 Time 4:00pm
 PSM staff LL/JW Drillers SW Drilling Others

Instrument

Piezometer model 350kPa HMA Model 1200 Piezometer serial number S18180
 Data logger model RST 5CH DT2055B Data logger serial number 19076
 Instrument ID (e.g. CSH-123-INC-1) VWP1C

Borehole

Borehole ID BH01
 Easting (m) 319565.8 Northing (m) 5753704.4
 Collar RL (m AHD) 31.57 Drilled depth (m) 30 Dipped depth prior to install (m) 1.4

Installation

Depth of instrument (m)	Tip direction	Screened rock mass unit (refer to borehole log)
29	☒ Up ☐ Down	XW Granite

Grout mix

Cement		Water		Bentonite	
Amount	Unit	Amount	Unit	Amount	Unit
Batch 1: 50	kg	Batch 1: 110	L	Batch 1: 12	kg
Batch 2: 20		Batch 2: 50		Batch 2: 1.5	

Comments

Batch 1: filled between ~12m to 30m Sand packed between 1m to 6.5m
 Batch 2: filled between ~6.5m to 12m Grouted with 25:1:0.3 mix between 0m to 1m

Zero reading (prior to grouting)

Time	Reading (kHz ² x 10 ⁻³)	Temperature (°C)	Pressure (kPa)	Remarks
12:15pm 20/02/2025	8990.3	23.0	2.0	above ground
4:00pm 20/02/2025	8987.9	21.3	2.3	0.4m above dipped depth at 1.4m
4:00pm 20/02/2025	8933.1	21.6	8.3	1.0m below dipped depth at 1.4m
4:45pm 20/02/2025	8105.2	20.5	99.1	at installation depth of 29m

First readings (after grouting)

#	Time	Reading (kHz ² x 10 ⁻³)	Temperature (°C)	Pressure (kPa)	Remarks
1	7:20am 21/02/2025	8586.4	18.9	46.5	Grout at 12m before batch 2 placed
2					
3					



CLIENT : PSM HOLDINGS AUSTRALIA PTY LTD

JOB No: GS0001602


SERIAL : S18169

DATE: 13/02/2025

RATING : 350 kPa

SHEET: 1

Vibrating Wire Piezometer Calibration Results



FACTORY ZERO READING : 8599 $\text{Hz}^2(10^{-3})$

PRESSURE COEFFICIENT : 0.10700 $\text{kPa}/\text{Hz}^2(10^{-3})$ ----- (C_p)

AMBIENT TEMPERATURE : 27.6 $^{\circ}\text{C}$

THERMAL COEFFICIENT : -0.07005 $\text{kPa}/^{\circ}\text{C}$ ----- (C_T)

SEE INSTRUCTION MANUAL FOR STANDARD TEMPERATURE/THERMISTOR DATA

MAXIMUM PRESSURE : 525 kPa

BAROMETRIC PRESSURE : 992 hPa

OPERATING TEMPERATURE RANGE : -20 $^{\circ}\text{C}$ to +80 $^{\circ}\text{C}$

For installation help,
scan the QR code to
view our manual.



$$\text{PORE PRESSURE} = (F_0 - F_1)C_p + (T_1 - T_0)C_T$$

(F_0) & (T_0) TO BE ESTABLISHED DURING INSTALLATION

www.hmagrp.com

Email: geotechnical@hmagrp.com Tel: +61 (0)3 8720 6700 Fax: +61 (0)3 8720 6799

Calibration Sheet



CLIENT : PSM HOLDINGS AUSTRALIA PTY LTD

JOB No: GS0001602


SERIAL : S18170

DATE: 13/02/2025

RATING : 350 kPa

SHEET: 2

Vibrating Wire Piezometer Calibration Results



FACTORY ZERO READING : 8517 $\text{Hz}^2(10^{-3})$

PRESSURE COEFFICIENT : 0.11040 $\text{kPa}/\text{Hz}^2(10^{-3})$ ----- (C_p)

AMBIENT TEMPERATURE : 27.5 $^{\circ}\text{C}$

THERMAL COEFFICIENT : -0.09148 $\text{kPa}/^{\circ}\text{C}$ ----- (C_T)

SEE INSTRUCTION MANUAL FOR STANDARD TEMPERATURE/THERMISTOR DATA

MAXIMUM PRESSURE : 525 kPa

BAROMETRIC PRESSURE : 992 hPa

OPERATING TEMPERATURE RANGE : -20 $^{\circ}\text{C}$ to +80 $^{\circ}\text{C}$

For installation help,
scan the QR code to
view our manual.



$$\text{PORE PRESSURE} = (F_0 - F_1)C_p + (T_1 - T_0)C_T$$

(F_0) & (T_0) TO BE ESTABLISHED DURING INSTALLATION

www.hmagrp.com

Email: geotechnical@hmagrp.com **Tel:** +61 (0)3 8720 6700 **Fax:** +61 (0)3 8720 6799

Calibration Sheet



CLIENT : PSM HOLDINGS AUSTRALIA PTY LTD

JOB No: GS0001602


SERIAL : S18180

DATE: 13/02/2025

RATING : 350 kPa

SHEET: 12

Vibrating Wire Piezometer Calibration Results



FACTORY ZERO READING : 9006 $\text{Hz}^2(10^{-3})$

PRESSURE COEFFICIENT : 0.10960 $\text{kPa}/\text{Hz}^2(10^{-3})$ ----- (C_p)

AMBIENT TEMPERATURE : 27.6 $^{\circ}\text{C}$

THERMAL COEFFICIENT : -0.05550 $\text{kPa}/^{\circ}\text{C}$ ----- (C_T)

SEE INSTRUCTION MANUAL FOR STANDARD TEMPERATURE/THERMISTOR DATA

MAXIMUM PRESSURE : 525 kPa

BAROMETRIC PRESSURE : 992 hPa

OPERATING TEMPERATURE RANGE : -20 $^{\circ}\text{C}$ to +80 $^{\circ}\text{C}$

For installation help,
scan the QR code to
view our manual.




$$\text{PORE PRESSURE} = (F_0 - F_1)C_p + (T_1 - T_0)C_T$$

(F_0) & (T_0) TO BE ESTABLISHED DURING INSTALLATION

www.hmagrp.com

Email: geotechnical@hmagrp.com Tel: +61 (0)3 8720 6700 Fax: +61 (0)3 8720 6799

P S M					Hole ID BH01A						
CLIENT : Mornington Peninsula Shire Council CONTRACTOR : SW Drilling PROJECT : McCrae Landslide LOCATION : McCrae, VIC PROJECT No. : PSM5665			POSITION : Refer to BH01A Log EASTING : 319565.7 m NORTHING : 5753703.3 m COORD. SYS. : GDA2020 / MGA Zone 55 GROUND RL : 31.69 m AHD		SHEET : 1 OF 1 STATUS : LOGGED BY : LL DRILL DATE : 25/02/2025						
Method	Drilling Water	Depth (m)	Elevation (m AHD)	Graphic Log	Soil / Rock Description	PIEZOMETER CONSTRUCTION DETAILS					
						ID STP1	Type Standpipe	Stick Up & RL 6.00 m 25.69 m	Tip Depth & RL 6.00 m 25.69 m	Installation Date 25/02/2025	Static Water Level
AD/V	NOT ENCOUNTERED		31		Refer to BH01 for Lithology.						
		1									
		2									
		3									
		4									
		5									
		6									
		7									
		8									
		9									
		22			Hole Terminated at 6.00 m Target depth. Standpipe Installed, and sand, gravel and bentonite packed in place.						
		23									
		24									
		25									
		26									
		27									
		28									
		29									
		30									
		31									

RIG : Geoprobe 7822 DT
INCLINATION : -90°
AZIMUTH : -
HOLE DIA. : 150 mm

CHECKED BY : TN
CHECKED DATE : 27/03/2025
APPROVED BY : DP
APPROVED DATE : 27/03/2025

REMARK

PSM 3.02.21.B - MOD FOR 5665.GLB Log MOD PIEZOMETER INSTALLATION LOG PSM5665.GPJ <<DrawingFile>> 26/03/2025 23:29 10.03.00.09 Dargel Fence and Map Tool Lib PSM 3.02.1 2019-05-06 Proj PSM 3.02.1 2019-05-06


BH02

SHEET : 1 OF 3
STATUS :
LOGGED BY: JW/LL
DRILL DATE : 20/02/2025 -
21/02/2025

PSM 3.02 LIB - MOD FOR 5665.GLB Log MON PIEZOMETER INSTALLATION LOG PSM5665.GPJ <<DrawingFile>> 09/04/2025 14:00 10.03.00.09 Date/1 Fence and Map Tool 1 Lib: PSM 3.02 1 2019-03-06 Pri: PSM 3.02 1 2019-03-06

P S M					Hole ID BH02						
CLIENT : Mornington Peninsula Shire Council CONTRACTOR : SW Drilling PROJECT : McCrae Landslide LOCATION : McCrae, VIC PROJECT No. : PSM5665			POSITION : Refer to BH02 Log EASTING : 319562.3 m NORTHING : 5753681.9 m COORD. SYS. : GDA2020 / MGA Zone 55 GROUND RL : 31.87 m AHD		SHEET : 2 OF 3 STATUS : LOGGED BY : JW/LL DRILL DATE : 20/02/2025 - 21/02/2025						
Method	Drilling Water	Depth (m)	Elevation (m AHD)	Graphic Log	Soil / Rock Description	PIEZOMETER CONSTRUCTION DETAILS					
						ID	Type	Stick Up & RL	Tip Depth & RL	Installation Date	Static Water Level
						VWP2A	Vibrating Wire Piezometer		6.50 m 25.37 m	24/02/2025	
						VWP2B	Vibrating Wire Piezometer		14.50 m 17.37 m	24/02/2025	
						VWP2C	Vibrating Wire Piezometer		28.50 m 3.37 m	24/02/2025	
CS	NOT ENCOUNTERED	11	21		(RS/XW GRANITE) CLAY trace sand trace gravel: low plasticity, brown; sand fine grained; gravel fine grained.						
			No recovery.								
		12	20		(XW GRANITE) Sandy CLAY: low plasticity, grey brown; sand fine grained.						
			(XW GRANITE) Sandy CLAY trace gravel: low plasticity, brown; sand fine to coarse grained; gravel fine to medium grained. Gravels becomes angular, coarse grained at 12.15 m.								
		13	19								
			(XW GRANITE) Sandy CLAY trace gravel trace cobbles: low plasticity, brown; sand fine to medium grained; gravel angular, fine to medium grained; cobbles granite, coarse grained, red brown, angular, high strength.								
		14	18								
			(XW GRANITE) Gravelly SAND: medium to coarse grained, yellow brown; gravel fine to medium grained.								
			(XW GRANITE) Clayey SAND: fine to coarse grained, brown; clay low plasticity.								
		15	17								
			(XW GRANITE) Sandy CLAY: low plasticity, grey; sand angular, fine to coarse grained.								
		16	16		NO CORE: 15.70 - 16.20 m						
			(XW GRANITE) Clayey SAND with gravel: fine to medium grained, brown; clay low plasticity; gravel fine to medium grained.								
		17	15								
HQ3	NOT ENCOUNTERED				NO CORE: 17.0 - 18.20 m						
		18	14								
			(XW GRANITE) CLAY: low plasticity, brown.								
			(XW GRANITE) Sandy CLAY trace gravel: low plasticity, brown; sand fine to coarse grained; gravel fine to coarse grained, granite.								
		19	13		NO CORE: 18.50 - 18.65 m						
			(XW GRANITE) Sandy CLAY: low plasticity, grey brown; sand fine to medium grained.								
			(XW GRANITE) SAND trace gravel: fine to coarse grained, grey brown; gravel fine grained.								
		12									
RIG : Geoprobe 7822 DT INCLINATION : -90° AZIMUTH : - HOLE DIA. : CS - 57 mm, HQ3 - 96 mm					CHECKED BY : TN CHECKED DATE : 27/03/2025 APPROVED BY : DP APPROVED DATE : 27/03/2025		REMARK				

PSM 3.02.21.B - MOD FOR 5665.GLB Log MON PIEZOMETER INSTALLATION LOG PSM5665.GPJ <<DrawingFile>> 26/03/2025 23:29 10.03.00.09 Dargel Fence and Map Tool Lib PSM 3.02.1 2019-05-06 Proj PSM 3.02.1 2019-05-06

 Hole ID BH02								
CLIENT : Mornington Peninsula Shire Council CONTRACTOR : SW Drilling PROJECT : McCrae Landslide LOCATION : McCrae, VIC PROJECT No. : PSM5665			POSITION : Refer to BH02 Log EASTING : 319562.3 m NORTHING : 5753681.9 m COORD. SYS. : GDA2020 / MGA Zone 55 GROUND RL : 31.87 m AHD		SHEET : 3 OF 3 STATUS : LOGGED BY : JW/LL DRILL DATE : 20/02/2025 - 21/02/2025			
Method	Drilling Water	Depth (m)	Elevation (m AHD)	Graphic Log	Soil / Rock Description	PIEZOMETER CONSTRUCTION DETAILS		
HQ3	NOT ENCOUNTERED	21	11		NO CORE: 20.00 - 21.15 m	ID VWP2A Vibrating Wire Piezometer VWP2B Vibrating Wire Piezometer VWP2C Vibrating Wire Piezometer Type Stick Up & RL Tip Depth & RL Installation Date Static Water Level 6.50 m 25.37 m 24/02/2025 14.50 m 17.37 m 24/02/2025 28.50 m 3.37 m 24/02/2025		
		22	10		(XW GRANITE) Sandy CLAY trace gravel: low plasticity, grey; sand fine to coarse grained; gravel fine to medium grained, granite source.			
		23	9		(XW GRANITE) Clayey SAND with gravel: fine to coarse grained, grey brown; clay low plasticity; gravel fine to medium grained.			
		24	8		(XW GRANITE) Gravelly SAND with clay: medium to coarse grained, grey brown; gravel subangular to angular, fine to medium grained; clay low plasticity.			
		25	7		Gravel 40mm diameter, angular, high strength. Becomes trace Clay at 24.5 m.			
		26	6		(XW GRANITE) CLAY: low plasticity, mottled grey, brown and white.			
		27	5		(XW GRANITE) CLAY trace gravel trace sand: low plasticity, grey; gravel fine to medium grained; sand fine grained.			
		28	4		(XW GRANITE) Sandy CLAY: low plasticity, grey; sand fine to coarse grained.			
		29	3		NO CORE: 27.50 - 28.45 m			
		30	2		(XW GRANITE) Sandy CLAY with gravel trace cobbles: low plasticity, brown; sand coarse grained; gravel fine grained; cobbles isolated, angular, high strength, slightly weathered granite, >70 mm diameter.			
		31	1		NO CORE: 29.00 - 29.37 m			
		32	0		(XW GRANITE) Clayey SAND with gravel: medium to coarse grained, brown; clay low plasticity; gravel fine grained.			
Hole terminated at 30.00m Target depth. Nested VWP's grouted in place at various depths.								
RIG : Geoprobe 7822 DT INCLINATION : -90° AZIMUTH : - HOLE DIA. : CS - 57 mm, HQ3 - 96 mm						CHECKED BY : TN CHECKED DATE : 27/03/2025 APPROVED BY : DP APPROVED DATE : 27/03/2025		REMARK



PIEZOMETER INSTALLATION - FIELD SHEET

Date 24/02/2025 Time 6:00pm

PSM staff LL/SD Drillers SW Drilling Others

Instrument

Piezometer model 350kPa HMA Model 1200 Piezometer serial number S18173

Data logger model RST 5CH DT2055B Data logger serial number 19070

Instrument ID (e.g. CSH-123-INC-1) VWP2A

Borehole

Borehole ID BH02

Easting (m) 319562.3 Northing (m) 5753681.9

Collar RL (m AHD) 31.87 Drilled depth (m) 30 Dipped depth prior to install (m) 2.4

Installation

Depth of instrument (m)	Tip direction	Screened rock mass unit (refer to borehole log)
6.5	☒ Up ☐ Down	Colluvium

Grout mix

Cement		Water		Bentonite	
Amount	Unit	Amount	Unit	Amount	Unit
Batch 1: 8	kg	Batch 1: 18	L	Batch 1: 2	kg

Comments

Batch 1: filled between 0m to 9.2m

Zero reading (prior to sand packing)

Time	Reading (kHz ² x 10 ⁻³)	Temperature (°C)	Pressure (kPa)	Remarks
6:00pm 24/02/2025	8680.7	33.9	4.7	above ground
7:00pm 24/02/2025	6307.8	20.9	271.9	at installation depth of 6.5m

First readings (after sand packing)

#	Time	Reading (kHz ² x 10 ⁻³)	Temperature (°C)	Pressure (kPa)	Remarks
1					
2					
3					



PIEZOMETER INSTALLATION - FIELD SHEET

Date 24/02/2025 Time 6:00pm

PSM staff LL/SD Drillers SW Drilling Others

Instrument

Piezometer model 350kPa HMA Model 1200 Piezometer serial number S18172

Data logger model RST 5CH DT2055B Data logger serial number 19070

Instrument ID (e.g. CSH-123-INC-1) VWP2B

Borehole

Borehole ID BH02

Easting (m) 319562.3 Northing (m) 5753681.9

Collar RL (m AHD) 31.87 Drilled depth (m) 30 Dipped depth prior to install (m) 2.4

Installation

Depth of instrument (m)	Tip direction	Screened rock mass unit (refer to borehole log)
14.5	☒ Up ☐ Down	XW Granite

Grout mix

Cement		Water		Bentonite	
Amount	Unit	Amount	Unit	Amount	Unit
Batch 1: 45	kg	Batch 1: 120	L	Batch 1: 10	kg
Batch 2: 13		Batch 2: 35		Batch 2: 4	
Batch 3: 8		Batch 3: 18		Batch 3: 2	

Comments

Batch 1: filled between ~14m to 30m Batch 3: filled between 0m to 9.2m
Batch 2: filled between ~9.2m to 14m

Zero reading (prior to grouting)

Time	Reading (kHz ² x 10 ⁻³)	Temperature (°C)	Pressure (kPa)	Remarks
6:00pm 24/02/2025	9029.0	28.5	3.1	above ground

First readings (after grouting)

#	Time	Reading (kHz ² x 10 ⁻³)	Temperature (°C)	Pressure (kPa)	Remarks
1	7:00pm 24/02/2025	8084.3	20.2	112.6	Grout at 14m before batch 2 placed
2					
3					



PIEZOMETER INSTALLATION - FIELD SHEET

Date 24/02/2025 Time 6:00pm
 PSM staff LL/SD Drillers SW Drilling Others

Instrument

Piezometer model 350kPa HMA Model 1200 Piezometer serial number S18178
 Data logger model RST 5CH DT2055B Data logger serial number 19070
 Instrument ID (e.g. CSH-123-INC-1) VWP2C

Borehole

Borehole ID BH02
 Easting (m) 319562.3 Northing (m) 5753681.9
 Collar RL (m AHD) 31.87 Drilled depth (m) 30 Dipped depth prior to install (m) 2.4

Installation

Depth of instrument (m)	Tip direction	Screened rock mass unit (refer to borehole log)
28.5	☒ Up ☐ Down	XW Granite

Grout mix

Cement		Water		Bentonite	
Amount	Unit	Amount	Unit	Amount	Unit
Batch 1: 45	kg	Batch 1: 120	L	Batch 1: 10	kg
Batch 2: 13		Batch 2: 35		Batch 2: 4	
Batch 3: 8		Batch 3: 18		Batch 3: 2	

Comments

Batch 1: filled between ~14m to 30m Batch 3: filled between 0m to 9.2m
 Batch 2: filled between ~9.2m to 14m

Zero reading (prior to grouting)

Time	Reading (kHz ² x 10 ⁻³)	Temperature (°C)	Pressure (kPa)	Remarks
6:00pm 24/02/2025	8925.3	28.3	3.2	above ground

First readings (after grouting)

#	Time	Reading (kHz ² x 10 ⁻³)	Temperature (°C)	Pressure (kPa)	Remarks
1	7:00pm 24/02/2025	8473.5	20.8	50.0	Grout at 14m before batch 2 placed
2					
3					



CLIENT : PSM HOLDINGS AUSTRALIA PTY LTD

JOB No: GS0001602


SERIAL : S18173

DATE: 13/02/2025

RATING : 350 kPa

SHEET: 5

Vibrating Wire Piezometer Calibration Results



FACTORY ZERO READING : 8729 $\text{Hz}^2(10^{-3})$

PRESSURE COEFFICIENT : 0.11200 $\text{kPa}/\text{Hz}^2(10^{-3})$ ----- (C_p)

AMBIENT TEMPERATURE : 27.5 $^{\circ}\text{C}$

THERMAL COEFFICIENT : -0.11440 $\text{kPa}/^{\circ}\text{C}$ ----- (C_T)

SEE INSTRUCTION MANUAL FOR STANDARD TEMPERATURE/THERMISTOR DATA

MAXIMUM PRESSURE : 525 kPa

BAROMETRIC PRESSURE : 992 hPa

OPERATING TEMPERATURE RANGE : -20 $^{\circ}\text{C}$ to +80 $^{\circ}\text{C}$

For installation help,
scan the QR code to
view our manual.



$$\text{PORE PRESSURE} = (F_0 - F_1)C_p + (T_1 - T_0)C_T$$

(F_0) & (T_0) TO BE ESTABLISHED DURING INSTALLATION

www.hmagrp.com

Email: geotechnical@hmagrp.com Tel: +61 (0)3 8720 6700 Fax: +61 (0)3 8720 6799

Calibration Sheet



CLIENT : PSM HOLDINGS AUSTRALIA PTY LTD

JOB No: GS0001602


SERIAL : S18172

DATE: 13/02/2025

RATING : 350 kPa

SHEET: 4

Vibrating Wire Piezometer Calibration Results



FACTORY ZERO READING : 9057 Hz²(10⁻³)

PRESSURE COEFFICIENT : 0.11510 kPa/Hz²(10⁻³) ----- (C_P)

AMBIENT TEMPERATURE : 27.4 °C

THERMAL COEFFICIENT : -0.09475 kPa/°C ----- (C_T)

SEE INSTRUCTION MANUAL FOR STANDARD TEMPERATURE/THERMISTOR DATA

MAXIMUM PRESSURE : 525 kPa

BAROMETRIC PRESSURE : 992 hPa

OPERATING TEMPERATURE RANGE : -20°C to +80°C

For installation help,
scan the QR code to
view our manual.



$$\text{PORE PRESSURE} = (F_0 - F_1)C_P + (T_1 - T_0)C_T$$

(F₀) & (T₀) TO BE ESTABLISHED DURING INSTALLATION

www.hmagrp.com

Email: geotechnical@hmagrp.com Tel: +61 (0)3 8720 6700 Fax: +61 (0)3 8720 6799

Calibration Sheet



CLIENT : PSM HOLDINGS AUSTRALIA PTY LTD

JOB No: GS0001602


SERIAL : S18178

DATE: 13/02/2025

RATING : 350 kPa

SHEET: 10

Vibrating Wire Piezometer Calibration Results



FACTORY ZERO READING : 8957 $\text{Hz}^2(10^{-3})$

PRESSURE COEFFICIENT : 0.10250 $\text{kPa}/\text{Hz}^2(10^{-3})$ (C_p)

AMBIENT TEMPERATURE : 27.5 $^{\circ}\text{C}$

THERMAL COEFFICIENT : -0.05987 $\text{kPa}/^{\circ}\text{C}$ (C_T)

SEE INSTRUCTION MANUAL FOR STANDARD TEMPERATURE/THERMISTOR DATA

MAXIMUM PRESSURE : 525 kPa

BAROMETRIC PRESSURE : 992 hPa

OPERATING TEMPERATURE RANGE : -20°C to $+80^{\circ}\text{C}$

For installation help,
scan the QR code to
view our manual.



$$\text{PORE PRESSURE} = (F_0 - F_1)C_p + (T_1 - T_0)C_T$$


(F_0) & (T_0) TO BE ESTABLISHED DURING INSTALLATION

www.hmagrp.com

Email: geotechnical@hmagrp.com Tel: +61 (0)3 8720 6700 Fax: +61 (0)3 8720 6799

BH03

SHEET : 1 OF 3
STATUS :
LOGGED BY: JW/LL
DRILL DATE : 17/02/2025 -
18/02/2025

						PIEZOMETER CONSTRUCTION DETAILS					
Method	Drilling Water	Depth (m)	Elevation (m AHD)	Graphic Log	Soil / Rock Description	ID	Type	Stick Up & RL	Tip Depth & RL	Installation Date	Static Water Level
						VWP3A	Vibrating Wire Piezometer	13.00 m	15.62 m	18/02/2025	
						VWP3B	Vibrating Wire Piezometer	28.00 m	0.62 m	18/02/2025	
CS	▽	1	28		TOPSOIL: Sandy SILT: low plasticity, brown; sand fine grained.		VWP3A	VWP3B	13.00 m	15.62 m	18/02/2025
				FILL: SAND with silt trace gravel: fine to medium grained, poorly graded, pale brown; gravel fine to medium grained, subangular gravel.							
				No recovery.							
			27		SAND with gravel trace silt: fine to medium grained, poorly graded, pale brown; gravel fine to coarse grained, subangular gravel.						
					SAND trace silt: fine to coarse grained, well graded, yellow brown; silt low plasticity.						
				No recovery.							
				Silty SAND trace gravel: fine to coarse grained, well graded, yellow brown; silt low plasticity; gravel fine grained.							
				Becomes dark brown with granite gravels at 3 m.							
			25		Becomes yellow brown at 3.5 m.						
			24		(RS/XW GRANITE) Clayey SAND: fine to coarse grained, well graded, sub-angular to angular, mottled brown and pale brown; clay low plasticity.						
6	23		No recovery.								
			(RS/XW GRANITE) Clayey SAND: fine to coarse grained, well graded, mottled brown and pale brown; clay low plasticity.								
		22		(RS/XW GRANITE) SAND trace clay: medium to coarse grained, well graded, sub-angular, grey brown; clay low plasticity.							
			Becomes fine to medium grained sand at 6.5 m.								
8	21		(XW GRANITE) Sandy CLAY: low plasticity, grey brown; sand fine to coarse grained.								
			NO CORE: 8.4 - 10.0 m								
9	20										
19											

RIG : Geoprobe 7822 DT

INCLINATION : -90°

AZIMUTH : -

HOLE DIA. : CS - 57 mm, HQ3 - 96 mm

CHECKED BY : TN

CHECKED DATE : 27/03/2025

APPROVED BY : DP

APPROVED DATE : 27/03/2025

REMARK

PSM 3.02.2 LIB - MOD FOR 5665.GLB Log MON PIEZOMETER INSTALLATION LOG PSM5665.GPJ <<DrawingFile>> 09/04/2025 14:00 10.03.00.09 Datgel Fence and Map Tool | Lib: PSM 3.02.1 2019-03-06 Proj: PSM 3.02.1 2019-03-06

BH03

POSITION : Refer to BH03 Log
EASTING : 319533.0 m
NORTHING : 5753715.6 m
COORD. SYS.: GDA2020 / MGA Zone 55
GROUND RL : 28.62 m AHD

SHEET : 2 OF 3
STATUS :
LOGGED BY : JW/LL
DRILL DATE : 17/02/2025 -
18/02/2025

					PIEZOMETER CONSTRUCTION DETAILS						
Method	Drilling Water	Depth (m)	Elevation (m AHD)	Graphic Log	Soil / Rock Description	ID	Type	Stick Up & RL	Tip Depth & RL	Installation Date	Static Water Level
						VWP3A	Vibrating Wire Piezometer		13.00 m 15.62 m	18/02/2025	
						VWP3B	Vibrating Wire Piezometer		28.00 m 0.62 m	18/02/2025	
CS		18			(XW GRANITE) SAND with clay: fine to coarse grained, grey; clay low plasticity.						
		11		(XW GRANITE) Sandy CLAY trace gravel: medium plasticity, dark grey; sand fine to coarse grained; gravel fine grained, subangular gravel.							
		17		(XW GRANITE) SAND trace clay trace gravel: fine to coarse grained, brown mottled orange; clay low plasticity; gravel fine grained, subangular gravel.							
12		NO CORE: 12.00 - 13.8 m									
HQ3	16			(XW GRANITE) Sandy CLAY trace gravel: low to medium plasticity, grey brown to brown; sand fine to coarse grained; no structure; gravel fine grained.							
	13										
	15										
SPT	14				(XW GRANITE) SAND trace clay: fine to coarse grained, yellow brown; clay low plasticity.						
	14				(XW GRANITE) Gravelly Sandy CLAY: low plasticity, grey; sand fine to coarse grained; gravel fine to medium grained subangular.						
	15				(XW GRANITE) SAND with clay trace gravel: fine to coarse grained, brown; clay low plasticity; gravel fine grained, subangular gravel.						
HQ3	13				NO CORE: 17.45 - 19.0 m						
	18										
	10										
		19					(XW GRANITE) SAND trace gravel: medium to coarse grained, brown; gravel fine grained, subangular gravel.				
		9			(XW GRANITE) Sandy CLAY: low plasticity, brown; sand fine grained.						
					NO CORE: 19.50 - 20.15 m						
						Grout					
RIG : Geoprobe 7822 DT						CHECKED BY : TN					
INCLINATION : -90°						CHECKED DATE : 27/03/2025					
AZIMUTH : -						APPROVED BY : DP					
HOLE DIA : CS - 57 mm, HQ3 - 96 mm						APPROVED DATE : 27/03/2025					
REMARK											

PSM 3.02.1 2019-03-06 Pri; PSM 3.02.1 2019-03-06
MON PIEZOMETER INSTALLATION LOG PSM5665.GPJ <<DrawingFile>> 10.03.00.09 Dateof Fence and Map Tool 1Lib; PSM 3.02.1 2019-03-06
PSM 3.02.2 LIB - MOD FOR 5665.GLB Loc 26/03/2025 23:29

 Hole ID BH03					
CLIENT : Mornington Peninsula Shire Council CONTRACTOR : SW Drilling PROJECT : McCrae Landslide LOCATION : McCrae, VIC PROJECT No. : PSM5665		POSITION : Refer to BH03 Log EASTING : 319533.0 m NORTHING : 5753715.6 m COORD. SYS. : GDA2020 / MGA Zone 55 GROUND RL : 28.62 m AHD		SHEET : 3 OF 3 STATUS : LOGGED BY : JW/LL DRILL DATE : 17/02/2025 - 18/02/2025	
PIEZOMETER CONSTRUCTION DETAILS					
ID	Type	Stick Up & RL	Tip Depth & RL	Installation Date	Static Water Level
VWP3A	Vibrating Wire Piezometer		13.00 m 15.62 m	18/02/2025	
VWP3B	Vibrating Wire Piezometer		28.00 m 0.62 m	18/02/2025	
Method	Drilling Water	Depth (m)	Elevation (m AHD)	Graphic Log	Soil / Rock Description
HQ3	NOT ENCOUNTERED	8			(XW GRANITE) Sandy CLAY: low plasticity, brown; sand fine grained.
		21			(XW GRANITE) Sandy CLAY trace gravel: low to medium plasticity, grey; sand fine to coarse grained; gravel fine grained, subangular gravel.
		7			
		22			NO CORE: 22.00 - 22.65 m
		6			
		23			(XW GRANITE) Clayey SAND trace gravel: fine to coarse grained, grey; clay low to medium plasticity; gravel fine grained, subangular gravel.
		5			
		24			
		4			(XW GRANITE) Silty SAND: fine grained, brown; silt low plasticity.
		25			(XW GRANITE) SAND with clay trace gravel: fine to coarse grained, grey; clay low plasticity; gravel fine grained, subangular gravel.
					NO CORE: 25.00 - 25.30 m
		3			(XW GRANITE) Sandy CLAY: low plasticity, grey; sand fine grained.
		26			
		2			NO CORE: 26.50 - 26.95 m
		27			(XW GRANITE) Gravelly Sandy CLAY: low plasticity, grey; sand fine to coarse grained; gravel fine grained; no structure.
1					
28			(XW GRANITE) Gravelly SAND with clay: medium to coarse grained, grey; gravel fine grained, subangular gravel; clay low plasticity.		
0					
29					
		-1			Hole Terminated at 29.50 m Target depth. Nested VWPs grouted in place at various depths.
RIG : Geoprobe 7822 DT INCLINATION : -90° AZIMUTH : - HOLE DIA. : CS - 57 mm, HQ3 - 96 mm CHECKED BY : TN CHECKED DATE : 27/03/2025 APPROVED BY : DP APPROVED DATE : 27/03/2025 REMARK					

P S M					Hole ID BH03A	
CLIENT : Mornington Peninsula Shire Council CONTRACTOR : SW Drilling PROJECT : McCrae Landslide LOCATION : McCrae, VIC PROJECT No. : PSM5665			POSITION : Refer to BH03A Log EASTING : 319533.7 m NORTHING : 5753716.7 m COORD. SYS. : GDA2020 / MGA Zone 55 GROUND RL : 28.70 m AHD		SHEET : 1 OF 1 STATUS : LOGGED BY : LL DRILL DATE : 25/02/2025	
Method	Drilling Water	Depth (m)	Elevation (m AHD)	Graphic Log	Soil / Rock Description	PIEZOMETER CONSTRUCTION DETAILS
AD/V	NOT ENCOUNTERED				Refer to BH03 for Lithology.	ID Type Stick Up & RL Tip Depth & RL Installation Date Static Water Level STP3 Standpipe 6.00 m 22.70 m 25/02/2025 VWP3C Vibrating Wire Piezometer 6.00 m 22.70 m 25/02/2025
		28				STP3 VWP3C Gatic Cover Grout Bentonite Gravel Sand 1.50 m 6.00 m
		22			Hole Terminated at 6.00 m Target depth. Standpipe and VWP Installed, and sand, gravel and bentonite packed in place.	
		19				
RIG : Geoprobe 7822 DT INCLINATION : -90° AZIMUTH : - HOLE DIA. : 150 mm					CHECKED BY : TN CHECKED DATE : 27/03/2025 APPROVED BY : DP APPROVED DATE : 27/03/2025	REMARK

PSM 3.02.21.B - MOD FOR 5665.GLB Log - MONA PIEZOMETER INSTALLATION LOG - PSM5665.GPJ <-DrawingFile>> 26/03/2025 23:29 10.03.00.09 Dargel Fence and Map Tool | Lib: PSM 3.02.1 2019-05-06 Proj: PSM 3.02.1 2019-05-06



PIEZOMETER INSTALLATION - FIELD SHEET

Date 18/02/2025 Time 4:30pm

PSM staff LL/JW Drillers SW Drilling Others

Instrument

Piezometer model 350kPa HMA Model 1200 Piezometer serial number S18171

Data logger model RST 5CH DT2055B Data logger serial number 19071

Instrument ID (e.g. CSH-123-INC-1) VWP3A

Borehole

Borehole ID BH03

Easting (m) 319533.0 Northing (m) 5753715.6

Collar RL (m AHD) 28.62 Drilled depth (m) 29.5 Dipped depth prior to install (m) 1

Installation

Depth of instrument (m)	Tip direction	Screened rock mass unit (refer to borehole log)
13	☒ Up ☐ Down	XW Granite

Grout mix

Cement		Water		Bentonite	
Amount	Unit	Amount	Unit	Amount	Unit
Batch 1: 30	kg	Batch 1: 80	L	Batch 1: 10	kg
Batch 2: 40		Batch 2: 80		Batch 2: 5	

Comments

Batch 1: filled between ~5.5m to 29.5m
Batch 2: filled between 0m to 5.5m

Zero reading (prior to grouting)

Time	Reading (kHz ² x 10 ⁻³)	Temperature (°C)	Pressure (kPa)	Remarks
2:45pm 18/02/2025	8630	18.0	1.2	above ground

First readings (after grouting)

#	Time	Reading (kHz ² x 10 ⁻³)	Temperature (°C)	Pressure (kPa)	Remarks
1	7:20am 19/02/2025	7927.6	17.6	73.3	Grout at 5.5m before batch 2 placed
2	8:10am 19/02/2025	7707.4	17.6	95.9	Grout at 0m after batch 2 placed
3	3:00pm 19/02/2025	8210.4	17.4	44.3	



PIEZOMETER INSTALLATION - FIELD SHEET

Date 18/02/2025 Time 4:30pm
 PSM staff LL/JW Drillers SW Drilling Others

Instrument

Piezometer model 350kPa HMA Model 1200 Piezometer serial number S18179
 Data logger model RST 5CH DT2055B Data logger serial number 19071
 Instrument ID (e.g. CSH-123-INC-1) VWP3B

Borehole

Borehole ID BH03
 Easting (m) 319533.0 Northing (m) 5753715.6
 Collar RL (m AHD) 28.62 Drilled depth (m) 29.5 Dipped depth prior to install (m) 1

Installation

Depth of instrument (m)	Tip direction	Screened rock mass unit (refer to borehole log)
28	☒ Up ☐ Down	XW Granite

Grout mix

Cement		Water		Bentonite	
Amount	Unit	Amount	Unit	Amount	Unit
Batch 1: 30	kg	Batch 1: 80	L	Batch 1: 10	kg
Batch 2: 40		Batch 2: 80		Batch 2: 5	

Comments

Batch 1: filled between ~5.5m to 29.5m
 Batch 2: filled between 0m to 5.5m

Zero reading (prior to grouting)

Time	Reading (kHz ² x 10 ⁻³)	Temperature (°C)	Pressure (kPa)	Remarks
2:45pm 18/02/2025	8964.0	19.2	2.1	above ground
4:40pm 18/02/2025	6420.3	18.4	285.6	at installation depth of 28m

First readings (after grouting)

#	Time	Reading (kHz ² x 10 ⁻³)	Temperature (°C)	Pressure (kPa)	Remarks
1	7:20am 19/02/2025	8541.5	17.8	49.4	Grout at 5.5m before batch 2 placed
2	8:10am 19/02/2025	8541.4	17.8	49.4	Grout at 0m after batch 2 placed
3	3:00pm 19/02/2025	8566.4	17.6	46.6	



PIEZOMETER INSTALLATION - FIELD SHEET

Date 25/02/2025 Time 9:30am

PSM staff LL Drillers SW Drilling Others

Instrument

Piezometer model 350kPa HMA Model 1200 Piezometer serial number S18177

Data logger model RST 5CH DT2055B Data logger serial number 19071

Instrument ID (e.g. CSH-123-INC-1) VWP3C

Borehole

Borehole ID BH03A

Easting (m) 319533.7 Northing (m) 5753716.7

Collar RL (m AHD) 28.7 Drilled depth (m) 6 Dipped depth prior to install (m) N/E

Installation

Depth of instrument (m)	Tip direction	Screened rock mass unit (refer to borehole log)
6	☒ Up ☐ Down	Residual/XW Granite

Grout mix

Cement		Water		Bentonite	
Amount	Unit	Amount	Unit	Amount	Unit
N/A		N/A		N/A	

Comments

Piezometer installed on outer circumference of Standpipe STP3A in BH03A. Sand packed between 1.5m to 6m, gravel packed between 1m to 1.5m and bentonite sealed to the surface. Capped with a gatic cover with some grout.

Zero reading (prior to standpipe installation)

Time	Reading (kHz ² x 10 ⁻³)	Temperature (°C)	Pressure (kPa)	Remarks
2:00pm 25/02/2025	8989.1	20.1	2.6	above ground

First readings (after standpipe installation)

#	Time	Reading (kHz ² x 10 ⁻³)	Temperature (°C)	Pressure (kPa)	Remarks
1					
2					
3					

Calibration Sheet



CLIENT : PSM HOLDINGS AUSTRALIA PTY LTD

JOB No: GS0001602


SERIAL : S18171

DATE: 13/02/2025

RATING : 350 kPa

SHEET: 3

Vibrating Wire Piezometer Calibration Results



FACTORY ZERO READING : 8633 Hz²(10⁻³)

PRESSURE COEFFICIENT : 0.10260 kPa/Hz²(10⁻³) ----- (C_P)

AMBIENT TEMPERATURE : 27.4 °C

THERMAL COEFFICIENT : -0.09803 kPa/°C ----- (C_T)

SEE INSTRUCTION MANUAL FOR STANDARD TEMPERATURE/THERMISTOR DATA

MAXIMUM PRESSURE : 525 kPa

BAROMETRIC PRESSURE : 992 hPa

OPERATING TEMPERATURE RANGE : -20°C to +80°C

For installation help,
scan the QR code to
view our manual.



$$\text{PORE PRESSURE} = (F_0 - F_1)C_P + (T_1 - T_0)C_T$$

(F₀) & (T₀) TO BE ESTABLISHED DURING INSTALLATION

www.hmagrp.com

Email: geotechnical@hmagrp.com Tel: +61 (0)3 8720 6700 Fax: +61 (0)3 8720 6799

Calibration Sheet



CLIENT : PSM HOLDINGS AUSTRALIA PTY LTD

JOB No: GS0001602


SERIAL : S18179

DATE: 13/02/2025

RATING : 350 kPa

SHEET: 11

Vibrating Wire Piezometer Calibration Results



FACTORY ZERO READING : 8972 $\text{Hz}^2(10^{-3})$

PRESSURE COEFFICIENT : 0.11140 $\text{kPa}/\text{Hz}^2(10^{-3})$ ----- (C_p)

AMBIENT TEMPERATURE : 27.4 $^{\circ}\text{C}$

THERMAL COEFFICIENT : -0.14550 $\text{kPa}/^{\circ}\text{C}$ ----- (C_T)

SEE INSTRUCTION MANUAL FOR STANDARD TEMPERATURE/THERMISTOR DATA

MAXIMUM PRESSURE : 525 kPa

BAROMETRIC PRESSURE : 992 hPa

OPERATING TEMPERATURE RANGE : -20 $^{\circ}\text{C}$ to +80 $^{\circ}\text{C}$

For installation help,
scan the QR code to
view our manual.



$$\text{PORE PRESSURE} = (F_0 - F_1)C_p + (T_1 - T_0)C_T$$

(F_0) & (T_0) TO BE ESTABLISHED DURING INSTALLATION

www.hmagrp.com

Email: geotechnical@hmagrp.com Tel: +61 (0)3 8720 6700 Fax: +61 (0)3 8720 6799

Calibration Sheet



CLIENT : PSM HOLDINGS AUSTRALIA PTY LTD

JOB No: GS0001602


SERIAL : S18177

DATE: 13/02/2025

RATING : 350 kPa

SHEET: 9

Vibrating Wire Piezometer Calibration Results



FACTORY ZERO READING : 9009 $\text{Hz}^2(10^{-3})$

PRESSURE COEFFICIENT : 0.10770 $\text{kPa}/\text{Hz}^2(10^{-3})$ ----- (C_p)

AMBIENT TEMPERATURE : 27.7 $^{\circ}\text{C}$

THERMAL COEFFICIENT : -0.05703 $\text{kPa}/^{\circ}\text{C}$ ----- (C_T)

SEE INSTRUCTION MANUAL FOR STANDARD TEMPERATURE/THERMISTOR DATA

MAXIMUM PRESSURE : 525 kPa

BAROMETRIC PRESSURE : 992 hPa

OPERATING TEMPERATURE RANGE : -20 $^{\circ}\text{C}$ to +80 $^{\circ}\text{C}$

For installation help,
scan the QR code to
view our manual.



$$\text{PORE PRESSURE} = (F_0 - F_1)C_p + (T_1 - T_0)C_T$$


(F_0) & (T_0) TO BE ESTABLISHED DURING INSTALLATION

www.hmagrp.com

Email: geotechnical@hmagrp.com Tel: +61 (0)3 8720 6700 Fax: +61 (0)3 8720 6799



BH04

SHEET : 1 OF 4
STATUS :
LOGGED BY : LL
DRILL DATE : 26/02/2025 -
27/02/2025

						PIEZOMETER CONSTRUCTION DETAILS					
Method	Drilling Water	Depth (m)	Elevation (m AHD)	Graphic Log	Soil / Rock Description	ID STP4	Type Standpipe	Stick Up & RL	Tip Depth & RL 29.70 m -2.88 m	Installation Date 27/02/2025	Static Water Level
CC					Asphaltic Concrete: Black No recovery.						
CS	NOT ENCOUNTERED	1	26		SAND with silt trace gravel: fine grained, poorly graded, pale yellow; silt low plasticity; gravel fine grained, angular.						
					No recovery.						
		2	25		SAND trace gravel: fine to medium grained, yellow grey; gravel fine grained, angular.						
					No recovery.						
		3	24		SAND trace gravel: fine to medium grained, yellow grey; gravel fine grained, angular.						
					No recovery.						
		4	23		SILT: low plasticity, yellow grey.						
					No recovery.						
		5	22		(RS) Sandy CLAY: low plasticity, mottled brown and grey; sand fine to medium grained.						
					No recovery.						
HQ3		6	21		(XW GRANITE) CLAY trace sand: low plasticity, grey mottled orange; sand fine grained; rock fabric observed.						
		7	20		No recovery.						
		8	19		No recovery.						
		9	18		No recovery.						
					NO CORE: 9.50 - 9.60 m						
		17			(XW GRANITE) CLAY trace sand trace gravel: low plasticity, grey mottled orange; sand fine grained; rock						
											

RIG : Geoprobe 7822 DT	CHECKED BY : TN	REMARK
INCLINATION : -90°	CHECKED DATE : 27/03/2025	
AZIMUTH : -	APPROVED BY : DP	
HOLE DIA. : CS - 57 mm, HQ3 - 96 mm	APPROVED DATE : 27/03/2025	

PSM 3.02.1 2019-03-06 Pri; PSM 3.02.1 2019-03-06
MON PIEZOMETER INSTALLATION LOG PSM5665.GPJ <<DrawingFile>> 10.03.00.09 Dateoll Fence and Map Tool 1Lib; PSM 3.02.1 2019-03-06
PSM 3.02.2 LIB - MOD FOR 5665.GLB Loc 26/03/2025 23:29

					Hole ID BH04				
CLIENT : Mornington Peninsula Shire Council CONTRACTOR : SW Drilling PROJECT : McCrae Landslide LOCATION : McCrae, VIC PROJECT No. : PSM5665			POSITION : Refer to BH04 Log EASTING : 319498.1 m NORTHING : 5753665.8 m COORD. SYS. : GDA2020 / MGA Zone 55 GROUND RL : 26.82 m AHD		SHEET : 2 OF 4 STATUS : LOGGED BY : LL DRILL DATE : 26/02/2025 - 27/02/2025				
Method	Drilling Water	Depth (m)	Elevation (m AHD)	Graphic Log	Soil / Rock Description	PIEZOMETER CONSTRUCTION DETAILS			
						ID STP4	Type Standpipe	Stick Up & RL 29.70 m -2.88 m	Tip Depth & RL 27/02/2025
HQ3	NOT ENCOUNTERED	16	16			14.70 m			
		11	16	(XW GRANITE) SAND with gravel: fine to coarse grained, orange; gravel fine grained.					
		15	16	(XW GRANITE) CLAY: low plasticity, grey.					
		12	15	(XW GRANITE) Clayey SAND: fine to medium grained, grey yellow; clay low plasticity.					
		13	14	(XW GRANITE) Sandy CLAY trace gravel: low plasticity, grey; sand fine to coarse grained; gravel fine grained.					
		14	13	(XW GRANITE) Gravelly SAND: fine to coarse grained, yellow brown; gravel fine to medium grained.					
		13	13	(XW GRANITE) Sandy CLAY trace gravel: low plasticity, grey yellow; sand fine to coarse grained; gravel fine to coarse grained, red brown angular moderately weathered granite clasts.					
		14	13	NO CORE: 14.00 - 14.52 m					
		15	12	(XW GRANITE) Gravelly SAND trace clay: fine to coarse grained, yellow brown; gravel fine to coarse grained red brown high to very high strength moderately weathered; clay low plasticity.					
		16	11	(XW GRANITE) CLAY trace gravel trace sand: low plasticity, red brown; gravel fine to medium grained; sand fine grained.					
		17	10	(XW GRANITE) Sandy GRAVEL trace clay: fine to medium grained, brown; sand fine to coarse grained; clay low plasticity.					
		18	9	(XW GRANITE) Clayey SAND trace gravel: fine to medium grained, grey brown; clay low plasticity; gravel fine grained, angular.					
		19	8	NO CORE: 16.30 - 17.50 m					
		7	7	NO CORE: 18.50 - 20.50 m					
		RIG : Geoprobe 7822 DT INCLINATION : -90° AZIMUTH : - HOLE DIA. : CS - 57 mm, HQ3 - 96 mm							

BH04

POSITION : Refer to BH04 Log
EASTING : 319498.1 m
NORTHING : 5753665.8 m
COORD. SYS. : GDA2020 / MGA Zone 55
GROUND RL : 26.82 m AHD

SHEET : 3 OF 4
STATUS :
LOGGED BY: LL
DRILL DATE : 26/02/2025 -
27/02/2025

PIEZOMETER CONSTRUCTION DETAILS					
ID	Type	Stick Up & RL	Tip Depth & RL	Installation Date	Static Water Level
STP4	Standpipe		29.70 m -2.88 m	27/02/2025	
Method	Drilling Water	Depth (m)	Elevation (m AHD)	Graphic Log	Soil / Rock Description
HQ3	NOT ENCOUNTERED				NO CORE: 18.50 - 20.50 m
		21	6	(XW GRANITE) SAND trace gravel: fine to coarse grained, grey; gravel occasional granite gravels red brown, very low to low strength, moderately weathered.	
				NO CORE: 20.75 - 20.80 m	
				(XW GRANITE) Sandy CLAY trace gravel: low plasticity, grey; sand fine to coarse grained; gravel fine to medium grained.	
		22	5		
				NO CORE: 22.50 - 22.95 m	
		23	4	(XW GRANITE) CLAY trace gravel trace sand: low plasticity, grey; gravel fine grained; sand coarse grained.	
				(XW GRANITE) Gravelly SAND: coarse grained, grey; gravel fine grained.	
		24	3		
				NO CORE: 24.00 - 25.50 m	
		25	2		
				(XW GRANITE) SAND trace gravel trace clay: fine to coarse grained, brown; gravel (quartz) fine grained; clay low plasticity.	
		26	1		
				NO CORE: 26.00 - 26.30 m	
				(XW GRANITE) Gravelly CLAY with sand: low plasticity, brown; gravel fine grained; sand fine to coarse grained.	
				NO CORE: 26.50 - 26.65 m	
		27	0	(XW GRANITE) Sandy CLAY trace gravel: low plasticity, brown; sand fine grained; gravel (quartz) fine grained.	
				(XW GRANITE) CLAY trace gravel: low plasticity, grey; gravel (quartz) fine grained, angular.	
				NO CORE: 27.50 - 27.65 m	
		28	-1	(XW GRANITE) CLAY trace gravel: low plasticity, grey; gravel (quartz) fine grained, angular.	
				NO CORE: 28.00 - 28.75 m	
				(XW GRANITE) CLAY with sand: low plasticity, grey brown; sand fine to coarse grained.	
		29	-2		
				NO CORE: 29.00 - 29.35 m	
				(XW GRANITE) CLAY with sand: low plasticity, grey brown; sand fine to coarse grained.	
		-3			
				NO CORE: 29.50 - 29.95 m	
					29.70 m
					Cuttings

RIG	: Geoprobe 7822 DT	CHECKED BY	: TN
INCLINATION	: -90°	CHECKED DATE	: 27/03/2025
AZIMUTH	: -	APPROVED BY	: DP
HOLE DIA.	: CS - 57 mm, HQ3 - 96 mm	APPROVED DATE	: 27/03/2025

REMARK

P S M					Hole ID BH04				
CLIENT : Mornington Peninsula Shire Council CONTRACTOR : SW Drilling PROJECT : McCrae Landslide LOCATION : McCrae, VIC PROJECT No. : PSM5665			POSITION : Refer to BH04 Log EASTING : 319498.1 m NORTHING : 5753665.8 m COORD. SYS. : GDA2020 / MGA Zone 55 GROUND RL : 26.82 m AHD		SHEET : 4 OF 4 STATUS : LOGGED BY : LL DRILL DATE : 26/02/2025 - 27/02/2025				
Method	Drilling Water	Depth (m)	Elevation (m AHD)	Graphic Log	Soil / Rock Description	PIEZOMETER CONSTRUCTION DETAILS			
						ID STP4	Type Standpipe	Stick Up & RL Tip Depth & RL 29.70 m -2.88 m	Installation Date Static Water Level 27/02/2025
					(XW GRANITE) CLAY with sand: low plasticity, grey brown; sand fine to coarse grained. Hole Terminated at 30.00 m Target depth. Standpipe Installed, and sand, gravel and bentonite packed in place.				
		31	-4						
		32	-5						
		33	-6						
		34	-7						
		35	-8						
		36	-9						
		37	-10						
		38	-11						
		39	-12						
			-13						
RIG : Geoprobe 7822 DT INCLINATION : -90° AZIMUTH : - HOLE DIA. : CS - 57 mm, HQ3 - 96 mm					CHECKED BY : TN CHECKED DATE : 27/03/2025 APPROVED BY : DP APPROVED DATE : 27/03/2025		REMARK		

PSM 3.02.2 LIB - MOD FOR 5665 CLB Log MODA PIEZOMETER INSTALLATION LOG PSM5665 GPJ <<DrawingFile>> 26/03/2025 23:29 10.03.00.09 Dargal Fence and Map Tool Lib PSM 3.02.1 2019-05-06 Proj PSM 3.02.1 2019-05-06

					Hole ID BH04A	
CLIENT : Mornington Peninsula Shire Council CONTRACTOR : SW Drilling PROJECT : McCrae Landslide LOCATION : McCrae, VIC PROJECT No. : PSM5665			POSITION : Refer to BH04A Log EASTING : 319499.2 m NORTHING : 5753666.1 m COORD. SYS. : GDA2020 / MGA Zone 55 GROUND RL : 26.86 m AHD		SHEET : 1 OF 1 STATUS : LOGGED BY : LL DRILL DATE : 27/02/2025	

Method	Drilling Water	Depth (m)	Elevation (m AHD)	Graphic Log	Soil / Rock Description	PIEZOMETER CONSTRUCTION DETAILS					
						ID	Type	Stick Up & RL	Tip Depth & RL	Installation Date	Static Water Level
AD/V	NOT ENCOUNTERED	1	26	Refer to BH04 for Lithology.	1.00 m	STP4A	Standpipe Piezometer	6.00 m	20.86 m	27/02/2025	Static Water Level
		2	25								
		3	24								
		4	23								
		5	22								
		6	21								
		7	20								
		8	19								
		9	18								
		10	17								
		6			Hole Terminated at 6.00 m Target depth. Standpipe Installed, and sand and bentonite packed in place.						

RIG : Geoprobe 7822 DT INCLINATION : -90° AZIMUTH : - HOLE DIA. : 150 mm	CHECKED BY : TN CHECKED DATE : 27/03/2025 APPROVED BY : DP APPROVED DATE : 27/03/2025	REMARK
---	--	--------

BH05

SHEET : 1 OF 1
STATUS :
LOGGED BY: LL
DRILL DATE : 26/02/2025

PIEZOMETER CONSTRUCTION DETAILS				
ID	Type	Stick Up & RL	Tip Depth & RL	Installation Date Static Water Level
VWP5A	Vibrating Wire Piezometer		4.80 m -2.82 m	26/02/2025
Method	Drilling Water	Depth (m)	Elevation (m AHD)	Soil / Rock Description
CC				Concrete
CS				No recovery.
				Gravelly SAND: fine to medium grained, grey brown; gravel angular, fine grained.
		1	1	SAND: medium to coarse grained, pale yellow.
				No recovery.
		2	0	SAND: fine to coarse grained, grey.
				No recovery.
		3	-1	Clayey SAND trace gravel: fine to coarse grained, grey; gravel fine grained.
				CLAY: low to medium plasticity, brown mottled grey.
		4	-2	SAND: fine to coarse grained, angular, grey.
				Clayey SAND: fine to medium grained, grey; clay low to medium plasticity.
		5	-3	(RS) CLAY trace sand: low plasticity, brown; sand fine grained.
				Hole Terminated at 5.00 m Target depth. VWP grouted, and sand and bentonite packed in place.
		6	-4	
		7	-5	
		8	-6	
		9	-7	

← Gatic Cover Bentonite

Grout

Sand

RIG : Geoprobe 7822 DT

INCLINATION : -90°

AZIMUTH : -

HOLE DIA. : CS - 57 mm

CHECKED BY : TN

CHECKED DATE : 27/03/2025

APPROVED BY : DP

APPROVED DATE : 27/03/2025

REMARK

PSM 3.02.2 LIB - MOD FOR 5665 GLB Log MON PIEZOMETER INSTALLATION LOG PSM5665.GPJ <<DrawingFile>> 26/03/2025 23:29 10.03.00.09 Datigel Fence and Map Tool | Lib: PSM 3.02.1 2019-03-06 Proj: PSM 3.02.1 2019-03-06



PIEZOMETER INSTALLATION - FIELD SHEET

Date 26/02/2025 Time 10:45am

PSM staff LL/SD Drillers SW Drilling Others

Instrument

Piezometer model 350kPa HMA Model 1200 Piezometer serial number S18175

Data logger model N/A Data logger serial number N/A

Instrument ID (e.g. CSH-123-INC-1) VWP5A

Borehole

Borehole ID BH05

Easting (m) 319500.7 Northing (m) 5753775.2

Collar RL (m AHD) 1.98 Drilled depth (m) 5.0 Dipped depth prior to install (m) N/E

Installation

Depth of instrument (m)	Tip direction	Screened rock mass unit (refer to borehole log)
4.8	☒ Up ☐ Down	Aeolian/Marine

Grout mix

Cement		Water		Bentonite	
Amount	Unit	Amount	Unit	Amount	Unit
Batch 1: 10	kg	Batch 1: 26	L	Batch 1: 3	kg

Comments

Sand packed between 4.5m and 5.0m. Bentonite seal at surface and capped with a gatic cover.
Fully grouted between 0m to 4.5m.

Zero reading (prior to grouting)

Time	Reading (kHz ² x 10 ⁻³)	Temperature (°C)	Pressure (kPa)	Remarks
10:30am 26/02/2025	8770.5	24.2	2.0	above ground

First readings (after grouting)

#	Time	Reading (kHz ² x 10 ⁻³)	Temperature (°C)	Pressure (kPa)	Remarks
1	11:15am 26/02/2025	8448.2	19.2	38.7	
2					
3					



CLIENT : PSM HOLDINGS AUSTRALIA PTY LTD

JOB No: GS0001602


SERIAL : S18175

DATE: 13/02/2025

RATING : 350 kPa

SHEET: 7

Vibrating Wire Piezometer Calibration Results



FACTORY ZERO READING : 8787 $\text{Hz}^2(10^{-3})$

PRESSURE COEFFICIENT : 0.11330 $\text{kPa}/\text{Hz}^2(10^{-3})$ ----- (C_p)

AMBIENT TEMPERATURE : 27.4 $^{\circ}\text{C}$

THERMAL COEFFICIENT : -0.04262 $\text{kPa}/^{\circ}\text{C}$ ----- (C_T)

SEE INSTRUCTION MANUAL FOR STANDARD TEMPERATURE/THERMISTOR DATA

MAXIMUM PRESSURE : 525 kPa

BAROMETRIC PRESSURE : 992 hPa

OPERATING TEMPERATURE RANGE : -20 $^{\circ}\text{C}$ to +80 $^{\circ}\text{C}$

For installation help,
scan the QR code to
view our manual.



$$\text{PORE PRESSURE} = (F_0 - F_1)C_p + (T_1 - T_0)C_T$$

(F_0) & (T_0) TO BE ESTABLISHED DURING INSTALLATION


www.hmagrp.com

Email: geotechnical@hmagrp.com Tel: +61 (0)3 8720 6700 Fax: +61 (0)3 8720 6799

				Hole ID NDT01	
CLIENT : Mornington Peninsula Shire Council CONTRACTOR : SW Drilling PROJECT : McCrae Landslide LOCATION : McCrae, VIC PROJECT No. : PSM5665			POSITION : Refer to NDT01 Log EASTING : 319571.8 m NORTHING : 5753700.6 m COORD. SYS. : GDA2020 / MGA Zone 55 GROUND RL : 32.34 m AHD		SHEET : 1 OF 1 STATUS : LOGGED BY : JW DRILL DATE : 12/02/2025

Method	Drilling Water	Depth (m)	Elevation (m AHD)	Graphic Log	Soil / Rock Description	PIEZOMETER CONSTRUCTION DETAILS			
						ID	Type	Stick Up & RL	Tip Depth & RL
NDD	NOT ENCOUNTERED	32			TOPSOIL: Sandy SILT: low plasticity, dark grey; sand fine grained. Insufficient information to provide a detailed material description, but inferred to be FILL sandy CLAY from observations of material near surface and video inspection.	STP1		← Gatic Cover Bentonite Gravel	1.50 m
		31			Insufficient information to provide a detailed material description, but inferred to be natural gravelly clayey SAND below the fill based on observed cuttings and video inspection.				
AD/V		2			Insufficient information to provide a detailed material description, but inferred to be natural gravelly clayey SAND below the fill based on observed cuttings and video inspection.				
		3			Insufficient information to provide a detailed material description, but inferred to be natural gravelly clayey SAND below the fill based on observed cuttings and video inspection.				
		4			Insufficient information to provide a detailed material description, but inferred to be natural gravelly clayey SAND below the fill based on observed cuttings and video inspection.				
		5			Hole Terminated at 5.00 m Target depth. Standpipe Installed, and sand, gravel and bentonite packed in place.				5.00 m
		6							
		7							
		8							
		9							
		10							
		11							
		12							
		13							
		14							
		15							
		16							
		17							
		18							
		19							
		20							
		21							
		22							
		23							
		24							
		25							
		26							
		27							

RIG : Vacuum Truck INCLINATION : -90° AZIMUTH : - HOLE DIA. : 400 mm	CHECKED BY : TN CHECKED DATE : 27/03/2025 APPROVED BY : DP APPROVED DATE : 27/03/2025	REMARK
---	--	--------

 Hole ID NDT02							
CLIENT : Mornington Peninsula Shire Council CONTRACTOR : SW Drilling PROJECT : McCrae Landslide LOCATION : McCrae, VIC PROJECT No. : PSM5665		POSITION : Refer to NDT02 Log EASTING : 319575.4 m NORTHING : 5753696.0 m COORD. SYS. : GDA2020 / MGA Zone 55 GROUND RL : 32.73 m AHD		SHEET : 1 OF 1 STATUS : LOGGED BY : SD DRILL DATE : 03/03/2025			
Method	Drilling Water	Depth (m)	Elevation (m AHD)	Graphic Log	Soil / Rock Description	PIEZOMETER CONSTRUCTION DETAILS ID Type Stick Up & RL Tip Depth & RL Installation Date Static Water Level VWP2D Vibrating Wire Piezometer 3.10 m 29.63 m 03/03/2025	
NDD	NOT ENCOUNTERED	1	32		TOPSOIL: Sandy SILT: low plasticity, dark grey; sand fine grained. Insufficient information to provide a detailed material description, but inferred to be FILL based on proximity to sewer trench.	 No Surface Completion Cuttings	
		2	31		Hole Terminated at 3.20 m Target depth. VWP installed, and sand, gravel and bentonite packed in place.		
		3	30				
		4	29				
		5	28				
		6	27				
		7	26				
		8	25				
		9	24				
			23				

RIG : Vacuum Truck INCLINATION : -90° AZIMUTH : - HOLE DIA. : 200 mm	CHECKED BY : TN CHECKED DATE : 27/03/2025 APPROVED BY : DP APPROVED DATE : 27/03/2025	REMARK



PIEZOMETER INSTALLATION - FIELD SHEET

Date 3/03/2025 Time 1:00pm

PSM staff SD/DRP Drillers SW Drilling Others

Instrument

Piezometer model 350kPa HMA Model 1200 Piezometer serial number S18176

Data logger model RST 1CH DT2011B Data logger serial number DT28683

Instrument ID (e.g. CSH-123-INC-1) VWP2D

Borehole

Borehole ID NDT02

Easting (m) 319575.4 Northing (m) 5753696.0

Collar RL (m AHD) 32.73 Drilled depth (m) 3.2 Dipped depth prior to install (m) 1.8

Installation

Depth of instrument (m)	Tip direction	Screened rock mass unit (refer to borehole log)
3.1	☒ Up ☐ Down	Fill

Grout mix

Cement		Water		Bentonite	
Amount	Unit	Amount	Unit	Amount	Unit
N/A		N/A		N/A	

Comments

Sand screen between ~2.8m to 3.2m. Bentonite plug to 50-100mm below surface and topped with topsoil.
Gravel pack between 0.9m to 2.8m.

Zero reading (prior to VWP installation)

Time	Reading ($\text{kHz}^2 \times 10^{-3}$)	Temperature ($^{\circ}\text{C}$)	Pressure (kPa)	Remarks
1:30pm 3/03/2025	8913.9	24.8	3.2	above ground

First readings (after VWP installation)

#	Time	Reading ($\text{kHz}^2 \times 10^{-3}$)	Temperature ($^{\circ}\text{C}$)	Pressure (kPa)	Remarks
1	1:50pm 3/03/2025	8734.5	21.1	25.1	
2					
3					

Calibration Sheet



CLIENT : PSM HOLDINGS AUSTRALIA PTY LTD

JOB No: GS0001602


SERIAL : S18176

DATE: 13/02/2025

RATING : 350 kPa

SHEET: 8

Vibrating Wire Piezometer Calibration Results



FACTORY ZERO READING : 8938 $\text{Hz}^2(10^{-3})$

PRESSURE COEFFICIENT : 0.11940 $\text{kPa}/\text{Hz}^2(10^{-3})$ ----- (C_p)

AMBIENT TEMPERATURE : 27.6 $^{\circ}\text{C}$

THERMAL COEFFICIENT : -0.12890 $\text{kPa}/^{\circ}\text{C}$ ----- (C_T)

SEE INSTRUCTION MANUAL FOR STANDARD TEMPERATURE/THERMISTOR DATA

MAXIMUM PRESSURE : 525 kPa

BAROMETRIC PRESSURE : 992 hPa

OPERATING TEMPERATURE RANGE : -20 $^{\circ}\text{C}$ to +80 $^{\circ}\text{C}$

For installation help,
scan the QR code to
view our manual.



$$\text{PORE PRESSURE} = (F_0 - F_1)C_p + (T_1 - T_0)C_T$$


(F_0) & (T_0) TO BE ESTABLISHED DURING INSTALLATION

www.hmagrp.com

Email: geotechnical@hmagrp.com Tel: +61 (0)3 8720 6700 Fax: +61 (0)3 8720 6799

Appendix D

CPT Results

**BLACK**
INSITU TESTINGProject: PSM5665
Location: McCrae

Client: PSM

G.L.: 0.00 m

Predrill: 0.00 m Predrilled

Date: 24/02/2025

Cone no.: C10CFIIP.C16325


Project no.: K205


CPT no.: CPT-01


1/1


Processed by: ALB


Checked by: MB



















**BLACK**
INSITU TESTINGClient: PSM
G.L.: 0.00 mProject: PSM5655
Location: McCrae

Predrill:	6.00 m Pre drilled
Date:	26/02/2025
Cone no.:	DC15CFIIP.C18609
Project no.:	K205
CPT no.:	CPT-04A
	1/1











Client: PSM

Date : 26/02/2025

Project : PSM5655

Project no. : K205

Location : McCrae

CPT no. : CPT-05

Test depth : 2.26 [m] - G.L.

Water level : 0.00 [m] - G.L.



Pells Sullivan Meynink

Office 16

Level 4, 60 Moorabool Street Geelong VIC 3220

www.psm.com.au

Project: McCrae Landslide

Location: McCrae, VIC

CPT: CPT-01


Total depth: 2.78 m, Date: 24/02/2025

Surface Elevation: 31.63 m

Coords: X:319564.80, Y:5753703.80

Cone Type: DC15FIIP

Cone Operator: Black Insitu






Pells Sullivan Meynink
Office 16
Level 4, 60 Moorabool Street Geelong VIC 3220
www.psm.com.au

Project: McCrae Landslide
Location: McCrae, VIC

CPT: CPT-01A

Total depth: 3.39 m, Date: 24/02/2025
Surface Elevation: 31.69 m
Coords: X:319565.00, Y:5753702.30
Cone Type: DC15CFIIP
Cone Operator: Black Insitu






Pells Sullivan Meynink
 Office 16
 Level 4, 60 Moorabool Street Geelong VIC 3220
 www.psm.com.au

Project: McCrae Landslide
Location: McCrae, VIC

CPT: CPT-01B

Total depth: 15.53 m, Date: 25/02/2025
 Surface Elevation: 31.70 m
 Coords: X:319565.70, Y:5753702.10
 Cone Type: DC15CFIIP
 Cone Operator: Black Insitu






Pells Sullivan Meynink
 Office 16
 Level 4, 60 Moorabool Street Geelong VIC 3220
www.psm.com.au

Project: McCrae Landslide
Location: McCrae, VIC

CPT: CPT-03

Total depth: 3.03 m, Date: 24/02/2025
 Surface Elevation: 28.68 m
 Coords: X:319533.30, Y:5753716.30
 Cone Type: DC15CFIIP
 Cone Operator: Black Insitu






Pells Sullivan Meynink
Office 16
Level 4, 60 Moorabool Street Geelong VIC 3220
www.psm.com.au

Project: McCrae Landslide
Location: McCrae, VIC

CPT: CPT-04

Total depth: 1.89 m, Date: 25/02/2025
Surface Elevation: 26.86 m
Coords: X:319499.20, Y:5753666.10
Cone Type: DC15CFIIP
Cone Operator: Black Insitu






Pells Sullivan Meynink
Office 16
Level 4, 60 Moorabool Street Geelong VIC 3220
www.psm.com.au

Project: McCrae Landslide
Location: McCrae, VIC

CPT: CPT-04A

Total depth: 13.90 m, Date: 26/02/2025
Surface Elevation: 26.86 m
Coords: X:319499.20, Y:5753666.10
Cone Type: DC15CFIIP
Cone Operator: Black Insitu





Pells Sullivan Meynink

Office 16

Level 4, 60 Moorabool Street Geelong VIC 3220

www.psm.com.au

Project: McCrae Landslide

Location: McCrae, VIC

CPT: CPT-05


Total depth: 2.27 m, Date: 26/02/2025

Surface Elevation: 1.91 m

Coords: X:319501.30, Y:5753776.90

Cone Type: DC15CFIIP

Cone Operator: Black Insitu



Appendix E

Laboratory Testing – Material Test Reports

Material Test Report

Report Number: GSSW2352-1
Issue Number: 1
Date Issued: 14/02/2025
Client: PELLIS SULLIVAN MEYNINK (PSM)

Contact: Dane Pope
Project Number: GSSW2352
Project Name: 10-12 POINT VIEW ROAD
Project Location: McCRAE
Client Reference: PSM5665
Work Request: 22410
Sample Number: 2352-S1
Date Sampled: 24/01/2025
Dates Tested: 05/02/2025 - 14/02/2025
Sampling Method: Sampled by Client - Tested as Received
The results apply to the sample as received
Sample Location: RILL/Consolidated waste on slope, Depth: 0.00m
Lot No: Sample ID S1
Material: clayey/silty SAND, trace gravel, pale grey, fine to coarse grained, low to medium plasticity, gravel 2%.



Ground Science South West
 Geotechnical & Environmental Consultants

Ground Science South West Pty Ltd
 8 Freedman Street North Geelong Vic 3215
 Phone: (03) 5282 1566

Email: chrism@groundsciencesw.com.au

Accredited for compliance with ISO/IEC 17025 - Testing




Irrelevant & Sensitive

Approved Signatory: Brent Elliott
 Laboratory Manager
 NATA Accredited Laboratory Number: 20109

Particle Size Distribution (AS1289 3.6.1)					
Sieve	Passed %	Passing Limits	Retained %	Retained Limits	
19 mm	100		0		
13.2 mm	100		0		
9.5 mm	100		0		
6.7 mm	99		0		
4.75 mm	99		0		
2.36 mm	98		1		
1.18 mm	91		7		
0.6 mm	81		10		
0.425 mm	74		7		
0.3 mm	66		8		
0.15 mm	53		13		
0.075 mm	31		23		

Moisture Content (AS1289.2.1.1)		Min	Max
Moisture Content (%)	8.9		



Material Test Report

Report Number: GSSW2352-1
Issue Number: 1
Date Issued: 14/02/2025
Client: PELLIS SULLIVAN MEYNINK (PSM)

Contact: Dane Pope
Project Number: GSSW2352
Project Name: 10-12 POINT VIEW ROAD
Project Location: McCRAE
Client Reference: PSM5665
Work Request: 22410
Sample Number: 2352-S2
Date Sampled: 24/01/2025
Dates Tested: 05/02/2025 - 13/02/2025
Sampling Method: Sampled by Client - Tested as Received
The results apply to the sample as received

Sample Location: On LHS/NE Slope, Depth: 0.00m

Lot No: Sample ID S2

Material: clayey/silty SAND, trace gravel, pale grey and brown, fine to coarse grained, low to medium plasticity, gravel 4%.



Ground Science South West
 Geotechnical & Environmental Consultants

Ground Science South West Pty Ltd
 8 Freedman Street North Geelong Vic 3215
 Phone: (03) 5282 1566

Email: chrism@groundsciencesw.com.au

Accredited for compliance with ISO/IEC 17025 - Testing



Irrelevant & Sensitive


Approved Signatory: Brent Elliott

Laboratory Manager

NATA Accredited Laboratory Number: 20109

Particle Size Distribution (AS1289 3.6.1)					
Sieve	Passed %	Passing Limits	Retained %	Retained Limits	
19 mm	100		0		
13.2 mm	98		2		
9.5 mm	98		0		
6.7 mm	98		0		
4.75 mm	98		0		
2.36 mm	96		1		
1.18 mm	88		9		
0.6 mm	76		11		
0.425 mm	67		9		
0.3 mm	56		12		
0.15 mm	45		11		
0.075 mm	28		16		

Moisture Content (AS1289.2.1.1)		Min	Max
Moisture Content (%)		19.0	



Material Test Report

Report Number: GSSW2352-1
Issue Number: 1
Date Issued: 14/02/2025
Client: PELLIS SULLIVAN MEYNINK (PSM)

Contact: Dane Pope
Project Number: GSSW2352
Project Name: 10-12 POINT VIEW ROAD
Project Location: McCRAE
Client Reference: PSM5665
Work Request: 22410
Sample Number: 2352-S3
Date Sampled: 24/01/2025
Dates Tested: 05/02/2025 - 13/02/2025
Sampling Method: Sampled by Client - Tested as Received
The results apply to the sample as received
Sample Location: Lower flank of RILL on RHS/SW Slope, Depth: 0.00m
Lot No: Sample ID S3
Material: clayey/silty SAND, trace gravel, pale grey, fine to coarse grained, low to medium plasticity, gravel 2%.



Ground Science South West
 Geotechnical & Environmental Consultants

Ground Science South West Pty Ltd
 8 Freedman Street North Geelong Vic 3215
 Phone: (03) 5282 1566

Email: chrism@groundsciencesw.com.au

Accredited for compliance with ISO/IEC 17025 - Testing




Irrelevant & Sensitive

Approved Signatory: Brent Elliott
 Laboratory Manager
 NATA Accredited Laboratory Number: 20109

Particle Size Distribution (AS1289 3.6.1)					
Sieve	Passed %	Passing Limits	Retained %	Retained Limits	
19 mm	100		0		
13.2 mm	100		0		
9.5 mm	99		1		
6.7 mm	99		0		
4.75 mm	99		0		
2.36 mm	98		1		
1.18 mm	91		7		
0.6 mm	80		11		
0.425 mm	71		9		
0.3 mm	61		10		
0.15 mm	50		11		
0.075 mm	35		15		

Moisture Content (AS1289.2.1.1)		Min	Max
Moisture Content (%)	15.9		



Material Test Report

Report Number: GSSW2352-1
Issue Number: 1
Date Issued: 14/02/2025
Client: PELLIS SULLIVAN MEYNINK (PSM)

Contact: Dane Pope
Project Number: GSSW2352
Project Name: 10-12 POINT VIEW ROAD
Project Location: McCRAE
Client Reference: PSM5665
Work Request: 22410
Sample Number: 2352-S4
Date Sampled: 24/01/2025
Dates Tested: 05/02/2025 - 13/02/2025
Sampling Method: Sampled by Client - Tested as Received
The results apply to the sample as received
Sample Location: Upper RHS/SW Slope, Gum Tree/Scarp, Depth: 0.00m
Lot No: Sample ID S4
Material: CH - sandy CLAY, trace gravel, pale grey mottled brown, high plasticity, sand 33% fine to coarse grained, gravel 1%.



Ground Science South West
 Geotechnical & Environmental Consultants

Ground Science South West Pty Ltd
 8 Freedman Street North Geelong Vic 3215
 Phone: (03) 5282 1566

Email: chrism@groundsciencesw.com.au

Accredited for compliance with ISO/IEC 17025 - Testing



Irrelevant & Sensitive


Approved Signatory: Brent Elliott
 Laboratory Manager
 NATA Accredited Laboratory Number: 20109

Particle Size Distribution (AS1289 3.6.1)				
Sieve	Passed %	Passing Limits	Retained %	Retained Limits
6.7 mm	100		0	
4.75 mm	100		0	
2.36 mm	99		0	
1.18 mm	97		3	
0.6 mm	91		6	
0.425 mm	87		4	
0.3 mm	82		5	
0.15 mm	75		7	
0.075 mm	66		9	

Moisture Content (AS1289.2.1.1)		Min	Max
Moisture Content (%)	34.0		

Atterberg Limit (AS1289 3.1.1 & 3.2.1 & 3.3.1)		Min	Max
Sample History	Oven Dried		
Preparation Method	Dry Sieve		
Liquid Limit (%)	55		
Plastic Limit (%)	19		
Plasticity Index (%)	36		

Linear Shrinkage (AS1289 3.4.1)		Min	Max
Moisture Condition Determined By	AS 1289.3.1.1		
Linear Shrinkage (%)	12.0		
Cracking Crumbling Curling	Curling		



Material Test Report

Report Number: GSSW2352-1
Issue Number: 1
Date Issued: 14/02/2025
Client: PELLIS SULLIVAN MEYNINK (PSM)

Contact: Dane Pope
Project Number: GSSW2352
Project Name: 10-12 POINT VIEW ROAD
Project Location: McCRAE
Client Reference: PSM5665
Work Request: 22410
Sample Number: 2352-S5
Date Sampled: 24/01/2025
Dates Tested: 05/02/2025 - 14/02/2025
Sampling Method: Sampled by Client - Tested as Received
The results apply to the sample as received

Sample Location: S4 Upper, Depth: 0.00m

Lot No: Sample ID S5

Material: sandy CLAY/SILT, trace gravel, pale grey, medium to high plasticity, sand 56% fine to coarse grained, gravel 2%.



Ground Science South West
 Geotechnical & Environmental Consultants

Ground Science South West Pty Ltd
 8 Freedman Street North Geelong Vic 3215
 Phone: (03) 5282 1566

Email: chrism@groundsciencesw.com.au

Accredited for compliance with ISO/IEC 17025 - Testing



Irrelevant & Sensitive


Approved Signatory: Brent Elliott

Laboratory Manager

NATA Accredited Laboratory Number: 20109

Particle Size Distribution (AS1289 3.6.1)					
Sieve	Passed %	Passing Limits	Retained %	Retained Limits	
6.7 mm	100		0		
4.75 mm	100		0		
2.36 mm	98		1		
1.18 mm	91		8		
0.6 mm	83		8		
0.425 mm	77		6		
0.3 mm	71		6		
0.15 mm	60		11		
0.075 mm	42		18		

Moisture Content (AS1289.2.1.1)		Min	Max
Moisture Content (%)		27.3	



Material Test Report

Report Number: GSSW2352-1
Issue Number: 1
Date Issued: 14/02/2025
Client: PELLIS SULLIVAN MEYNINK (PSM)

Contact: Dane Pope
Project Number: GSSW2352
Project Name: 10-12 POINT VIEW ROAD
Project Location: McCRAE
Client Reference: PSM5665
Work Request: 22410
Sample Number: 2352-S6
Date Sampled: 24/01/2025
Dates Tested: 05/02/2025 - 14/02/2025
Sampling Method: Sampled by Client - Tested as Received
The results apply to the sample as received

Sample Location: SW Flank 2022 Air Dry, Depth: 0.00m

Lot No: Sample ID S6

Material: SM - silty SAND, trace gravel, pale grey, fine to coarse grained, low plasticity, gravel 8%.



Ground Science South West
 Geotechnical & Environmental Consultants

Ground Science South West Pty Ltd
 8 Freedman Street North Geelong Vic 3215
 Phone: (03) 5282 1566

Email: chrism@groundsciencesw.com.au

Accredited for compliance with ISO/IEC 17025 - Testing



Irrelevant & Sensitive

Approved Signatory: Brent Elliott

Laboratory Manager


NATA Accredited Laboratory Number: 20109

Particle Size Distribution (AS1289 3.6.1)				
Sieve	Passed %	Passing Limits	Retained %	Retained Limits
19 mm	100		0	
13.2 mm	100		0	
9.5 mm	99		1	
6.7 mm	99		0	
4.75 mm	98		1	
2.36 mm	92		6	
1.18 mm	77		16	
0.6 mm	63		13	
0.425 mm	56		7	
0.3 mm	50		7	
0.15 mm	40		10	
0.075 mm	25		14	

Moisture Content (AS1289.2.1.1)		Min	Max
Moisture Content (%)	0.7		

Atterberg Limit (AS1289 3.1.1 & 3.2.1 & 3.3.1)		Min	Max
Sample History	Oven Dried		
Preparation Method	Dry Sieve		
Liquid Limit (%)	18		
Plastic Limit (%)	16		
Plasticity Index (%)	2		

Linear Shrinkage (AS1289 3.4.1)		Min	Max
Moisture Condition Determined By	AS 1289.3.1.1		
Linear Shrinkage (%)	1.0		
Cracking Crumbling Curling	Cracking		



Material Test Report

Report Number: GSSW2352-1
Issue Number: 1
Date Issued: 14/02/2025
Client: PELLIS SULLIVAN MEYNINK (PSM)

Contact: Dane Pope
Project Number: GSSW2352
Project Name: 10-12 POINT VIEW ROAD
Project Location: McCRAE
Client Reference: PSM5665
Work Request: 22410
Dates Tested: 05/02/2025 - 06/02/2025



Ground Science South West
 Geotechnical & Environmental Consultants

Ground Science South West Pty Ltd
 8 Freedman Street North Geelong Vic 3215
 Phone: (03) 5282 1566

Email: chrism@groundsciencesw.com.au

Accredited for compliance with ISO/IEC 17025 - Testing



Irrelevant & Sensitive

Approved Signatory: Brent Elliott
 Laboratory Manager
 NATA Accredited Laboratory Number: 20109

Moisture Content AS 1289 2.1.1

Sample Number	Sample Location	Moisture Content (%)	Min	Max	Material
2352-S1	RILL/Consolidated waste on slope, Depth: 0.00m	8.9 %	**	**	clayey/silty SAND, trace gravel, pale grey, fine to coarse grained, low to medium plasticity, gravel 2%.
2352-S2	On LHS/NE Slope, Depth: 0.00m	19.0 %	**	**	clayey/silty SAND, trace gravel, pale grey and brown, fine to coarse grained, low to medium plasticity, gravel 4%.
2352-S3	Lower flank of RILL on RHS/SW Slope, Depth: 0.00m	15.9 %	**	**	clayey/silty SAND, trace gravel, pale grey, fine to coarse grained, low to medium plasticity, gravel 2%.
2352-S4	Upper RHS/SW Slope, Gum Tree/Scarp, Depth: 0.00m	34.0 %	**	**	CH - sandy CLAY, trace gravel, pale grey mottled brown, high plasticity, sand 33% fine to coarse grained, gravel 1%.
2352-S5	S4 Upper, Depth: 0.00m	27.3 %	**	**	sandy CLAY/SILT, trace gravel, pale grey, medium to high plasticity, sand 56% fine to coarse grained, gravel 2%.
2352-S6	SW Flank 2022 Air Dry, Depth: 0.00m	0.7 %	**	**	SM - silty SAND, trace gravel, pale grey, fine to coarse grained, low plasticity, gravel 8%.

Material Test Report

Report Number: GSSW2352-2
Issue Number: 1
Date Issued: 25/03/2025
Client: PELLIS SULLIVAN MEYNINK (PSM)

Contact: Dane Pope
Project Number: GSSW2352
Project Name: McCRAE LANDSLIDE
Project Location: 10-12 POINT VIEW ROAD, McCRAE
Client Reference: PSM5665
Work Request: 22767
Sample Number: 2352-S7
Date Sampled: 17/02/2025
Dates Tested: 11/03/2025 - 21/03/2025
Sampling Method: Sampled by Client - Tested as Received
The results apply to the sample as received

Sample Location: BH03, Depth: 2.70m - 4.00m

Material: clayey/silty SAND, trace gravel, fine to coarse, low to medium plasticity, gravel 5%.



Ground Science South West
 Geotechnical & Environmental Consultants

Ground Science South West Pty Ltd
 8 Freedman Street North Geelong Vic 3215
 Phone: (03) 5282 1566

Email: chrism@groundsciencesw.com.au

Accredited for compliance with ISO/IEC 17025 - Testing




Irrelevant & Sensitive

Approved Signatory: Brent Elliott

Laboratory Manager

NATA Accredited Laboratory Number: 20109

Particle Size Distribution (AS1289 3.6.1)				
Sieve	Passed %	Passing Limits	Retained %	Retained Limits
75 mm	100		0	
63 mm	100		0	
53 mm	100		0	
37.5 mm	100		0	
26.5 mm	100		0	
19 mm	100		0	
9.5 mm	100		0	
6.7 mm	100		0	
4.75 mm	99		1	
2.36 mm	95		4	
1.18 mm	80		15	
0.6 mm	65		15	
0.425 mm	58		8	
0.3 mm	51		7	
0.15 mm	41		9	
0.075 mm	28		13	
Moisture Content (AS1289.2.1.1)				Min Max
Moisture Content (%)		4.7		



Material Test Report

Report Number: GSSW2352-2
Issue Number: 1
Date Issued: 25/03/2025
Client: PELLIS SULLIVAN MEYNINK (PSM)

Contact: Dane Pope
Project Number: GSSW2352
Project Name: McCRAE LANDSLIDE
Project Location: 10-12 POINT VIEW ROAD, McCRAE
Client Reference: PSM5665
Work Request: 22767
Sample Number: 2352-S8
Date Sampled: 17/02/2025
Dates Tested: 11/03/2025 - 24/03/2025
Sampling Method: Sampled by Client - Tested as Received
The results apply to the sample as received
Sample Location: BH03, Depth: 7.20m - 8.00m
Material: CL - sandy CLAY, low plasticity, sand 40% fine to coarse grained.



Ground Science South West
 Geotechnical & Environmental Consultants

Ground Science South West Pty Ltd
 8 Freedman Street North Geelong Vic 3215
 Phone: (03) 5282 1566

Email: chrism@groundsciencesw.com.au

Accredited for compliance with ISO/IEC 17025 - Testing



Irrelevant & Sensitive

Approved Signatory: Brent Elliott

Laboratory Manager


NATA Accredited Laboratory Number: 20109

Particle Size Distribution (AS1289 3.6.1)					
Sieve	Passed %	Passing Limits	Retained %	Retained Limits	
75 mm	100		0		
63 mm	100		0		
53 mm	100		0		
37.5 mm	100		0		
26.5 mm	100		0		
19 mm	100		0		
4.75 mm	100		0		
2.36 mm	100		0		
1.18 mm	98		2		
0.6 mm	92		6		
0.425 mm	88		5		
0.3 mm	82		6		
0.15 mm	71		10		
0.075 mm	60		12		

Moisture Content (AS1289.2.1.1)		Min	Max
Moisture Content (%)	9.3		

Atterberg Limit (AS1289 3.1.2 & 3.2.1 & 3.3.1)		Min	Max
Sample History	Oven Dried		
Preparation Method	Dry Sieve		
Liquid Limit (%)	27		
Plastic Limit (%)	12		
Plasticity Index (%)	15		

Linear Shrinkage (AS1289 3.4.1)		Min	Max
Moisture Condition Determined By	AS 1289.3.1.2		
Linear Shrinkage (%)	4.0		
Cracking Crumbling Curling	Cracking		



Material Test Report

Report Number: GSSW2352-2
Issue Number: 1
Date Issued: 25/03/2025
Client: PELLIS SULLIVAN MEYNINK (PSM)

Contact: Dane Pope
Project Number: GSSW2352
Project Name: McCRAE LANDSLIDE
Project Location: 10-12 POINT VIEW ROAD, McCRAE
Client Reference: PSM5665
Work Request: 22767
Sample Number: 2352-S9
Date Sampled: 17/02/2025
Dates Tested: 11/03/2025 - 25/03/2025
Sampling Method: Sampled by Client - Tested as Received
The results apply to the sample as received

Sample Location: BH03, Depth: 10.80m - 11.50m

Material: CI - sandy CLAY, trace gravel, medium plasticity, sand 57%
 fine to coarse grained, gravel 2%.



Ground Science South West
 Geotechnical & Environmental Consultants

Ground Science South West Pty Ltd
 8 Freedman Street North Geelong Vic 3215
 Phone: (03) 5282 1566

Email: chrism@groundsciencesw.com.au

Accredited for compliance with ISO/IEC 17025 - Testing



Irrelevant & Sensitive

Approved Signatory: Brent Elliott

Laboratory Manager


NATA Accredited Laboratory Number: 20109

Particle Size Distribution (AS1289 3.6.1)					
Sieve	Passed %	Passing Limits	Retained %	Retained Limits	
6.7 mm	100		0		
4.75 mm	100		0		
2.36 mm	98		2		
1.18 mm	86		12		
0.6 mm	72		13		
0.425 mm	66		7		
0.3 mm	59		6		
0.15 mm	51		9		
0.075 mm	41		10		

Moisture Content (AS1289.2.1.1)			
	Min	Max	
Moisture Content (%)	13.7		

Atterberg Limit (AS1289 3.1.2 & 3.2.1 & 3.3.1)			
	Min	Max	
Sample History	Oven Dried		
Preparation Method	Dry Sieve		
Liquid Limit (%)	37		
Plastic Limit (%)	16		
Plasticity Index (%)	21		

Linear Shrinkage (AS1289 3.4.1)			
	Min	Max	
Moisture Condition Determined By	AS 1289.3.1.2		
Linear Shrinkage (%)	7.0		
Cracking Crumbling Curling	Curling		



Material Test Report

Report Number: GSSW2352-2
Issue Number: 1
Date Issued: 25/03/2025
Client: PELLIS SULLIVAN MEYNINK (PSM)

Contact: Dane Pope
Project Number: GSSW2352
Project Name: McCRAE LANDSLIDE
Project Location: 10-12 POINT VIEW ROAD, McCRAE
Client Reference: PSM5665
Work Request: 22767
Sample Number: 2352-S10
Date Sampled: 17/02/2025
Dates Tested: 11/03/2025 - 25/03/2025
Sampling Method: Sampled by Client - Tested as Received
The results apply to the sample as received

Sample Location: BH03, Depth: 14.75m - 14.85m

Material: sandy CLAY/SILT, trace gravel, low to medium plasticity, sand 51% fine to coarse grained, gravel 5%.



Ground Science South West
 Geotechnical & Environmental Consultants

Ground Science South West Pty Ltd
 8 Freedman Street North Geelong Vic 3215
 Phone: (03) 5282 1566

Email: chrism@groundsciencesw.com.au

Accredited for compliance with ISO/IEC 17025 - Testing



Irrelevant & Sensitive


Approved Signatory: Brent Elliott

Laboratory Manager

NATA Accredited Laboratory Number: 20109

Particle Size Distribution (AS1289 3.6.1)					
Sieve	Passed %	Passing Limits	Retained %	Retained Limits	
6.7 mm	100		0		
4.75 mm	100		0		
2.36 mm	95		5		
1.18 mm	82		13		
0.6 mm	70		12		
0.425 mm	65		5		
0.3 mm	60		5		
0.15 mm	53		6		
0.075 mm	44		10		

Moisture Content (AS1289.2.1.1)				Min	Max
Moisture Content (%)		12.7			



Material Test Report

Report Number: GSSW2352-2
Issue Number: 1
Date Issued: 25/03/2025
Client: PELLIS SULLIVAN MEYNINK (PSM)

Contact: Dane Pope
Project Number: GSSW2352
Project Name: McCRAE LANDSLIDE
Project Location: 10-12 POINT VIEW ROAD, McCRAE
Client Reference: PSM5665
Work Request: 22767
Sample Number: 2352-S12
Date Sampled: 18/02/2025
Dates Tested: 11/03/2025 - 18/03/2025
Sampling Method: Sampled by Client - Tested as Received
The results apply to the sample as received

Sample Location: BH03, Depth: 21.40m - 21.55m

Material: sandy CLAY/SILT, trace gravel, low to medium plasticity, sand 56% fine to coarse grained, gravel 3%.



Ground Science South West
 Geotechnical & Environmental Consultants

Ground Science South West Pty Ltd
 8 Freedman Street North Geelong Vic 3215
 Phone: (03) 5282 1566

Email: chrism@groundsciencesw.com.au

Accredited for compliance with ISO/IEC 17025 - Testing



Irrelevant & Sensitive


Approved Signatory: Brent Elliott

Laboratory Manager

NATA Accredited Laboratory Number: 20109

Particle Size Distribution (AS1289 3.6.1)					
Sieve	Passed %	Passing Limits	Retained %	Retained Limits	
9.5 mm	100		0		
6.7 mm	100		0		
4.75 mm	99		0		
2.36 mm	97		2		
1.18 mm	83		14		
0.6 mm	68		15		
0.425 mm	61		7		
0.3 mm	54		6		
0.15 mm	47		7		
0.075 mm	41		6		

Moisture Content (AS1289.2.1.1)		Min	Max
Moisture Content (%)	11.5		



Material Test Report

Report Number: GSSW2352-2
Issue Number: 1
Date Issued: 25/03/2025
Client: PELLIS SULLIVAN MEYNINK (PSM)

Contact: Dane Pope
Project Number: GSSW2352
Project Name: McCRAE LANDSLIDE
Project Location: 10-12 POINT VIEW ROAD, McCRAE
Client Reference: PSM5665
Work Request: 22767
Sample Number: 2352-S13
Date Sampled: 18/02/2025
Dates Tested: 11/03/2025 - 25/03/2025
Sampling Method: Sampled by Client - Tested as Received
The results apply to the sample as received

Sample Location: BH03, Depth: 23.30m - 23.40m

Material: clayey/silty SAND, trace gravel, fine to coarse grained, low to medium plasticity, gravel 13% fine.



Ground Science South West
 Geotechnical & Environmental Consultants

Ground Science South West Pty Ltd
 8 Freedman Street North Geelong Vic 3215
 Phone: (03) 5282 1566

Email: chrism@groundsciencesw.com.au

Accredited for compliance with ISO/IEC 17025 - Testing




Irrelevant & Sensitive

Approved Signatory: Brent Elliott

Laboratory Manager

NATA Accredited Laboratory Number: 20109

Particle Size Distribution (AS1141.11.1)					
Sample Washing	Sample was Washed				
Sieve	Passed %	Passing Limits	Retained %	Retained Limits	
9.5 mm	100		0		
6.7 mm	100		0		
4.75 mm	99		1		
2.36 mm	87		12		
1.18 mm	67		19		
0.6 mm	53		14		
0.425 mm	46		7		
0.3 mm	40		6		
0.15 mm	31		8		
0.075 mm	23		9		
Moisture Content (1289.2.1.1)				Min	Max
Moisture Content (%)			5.5		



Material Test Report

Report Number: GSSW2352-2
Issue Number: 1
Date Issued: 25/03/2025
Client: PELLIS SULLIVAN MEYNINK (PSM)

Contact: Dane Pope
Project Number: GSSW2352
Project Name: McCRAE LANDSLIDE
Project Location: 10-12 POINT VIEW ROAD, McCRAE
Client Reference: PSM5665
Work Request: 22767
Sample Number: 2352-S14
Date Sampled: 19/02/2025
Dates Tested: 11/03/2025 - 25/03/2025
Sampling Method: Sampled by Client - Tested as Received
The results apply to the sample as received

Sample Location: BH01, Depth: 1.40m - 2.30m

Material: clayey/silty SAND, trace gravel, fine to coarse grained, low to medium plasticity, gravel 5%.



Ground Science South West
 Geotechnical & Environmental Consultants

Ground Science South West Pty Ltd
 8 Freedman Street North Geelong Vic 3215
 Phone: (03) 5282 1566

Email: chrism@groundsciencesw.com.au

Accredited for compliance with ISO/IEC 17025 - Testing




Irrelevant & Sensitive

Approved Signatory: Brent Elliott

Laboratory Manager

NATA Accredited Laboratory Number: 20109

Particle Size Distribution (AS1141.11.1)					
Sample Washing	Sample was Washed				
Sieve	Passed %	Passing Limits	Retained %	Retained Limits	
13.2 mm	100		0		
9.5 mm	100		0		
6.7 mm	99		0		
4.75 mm	99		0		
2.36 mm	95		4		
1.18 mm	79		15		
0.6 mm	63		16		
0.425 mm	54		9		
0.3 mm	46		8		
0.15 mm	37		10		
0.075 mm	26		10		
Moisture Content (1289.2.1.1)					
			Min	Max	
Moisture Content (%)			4.4		



Material Test Report

Report Number: GSSW2352-2
Issue Number: 1
Date Issued: 25/03/2025
Client: PELLIS SULLIVAN MEYNINK (PSM)

Contact: Dane Pope
Project Number: GSSW2352
Project Name: McCRAE LANDSLIDE
Project Location: 10-12 POINT VIEW ROAD, McCRAE
Client Reference: PSM5665
Work Request: 22767
Sample Number: 2352-S15
Date Sampled: 19/02/2025
Dates Tested: 11/03/2025 - 24/03/2025
Sampling Method: Sampled by Client - Tested as Received
The results apply to the sample as received

Sample Location: BH01, Depth: 7.20m - 8.00m

Material: CL - sandy CLAY, trace gravel, low plasticity, sand 52% fine to coarse grained, gravel 1%.



Ground Science South West
 Geotechnical & Environmental Consultants

Ground Science South West Pty Ltd
 8 Freedman Street North Geelong Vic 3215
 Phone: (03) 5282 1566

Email: chrism@groundsciencesw.com.au

Accredited for compliance with ISO/IEC 17025 - Testing



Irrelevant & Sensitive

Approved Signatory: Brent Elliott

Laboratory Manager


NATA Accredited Laboratory Number: 20109

Particle Size Distribution (AS1289 3.6.1)					
Sieve	Passed %	Passing Limits	Retained %	Retained Limits	
19 mm	100		0		
13.2 mm	99		1		
9.5 mm	99		0		
6.7 mm	99		0		
4.75 mm	99		0		
2.36 mm	99		1		
1.18 mm	92		6		
0.6 mm	83		10		
0.425 mm	77		6		
0.3 mm	71		6		
0.15 mm	60		10		
0.075 mm	47		13		

Moisture Content (AS1289.2.1.1)		Min	Max
Moisture Content (%)	11.3		

Atterberg Limit (AS1289 3.1.2 & 3.2.1 & 3.3.1)		Min	Max
Sample History	Oven Dried		
Preparation Method	Dry Sieve		
Liquid Limit (%)	32		
Plastic Limit (%)	12		
Plasticity Index (%)	20		

Linear Shrinkage (AS1289 3.4.1)		Min	Max
Moisture Condition Determined By	AS 1289.3.1.2		
Linear Shrinkage (%)	6.0		
Cracking Crumbling Curling	Cracking		



Material Test Report

Report Number: GSSW2352-2
Issue Number: 1
Date Issued: 25/03/2025
Client: PELLIS SULLIVAN MEYNINK (PSM)

Contact: Dane Pope
Project Number: GSSW2352
Project Name: McCRAE LANDSLIDE
Project Location: 10-12 POINT VIEW ROAD, McCRAE
Client Reference: PSM5665
Work Request: 22767
Sample Number: 2352-S18
Date Sampled: 21/02/2025
Dates Tested: 11/03/2025 - 21/03/2025
Sampling Method: Sampled by Client - Tested as Received
The results apply to the sample as received

Sample Location: BH02, Depth: 1.60m - 2.60m

Material: clayey/silty SAND, trace gravel, fine to coarse grained, low to medium plasticity, gravel 7%.



Ground Science South West
 Geotechnical & Environmental Consultants

Ground Science South West Pty Ltd
 8 Freedman Street North Geelong Vic 3215
 Phone: (03) 5282 1566

Email: chrism@groundsciencesw.com.au

Accredited for compliance with ISO/IEC 17025 - Testing



Irrelevant & Sensitive


Approved Signatory: Brent Elliott

Laboratory Manager

NATA Accredited Laboratory Number: 20109

Particle Size Distribution (AS1289 3.6.1)					
Sieve	Passed %	Passing Limits	Retained %	Retained Limits	
13.2 mm	100		0		
9.5 mm	100		0		
6.7 mm	99		1		
4.75 mm	98		1		
2.36 mm	93		5		
1.18 mm	79		13		
0.6 mm	67		12		
0.425 mm	60		7		
0.3 mm	53		7		
0.15 mm	42		11		
0.075 mm	26		16		

Moisture Content (AS1289.2.1.1)		Min	Max
Moisture Content (%)	1.4		



Material Test Report

Report Number: GSSW2352-2
Issue Number: 1
Date Issued: 25/03/2025
Client: PELLIS SULLIVAN MEYNINK (PSM)

Contact: Dane Pope
Project Number: GSSW2352
Project Name: McCRAE LANDSLIDE
Project Location: 10-12 POINT VIEW ROAD, McCRAE
Client Reference: PSM5665
Work Request: 22767
Sample Number: 2352-S19
Date Sampled: 21/02/2025
Dates Tested: 11/03/2025 - 24/03/2025
Sampling Method: Sampled by Client - Tested as Received
The results apply to the sample as received

Sample Location: BH02, Depth: 4.20m - 5.00m

Material: CL - sandy CLAY, trace gravel, low plasticity, sand 55% fine to coarse grained, gravel 1%.



Ground Science South West
 Geotechnical & Environmental Consultants

Ground Science South West Pty Ltd
 8 Freedman Street North Geelong Vic 3215
 Phone: (03) 5282 1566

Email: chrism@groundsciencesw.com.au

Accredited for compliance with ISO/IEC 17025 - Testing



Irrelevant & Sensitive

Approved Signatory: Brent Elliott

Laboratory Manager


NATA Accredited Laboratory Number: 20109

Particle Size Distribution (AS1289 3.6.1)					
Sieve	Passed %	Passing Limits	Retained %	Retained Limits	
6.7 mm	100		0		
4.75 mm	100		0		
2.36 mm	99		1		
1.18 mm	88		11		
0.6 mm	76		12		
0.425 mm	69		6		
0.3 mm	63		6		
0.15 mm	54		9		
0.075 mm	44		10		

Moisture Content (AS1289.2.1.1)			
	Min	Max	
Moisture Content (%)	3.9		

Atterberg Limit (AS1289 3.1.2 & 3.2.1 & 3.3.1)			
	Min	Max	
Sample History	Oven Dried		
Preparation Method	Dry Sieve		
Liquid Limit (%)	25		
Plastic Limit (%)	12		
Plasticity Index (%)	13		

Linear Shrinkage (AS1289 3.4.1)			
	Min	Max	
Moisture Condition Determined By	AS 1289.3.1.2		
Linear Shrinkage (%)	4.5		
Cracking Crumbling Curling	Cracking		



Material Test Report

Report Number: GSSW2352-2
Issue Number: 1
Date Issued: 25/03/2025
Client: PELLIS SULLIVAN MEYNINK (PSM)

Contact: Dane Pope
Project Number: GSSW2352
Project Name: McCRAE LANDSLIDE
Project Location: 10-12 POINT VIEW ROAD, McCRAE
Client Reference: PSM5665
Work Request: 22767
Sample Number: 2352-S20
Date Sampled: 21/02/2025
Dates Tested: 11/03/2025 - 24/03/2025
Sampling Method: Sampled by Client - Tested as Received
The results apply to the sample as received
Sample Location: BH02, Depth: 6.70m - 7.50m
Material: CI - sandy CLAY, medium plasticity, sand 43% fine to coarse grained.



Ground Science South West
 Geotechnical & Environmental Consultants

Ground Science South West Pty Ltd
 8 Freedman Street North Geelong Vic 3215
 Phone: (03) 5282 1566

Email: chrism@groundsciencesw.com.au

Accredited for compliance with ISO/IEC 17025 - Testing



Irrelevant & Sensitive


Approved Signatory: Brent Elliott
 Laboratory Manager
 NATA Accredited Laboratory Number: 20109

Particle Size Distribution (AS1289 3.6.1)					
Sieve	Passed %	Passing Limits	Retained %	Retained Limits	
4.75 mm	100		0		
2.36 mm	100		0		
1.18 mm	95		5		
0.6 mm	88		7		
0.425 mm	83		5		
0.3 mm	78		5		
0.15 mm	68		10		
0.075 mm	57		11		

Moisture Content (AS1289.2.1.1)			
	Min	Max	
Moisture Content (%)	11.1		

Atterberg Limit (AS1289 3.1.2 & 3.2.1 & 3.3.1)			
	Min	Max	
Sample History	Oven Dried		
Preparation Method	Dry Sieve		
Liquid Limit (%)	43		
Plastic Limit (%)	17		
Plasticity Index (%)	26		

Linear Shrinkage (AS1289 3.4.1)			
	Min	Max	
Moisture Condition Determined By	AS 1289.3.1.2		
Linear Shrinkage (%)	9.0		
Cracking Crumbling Curling	Curling		



Material Test Report

Report Number: GSSW2352-2
Issue Number: 1
Date Issued: 25/03/2025
Client: PELLIS SULLIVAN MEYNINK (PSM)

Contact: Dane Pope
Project Number: GSSW2352
Project Name: McCRAE LANDSLIDE
Project Location: 10-12 POINT VIEW ROAD, McCRAE
Client Reference: PSM5665
Work Request: 22767
Sample Number: 2352-S23
Date Sampled: 26/02/2025
Dates Tested: 11/03/2025 - 25/03/2025
Sampling Method: Sampled by Client - Tested as Received
The results apply to the sample as received

Sample Location: BH05, Depth: 2.60m - 3.60m

Material: clayey/silty SAND, trace gravel, fine to coarse grained, low to medium plasticity, gravel 6%.



Ground Science South West
 Geotechnical & Environmental Consultants

Ground Science South West Pty Ltd
 8 Freedman Street North Geelong Vic 3215
 Phone: (03) 5282 1566

Email: chrism@groundsciencesw.com.au

Accredited for compliance with ISO/IEC 17025 - Testing



Irrelevant & Sensitive

Approved Signatory: Brent Elliott


Laboratory Manager

NATA Accredited Laboratory Number: 20109

Particle Size Distribution (AS1141.11.1)

Sample Washing	Sample was Washed			
Sieve	Passed %	Passing Limits	Retained %	Retained Limits
9.5 mm	100		0	
6.7 mm	100		0	
4.75 mm	99		0	
2.36 mm	94		5	
1.18 mm	81		13	
0.6 mm	68		13	
0.425 mm	60		7	
0.3 mm	53		7	
0.15 mm	42		11	
0.075 mm	29		12	

Moisture Content (1289.2.1.1)	Min	Max
Moisture Content (%)	13.0	



Material Test Report

Report Number: GSSW2352-2
Issue Number: 1
Date Issued: 25/03/2025
Client: PELLIS SULLIVAN MEYNINK (PSM)

Contact: Dane Pope
Project Number: GSSW2352
Project Name: McCRAE LANDSLIDE
Project Location: 10-12 POINT VIEW ROAD, McCRAE
Client Reference: PSM5665
Work Request: 22767
Sample Number: 2352-S24
Date Sampled: 26/02/2025
Dates Tested: 11/03/2025 - 24/03/2025
Sampling Method: Sampled by Client - Tested as Received
The results apply to the sample as received
Sample Location: BH04, Depth: 3.10m - 3.60m
Material: SILT, low plasticity.



Ground Science South West
 Geotechnical & Environmental Consultants

Ground Science South West Pty Ltd
 8 Freedman Street North Geelong Vic 3215
 Phone: (03) 5282 1566

Email: chrism@groundsciencesw.com.au

Accredited for compliance with ISO/IEC 17025 - Testing



Irrelevant & Sensitive

Approved Signatory: Brent Elliott
 Laboratory Manager
 NATA Accredited Laboratory Number: 20109

Atterberg Limit (AS1289 3.1.2 & 3.2.1 & 3.3.1)		Min	Max
Sample History	Oven Dried		
Preparation Method	Dry Sieve		
Liquid Limit (%)	16		
Plastic Limit (%)	14		
Plasticity Index (%)	2		

Linear Shrinkage (AS1289 3.4.1)		Min	Max
Moisture Condition Determined By	AS 1289.3.1.2		
Linear Shrinkage (%)	1.0		
Cracking Crumbling Curling	Cracking		

Material Test Report

Report Number: GSSW2352-2
Issue Number: 1
Date Issued: 25/03/2025
Client: PELLIS SULLIVAN MEYNINK (PSM)

Contact: Dane Pope
Project Number: GSSW2352
Project Name: McCRAE LANDSLIDE
Project Location: 10-12 POINT VIEW ROAD, McCRAE
Client Reference: PSM5665
Work Request: 22767
Sample Number: 2352-S25
Date Sampled: 26/02/2025
Dates Tested: 11/03/2025 - 24/03/2025
Sampling Method: Sampled by Client - Tested as Received
The results apply to the sample as received
Sample Location: BH04, Depth: 5.00m - 5.80m
Material: CLAY, low plasticity.



Ground Science South West
 Geotechnical & Environmental Consultants

Ground Science South West Pty Ltd
 8 Freedman Street North Geelong Vic 3215
 Phone: (03) 5282 1566

Email: chrism@groundsciencesw.com.au

Accredited for compliance with ISO/IEC 17025 - Testing



Irrelevant & Sensitive

Approved Signatory: Brent Elliott
 Laboratory Manager
 NATA Accredited Laboratory Number: 20109

Atterberg Limit (AS1289 3.1.2 & 3.2.1 & 3.3.1)		Min	Max
Sample History	Oven Dried		
Preparation Method	Dry Sieve		
Liquid Limit (%)	30		
Plastic Limit (%)	13		
Plasticity Index (%)	17		

Linear Shrinkage (AS1289 3.4.1)		Min	Max
Moisture Condition Determined By	AS 1289.3.1.2		
Linear Shrinkage (%)	5.5		
Cracking Crumbling Curling	Cracking & Curling		

Material Test Report

Report Number: GSSW2352-2
Issue Number: 1
Date Issued: 25/03/2025
Client: PELLIS SULLIVAN MEYNINK (PSM)

Contact: Dane Pope
Project Number: GSSW2352
Project Name: McCRAE LANDSLIDE
Project Location: 10-12 POINT VIEW ROAD, McCRAE
Client Reference: PSM5665
Work Request: 22767
Dates Tested: 11/03/2025 - 12/03/2025
Sampling Method: Sampled by Client - Tested as Received
The results apply to the sample as received



Ground Science South West
 Geotechnical & Environmental Consultants

Ground Science South West Pty Ltd
 8 Freedman Street North Geelong Vic 3215
 Phone: (03) 5282 1566

Email: chrism@groundsciencesw.com.au

Accredited for compliance with ISO/IEC 17025 - Testing



Irrelevant & Sensitive

Approved Signatory: Brent Elliott
 Laboratory Manager
 NATA Accredited Laboratory Number: 20109

Moisture Content AS 1289 2.1.1

Sample Number	Sample Location	Moisture Content (%)	Min	Max	Material
2352-S10	BH03, Depth: 14.75m - 14.85m	12.7 %	**	**	sandy CLAY/SILT, trace gravel, low to medium plasticity, sand 51% fine to coarse grained, gravel 5%.
2352-S11	BH03, Depth: 15.50m - 15.60m	5.9 %	**	**	**
2352-S12	BH03, Depth: 21.40m - 21.55m	11.5 %	**	**	sandy CLAY/SILT, trace gravel, low to medium plasticity, sand 56% fine to coarse grained, gravel 3%.
2352-S13	BH03, Depth: 23.30m - 23.40m	5.5 %	**	**	clayey/silty SAND, trace gravel, fine to coarse grained, low to medium plasticity, gravel 13% fine.
2352-S16	BH01, Depth: 17.80m - 17.90m	0.6 %	**	**	**
2352-S17	BH01, Depth: 22.90m - 23.00m	0.6 %	**	**	**
2352-S22	BH05, Depth: 1.60m - 2.30m	10.0 %	**	**	**
2352-S26	BH04, Depth: 15.00m - 15.10m	3.4 %	**	**	**

Appendix F

Surface Water Testing – Detailed Laboratory Reports

DRAFT



Legend
● Surface Water Sampling
— Cadastral
— Roads



Job No: 68664

Client: PSM


Version: DRAFT

Date: 24-Jan-2025

Drawn By: RT

Checked By: JH

Scale 1:2,000



Coord. Sys. GDA2020 MGA Zone 55

**Point Nepean Rd
McCrae, Victoria**

SURFACE WATER SAMPLING

FIGURE 2

DRAFT

Controlled Copy (June 2015)
© 2011-2019 JBS&G Australia Pty Ltd

DRAFT

T: 03 9642 0599 | M: 0498 733 092 | E: jphall@jbsg.com.au | W: jbsg.com.au | L: [Conditions and Limitations](#)

Exceptional Outcomes



Re: 68664 - Updated COC

From Karl Bulow <Karl.Bulow@eurofinsanz.com>
Date Mon 20/01/25 4:01 PM
To Jake P. Hall <jphall@jbsg.com.au>; Harry Bacalis <Harry.Bacalis@eurofinsanz.com>;
SH_AU_CAU001_EnviroSampleVic <EnviroSampleVic@eurofinsanz.com>

Verified Sender: This email is from an internal and/or verified domain which passed security verifications.
Remember to still be cautious with personal data and follow company policies.

Thanks Jake.

[@SH_AU_CAU001_EnviroSampleVic](#) - Please use this updated COC for report **68664 - 72 hour TAT**.

Kind Regards,

Karl Bulow
Analytical Services Manager SA

Eurofins | Environment Testing
6 Monterey Rd
Dandenong South, VIC, 3175

Mobile : 0477 574 867
Email : karl.bulow@eurofinsanz.com

This e-mail including its attachments may contain confidential and proprietary information. Any unauthorized disclosure or use of this e-mail including its attachments is prohibited and may be prosecuted. If you are not the intended recipient, please inform the sender by an e-mail reply and delete the message.
Transmission by e-mail is not secure and can result in errors or omissions in the content of the message. Despite state-of-the-art precautions we cannot guarantee that e-mails and attachments are free from viruses. We accept no liability for viruses or any transmission-related errors and omissions. You need to always virus-check any e-mails and attachments.
Eurofins companies are independent legal entities that are bound only by members of their management bodies. No other persons have representation power unless specifically authorised by proxy or other legal means.

From: Jake P. Hall <jphall@jbsg.com.au>
Sent: Monday, January 20, 2025 3:58 PM
To: Karl Bulow <Karl.Bulow@eurofinsanz.com>; Harry Bacalis <Harry.Bacalis@eurofinsanz.com>
Cc: SH_AU_CAU001_EnviroSampleVic <EnviroSampleVic@eurofinsanz.com>
Subject: RE: 68664 - Updated COC

Unverified Sender: The sender of this email has not been verified. Review the content of the message carefully and verify the identity of the sender before acting on this email: replying, opening attachments or clicking links.

Hi Karl,

Please see attached.

Cheers,

 **Jake Hall | Senior Project Scientist | JBS&G**
Wurundjeri Country | Level 19, 31 Queen Street, Melbourne, VIC

From: Karl Bulow <Karl.Bulow@eurofinsanz.com>
Sent: Monday, 20 January 2025 3:45 PM
To: Jake P. Hall <jphall@jbsg.com.au>; Harry Bacalis <Harry.Bacalis@eurofinsanz.com>
Cc: SH_AU_CAU001_EnviroSampleVic <EnviroSampleVic@eurofinsanz.com>
Subject: Re: 68664 - Updated COC

*****[EXTERNAL EMAIL] Stop and think before opening attachments, clicking or responding.*****

Hi Jake,

If possible, would you be able to send an updated COC attachment that includes Fluoride added. Mainly so we can send that to enviro-lab as well so they don't miss it.

Kind Regards,

Karl Bulow
Analytical Services Manager SA

Eurofins | Environment Testing
6 Monterey Rd
Dandenong South, VIC, 3175

Mobile : 0477 574 867
Email : karl.bulow@eurofinsanz.com

This e-mail including its attachments may contain confidential and proprietary information. Any unauthorized disclosure or use of this e-mail including its attachments is prohibited and may be prosecuted. If you are not the intended recipient, please inform the sender by an e-mail reply and delete the message.

Transmission by e-mail is not secure and can result in errors or omissions in the content of the message. Despite state-of-the-art precautions we cannot guarantee that e-mails and attachments are free from viruses. We accept no liability for viruses or any transmission-related errors and omissions. You need to always virus-check any e-mails and attachments.
Eurofins companies are independent legal entities that are bound only by members of their management bodies. No other persons have representation power unless specifically authorised by proxy or other legal means.

From: Jake P. Hall <jphall@jbsg.com.au>
Sent: Monday, January 20, 2025 3:40 PM
To: Harry Bacalis <Harry.Bacalis@eurofinsanz.com>
Cc: Karl Bulow <Karl.Bulow@eurofinsanz.com>
Subject: 68664 - Updated COC

Unverified Sender: The sender of this email has not been verified. Review the content of the message carefully and verify the identity of the sender before acting on this email: replying, opening attachments or clicking links.

Hi Harry,

Hope you are well.

I dropped off some samples today (around 2:00pm) that are on a 72hr TAT.

Can I please add **Fluoride** analysis to all samples (including those being forwarded onto Envirolab)

DRAFT

DATE 2-18-75
TIME 10:22
COURT 10:22
TEMPERATURE
ATTEMPT TO CHIEF YES NO

COPY EL 1

Chain of Custody

DRAFT

[illegible]

DRAFT

Controlled Copy (June 2015)
© 2011-2019 JBS&G Australia Pty Ltd

JBS & G Australia (VIC) P/L
 PO Box 3166
 Norwood
 SA 5067



NATA Accredited
 Accreditation Number 1261
 Site Number 1254

Accredited for compliance with ISO/IEC 17025 – Testing
 NATA is a signatory to the ILAC Mutual Recognition
 Arrangement for the mutual recognition of the
 equivalence of testing, medical testing, calibration,
 inspection, proficiency testing scheme providers and
 reference materials producers reports and certificates.

Attention: **Jake Hall**

Report **1179041-W**
 Project name **LAND SLIDE WATER TESTING**
 Project ID **68664**
 Received Date **Jan 20, 2025**

Client Sample ID			SW01	SW02	SW03	SW04
Sample Matrix			Water	Water	Water	Water
Eurofins Sample No.			M25- Ja0027677	M25- Ja0027678	M25- Ja0027679	M25- Ja0027680
Date Sampled			Jan 20, 2025	Jan 20, 2025	Jan 20, 2025	Jan 20, 2025
Test/Reference	LOR	Unit				
Ammonia (as N)	0.01	mg/L	0.02	0.79	0.48	0.62
Chloride	1	mg/L	19	81	90	89
Conductivity (at 25 °C)	10	uS/cm	140	400	480	440
Fluoride	0.5	mg/L	< 0.5	< 0.5	< 0.5	< 0.5
Nitrate (as N)	0.02	mg/L	0.27	< 0.02	< 0.4	< 0.4
pH (at 25 °C)	0.1	pH Units	6.8	6.9	7.2	7.4
Sulphate (as SO ₄)	5	mg/L	< 5	19	27	20
Total Dissolved Solids Dried at 180 °C ± 2 °C	10	mg/L	100	1400	1400	1100
Alkalinity (speciated)						
Bicarbonate Alkalinity (as CaCO ₃)	20	mg/L	41	79	95	93
Carbonate Alkalinity (as CaCO ₃)	10	mg/L	< 10	< 10	< 10	< 10
Alkali Metals						
Calcium	0.5	mg/L	9.6	8.4	11	10
Magnesium	0.5	mg/L	1.6	7.7	8.2	7.6
Potassium	0.5	mg/L	1.2	2.5	3.3	2.8
Sodium	0.5	mg/L	11	55	64	57
Heavy Metals						
Arsenic (filtered)	0.001	mg/L	< 0.001	< 0.001	< 0.001	< 0.001
Cadmium (filtered)	0.0002	mg/L	< 0.0002	< 0.0002	< 0.0002	< 0.0002
Chromium (filtered)	0.001	mg/L	< 0.001	< 0.001	< 0.001	< 0.001
Copper (filtered)	0.001	mg/L	0.004	0.006	0.006	0.005
Lead (filtered)	0.001	mg/L	< 0.001	< 0.001	< 0.001	< 0.001
Mercury (filtered)	0.0001	mg/L	< 0.0001	< 0.0001	< 0.0001	< 0.0001
Nickel (filtered)	0.001	mg/L	< 0.001	0.001	0.001	0.001
Zinc (filtered)	0.005	mg/L	0.008	< 0.005	< 0.005	< 0.005

Client Sample ID			SW05 Water M25- Ja0027681 Jan 20, 2025	DUP01 Water M25- Ja0027682 Jan 20, 2025	DUP02 Water M25- Ja0027683 Jan 20, 2025	DUP03 Water M25- Ja0027684 Jan 20, 2025
Sample Matrix						
Eurofins Sample No.						
Date Sampled						
Test/Reference	LOR	Unit				
Ammonia (as N)	0.01	mg/L	0.42	0.44	0.52	0.45
Chloride	1	mg/L	240	82	92	220
Conductivity (at 25 °C)	10	uS/cm	1200	420	480	1200
Fluoride	0.5	mg/L	< 0.5	< 0.5	< 0.5	< 0.5
Nitrate (as N)	0.02	mg/L	< 0.4	< 0.4	< 0.4	< 0.02
pH (at 25 °C)	0.1	pH Units	8.0	6.9	7.3	8.0
Sulphate (as SO4)	5	mg/L	100	18	26	100
Total Dissolved Solids Dried at 180 °C ± 2 °C	10	mg/L	640	2000	1800	1000
Alkalinity (speciated)						
Bicarbonate Alkalinity (as CaCO3)	20	mg/L	190	88	91	220
Carbonate Alkalinity (as CaCO3)	10	mg/L	< 10	< 10	< 10	< 10
Alkali Metals						
Calcium	0.5	mg/L	41	8.3	11	42
Magnesium	0.5	mg/L	21	7.8	8.1	21
Potassium	0.5	mg/L	14	2.6	3.4	14
Sodium	0.5	mg/L	160	56	63	150
Heavy Metals						
Arsenic (filtered)	0.001	mg/L	0.007	< 0.001	< 0.001	0.007
Cadmium (filtered)	0.0002	mg/L	< 0.0002	< 0.0002	< 0.0002	< 0.0002
Chromium (filtered)	0.001	mg/L	0.002	0.001	< 0.001	0.002
Copper (filtered)	0.001	mg/L	0.008	0.006	0.005	0.008
Lead (filtered)	0.001	mg/L	< 0.001	< 0.001	< 0.001	< 0.001
Mercury (filtered)	0.0001	mg/L	< 0.0001	< 0.0001	< 0.0001	< 0.0001
Nickel (filtered)	0.001	mg/L	0.002	0.001	0.001	0.002
Zinc (filtered)	0.005	mg/L	0.009	< 0.005	< 0.005	0.008

Sample History

Where samples are submitted/analysed over several days, the last date of extraction is reported.

If the date and time of sampling are not provided, the Laboratory will not be responsible for compromised results should testing be performed outside the recommended holding time.

Description	Testing Site	Extracted	Holding Time
Eurofins Suite B11B			
Ammonia (as N)	Melbourne	Jan 21, 2025	28 Days
- Method: APHA 4500-NH3 Ammonia Nitrogen by FIA			
Chloride	Melbourne	Jan 21, 2025	28 Days
- Method: LTM-INO-4090 Chloride by Discrete Analyser			
Conductivity (at 25 °C)	Melbourne	Jan 21, 2025	28 Days
- Method: LTM-INO-4030 Conductivity			
Nitrate (as N)	Melbourne	Jan 21, 2025	28 Days
- Method: LTM-INO-4120 Analysis of NOx NO2 NH3 by FIA			
Sulphate (as SO4)	Melbourne	Jan 21, 2025	28 Days
- Method: LTM-INO-4110 Sulfate by Discrete Analyser			
Total Dissolved Solids Dried at 180 °C ± 2 °C	Melbourne	Jan 21, 2025	28 Days
- Method: LTM-INO-4170 Total Dissolved Solids in Water			
Alkalinity (speciated)	Melbourne	Jan 21, 2025	14 Days
- Method: LTM-INO-4250 Alkalinity by Electrometric Titration			
Alkali Metals	Melbourne	Jan 21, 2025	180 Days
- Method: LTM-MET-3010 Alkali Metals Sulfur Silicon Phosphorus by ICP-AES			
Fluoride	Melbourne	Jan 21, 2025	28 Days
- Method: LTM-INO-4270 Anions by Ion Chromatography			
pH (at 25 °C)	Melbourne	Jan 21, 2025	6 Hours
- Method: LTM-GEN-7090 pH in water by ISE			
Metals M8 filtered	Melbourne	Jan 21, 2025	28 Days
- Method: LTM-MET-3040 Metals in Waters, Soils & Sediments by ICP-MS			

Melbourne	Geelong	Sydney	Canberra	Brisbane	Newcastle
6 Monterey Road Dandenong South VIC 3175 +61 3 8564 5000 NATA# 1261 Site# 1254	19/8 Lewalan Street Grovedale VIC 3216 +61 3 8564 5000 NATA# 1261 Site# 25403	179 Magowar Road Girraween NSW 2145 +61 2 9900 8400 NATA# 1261 Site# 18217	Unit 1,2 Dacre Street Mitchell ACT 2911 +61 2 6113 8091 NATA# 1261 Site# 25466	1/21 Smallwood Place Murarrie QLD 4172 T: +61 7 3902 4600 NATA# 1261 Site# 20794 & 2780	1/2 Frost Drive Mayfield West NSW 2304 +61 2 4968 8448 NATA# 1261 Site# 25079

Perth
46-48 Banksia Road Welshpool WA 6106 +61 8 6253 4444 NATA# 2377 Site# 2370 & 2554

Auckland	Auckland (Focus)	Christchurch	Tauranga
35 O'Rourke Road Penrose, Auckland 1061 +64 9 526 4551 IANZ# 1327	Unit C2 Pacific Ridge Mount Wellington Auckland +64 9 525 0568 IANZ# 1308	3 Deton Drive Colleston Christchurch 76 +64 3 343 5201 IANZ# 1290	1233 Hamer Road, Gate P Tauranga 31 +64 9 525 0568 IANZ# 1402

Company Name: JBS & G Australia (VIC) P/L
Address: PO Box 3166
Norwood
SA 5067
Project Name: LAND SLIDE WATER TESTING
Project ID: 68664

Order No.:
Report #: 1179041
Phone: 03 9642 0599
Fax:

Received: Jan 20, 2025 3:58 PM
Due: Jan 23, 2025
Priority: 3 Day
Contact Name: Jake Hall

Eurofins Analytical Services Manager : Harry Bacalis

Sample Detail						Fluoride	pH (at 25 °C)	Metals M8 filtered	Eurofins Suite B11B
Melbourne Laboratory - NATA # 1261 Site # 1254						X	X	X	X
External Laboratory									
No	Sample ID	Sample Date	Sampling Time	Matrix	LAB ID				
1	SW01	Jan 20, 2025		Water	M25-Ja0027677	X	X	X	X
2	SW02	Jan 20, 2025		Water	M25-Ja0027678	X	X	X	X
3	SW03	Jan 20, 2025		Water	M25-Ja0027679	X	X	X	X
4	SW04	Jan 20, 2025		Water	M25-Ja0027680	X	X	X	X
5	SW05	Jan 20, 2025		Water	M25-Ja0027681	X	X	X	X
6	DUP01	Jan 20, 2025		Water	M25-Ja0027682	X	X	X	X
7	DUP02	Jan 20, 2025		Water	M25-Ja0027683	X	X	X	X
8	DUP03	Jan 20, 2025		Water	M25-Ja0027684	X	X	X	X
Test Counts						8	8	8	8

Internal Quality Control Review and Glossary

General

1. Laboratory QC results for Method Blanks, Duplicates, Matrix Spikes, and Laboratory Control Samples follow guidelines delineated in the National Environment Protection (Assessment of Site Contamination) Measure 1999, as amended May 2013. They are included in this QC report where applicable. Additional QC data may be available on request.
2. Unless otherwise stated, all soil/sediment/solid results are reported on a dry weight basis.
3. Unless otherwise stated, all biota/food results are reported on a wet weight basis on the edible portion.
4. For CEC results where the sample's origin is unknown or environmentally contaminated, the results should be used advisedly.
5. Actual LORs are matrix dependent. Quoted LORs may be raised where sample extracts are diluted due to interferences.
6. Results are uncorrected for matrix spikes or surrogate recoveries except for PFAS compounds where annotated.
7. SVOC analysis on waters is performed on homogenised, unfiltered samples unless noted otherwise.
8. Samples were analysed on an 'as received' basis.
9. Information identified in this report with **blue** colour indicates data provided by customers that may have an impact on the results.
10. This report replaces any interim results previously issued.

Holding Times

Please refer to the 'Sample Preservation and Container Guide' for holding times (QS3001).

For samples received on the last day of holding time, notification of testing requirements should have been received at least 6 hours before sample receipt deadlines as stated on the SRA.

If the Laboratory did not receive the information in the required timeframe, and despite any other integrity issues, suitably qualified results may still be reported.

Holding times apply from the sampling date; therefore, compliance with these may be outside the laboratory's control.

For VOCs containing vinyl chloride, styrene and 2-chloroethyl vinyl ether, the holding time is seven days; however, for all other VOCs, such as BTEX or C6-10 TRH, the holding time is 14 days.

Units

mg/kg: milligrams per kilogram	mg/L: milligrams per litre	ppm: parts per million
µg/L: micrograms per litre	ppb: parts per billion	%: Percentage
org/100 mL: Organisms per 100 millilitres	NTU: Nephelometric Turbidity Units	MPN/100 mL: Most Probable Number of organisms per 100 millilitres
CFU: Colony Forming Unit	Colour: Pt-Co Units (CU)	

Terms

APHA	American Public Health Association
CEC	Cation Exchange Capacity
COC	Chain of Custody
CP	Client Parent - QC was performed on samples pertaining to this report
CRM	Certified Reference Material (ISO17034) - reported as percent recovery.
Dry	Where moisture has been determined on a solid sample, the result is expressed on a dry weight basis.
Duplicate	A second piece of analysis from the same sample and reported in the same units as the result to show comparison.
LOR	Limit of Reporting.
LCS	Laboratory Control Sample - reported as percent recovery.
Method Blank	In the case of solid samples, these are performed on laboratory-certified clean sands and in the case of water samples, these are performed on de-ionised water.
NCP	Non-Client Parent - QC performed on samples not pertaining to this report, QC represents the sequence or batch that client samples were analysed within.
RPD	Relative Percent Difference between two Duplicate pieces of analysis.
SPIKE	Addition of the analyte to the sample and reported as percentage recovery.
SRA	Sample Receipt Advice
Surr - Surrogate	The addition of a similar compound to the analyte target is reported as percentage recovery. See below for acceptance criteria.
TBTO	Tributyltin oxide (bis-tributyltin oxide) - individual tributyltin compounds cannot be identified separately in the environment; however, free tributyltin was measured, and its values were converted stoichiometrically into tributyltin oxide for comparison with regulatory limits.
TCLP	Toxicity Characteristic Leaching Procedure
TEQ	Toxic Equivalency Quotient or Total Equivalence
QSM	US Department of Defense Quality Systems Manual Version 6.0
US EPA	United States Environmental Protection Agency
WA DWER	Sum of PFBA, PFPeA, PFHxA, PFHpA, PFOA, PFBS, PFHxS, PFOS, 6:2 FTSA, 8:2 FTSA

QC - Acceptance Criteria

The acceptance criteria should only be used as a guide and may be different when site-specific Sampling Analysis and Quality Plan (SAQP) have been implemented.

RPD Duplicates: Global RPD Duplicates Acceptance Criteria is ≤30%; however, the following acceptance guidelines are equally applicable:

Results <10 times the LOR:	No Limit
Results between 10-20 times the LOR:	RPD must lie between 0-50%
Results >20 times the LOR:	RPD must lie between 0-30%

NOTE: pH duplicates are reported as a range, not as RPD

Surrogate Recoveries: Recoveries must lie between 20-130% for Speciated Phenols & 50-150% for PFAS. SVOCs recoveries 20 – 150%, VOC recoveries 50 – 150%

PFAS field samples containing surrogate recoveries above the QC limit designated in QSM 6.0, where no positive PFAS results have been reported or reviewed, and no data was affected.

QC Data General Comments

1. Where a result is reported as less than (<), higher than the nominated LOR, this is due to either matrix interference, extract dilution required due to interferences or contaminant levels within the sample, high moisture content or insufficient sample provided.
2. Duplicate data shown within this report that states the word "BATCH" is a Batch Duplicate from outside of your sample batch but within the laboratory sample batch at a 1:10 ratio. The Parent and Duplicate data shown are not data from your samples.
3. pH and Free Chlorine analysed in the laboratory - Analysis on this test must begin within 30 minutes of sampling. Therefore, laboratory analysis is unlikely to be completed within holding time. Analysis will begin as soon as possible after sample receipt.
4. Recovery Data (Spikes & Surrogates) - where chromatographic interference does not allow the determination of recovery, the term "INT" appears against that analyte.
5. For Matrix Spikes and LCS results, a dash "-" in the report means that the specific analyte was not added to the QC sample.
6. Duplicate RPDs are calculated from raw analytical data; thus, it is possible to have two sets of data.

Quality Control Results

Test	Units	Result 1			Acceptance Limits	Pass Limits	Qualifying Code
Method Blank							
Chloride	mg/L	< 1			1	Pass	
Conductivity (at 25 °C)	uS/cm	< 10			10	Pass	
Sulphate (as SO ₄)	mg/L	< 5			5	Pass	
Total Dissolved Solids Dried at 180 °C ± 2 °C	mg/L	< 10			10	Pass	
Method Blank							
Alkali Metals							
Calcium	mg/L	< 0.5			0.5	Pass	
Magnesium	mg/L	< 0.5			0.5	Pass	
Potassium	mg/L	< 0.5			0.5	Pass	
Sodium	mg/L	< 0.5			0.5	Pass	
Method Blank							
Heavy Metals							
Arsenic (filtered)	mg/L	< 0.001			0.001	Pass	
Cadmium (filtered)	mg/L	< 0.0002			0.0002	Pass	
Chromium (filtered)	mg/L	< 0.001			0.001	Pass	
Copper (filtered)	mg/L	< 0.001			0.001	Pass	
Lead (filtered)	mg/L	< 0.001			0.001	Pass	
Mercury (filtered)	mg/L	< 0.0001			0.0001	Pass	
Nickel (filtered)	mg/L	< 0.001			0.001	Pass	
Zinc (filtered)	mg/L	< 0.005			0.005	Pass	
Method Blank							
Fluoride	mg/L	< 0.5			0.5	Pass	
Method Blank							
Fluoride	mg/L	< 0.5			0.5	Pass	
Method Blank							
Ammonia (as N)	mg/L	< 0.01			0.01	Pass	
Method Blank							
Alkali Metals							
Calcium	mg/L	< 0.5			0.5	Pass	
Magnesium	mg/L	< 0.5			0.5	Pass	
Potassium	mg/L	< 0.5			0.5	Pass	
Sodium	mg/L	< 0.5			0.5	Pass	
Method Blank							
Alkali Metals							
Calcium	mg/L	< 0.5			0.5	Pass	
Magnesium	mg/L	< 0.5			0.5	Pass	
Potassium	mg/L	< 0.5			0.5	Pass	
Sodium	mg/L	< 0.5			0.5	Pass	
LCS - % Recovery							
Chloride	%	108			70-130	Pass	
Conductivity (at 25 °C)	%	98			70-130	Pass	
Sulphate (as SO ₄)	%	113			70-130	Pass	
Total Dissolved Solids Dried at 180 °C ± 2 °C	%	101			70-130	Pass	
LCS - % Recovery							
Alkalinity (speciated)							
Carbonate Alkalinity (as CaCO ₃)	%	94			70-130	Pass	
LCS - % Recovery							
Alkali Metals							
Calcium	%	98			80-120	Pass	
Magnesium	%	99			80-120	Pass	
Potassium	%	97			80-120	Pass	

Test			Units	Result 1			Acceptance Limits	Pass Limits	Qualifying Code
Sodium			%	97			80-120	Pass	
LCS - % Recovery									
Heavy Metals									
Arsenic (filtered)			%	94			80-120	Pass	
Cadmium (filtered)			%	93			80-120	Pass	
Chromium (filtered)			%	96			80-120	Pass	
Copper (filtered)			%	94			80-120	Pass	
Lead (filtered)			%	89			80-120	Pass	
Mercury (filtered)			%	91			80-120	Pass	
Nickel (filtered)			%	95			80-120	Pass	
Zinc (filtered)			%	95			80-120	Pass	
LCS - % Recovery									
Fluoride			%	73			70-130	Pass	
LCS - % Recovery									
Fluoride			%	82			70-130	Pass	
LCS - % Recovery									
Ammonia (as N)			%	80			70-130	Pass	
LCS - % Recovery									
Alkali Metals									
Calcium			%	93			80-120	Pass	
Magnesium			%	93			80-120	Pass	
Potassium			%	90			80-120	Pass	
Sodium			%	92			80-120	Pass	
LCS - % Recovery									
Ammonia (as N)			%	97			70-130	Pass	
LCS - % Recovery									
Alkali Metals									
Calcium			%	101			80-120	Pass	
Magnesium			%	100			80-120	Pass	
Potassium			%	97			80-120	Pass	
Sodium			%	98			80-120	Pass	
Test	Lab Sample ID	QA Source	Units	Result 1			Acceptance Limits	Pass Limits	Qualifying Code
Spike - % Recovery									
				Result 1					
Sulphate (as SO ₄)	M25-Ja0027677	CP	%	98			70-130	Pass	
Spike - % Recovery									
				Result 1					
Arsenic (filtered)	M25-Ja0027677	CP	%	95			75-125	Pass	
Cadmium (filtered)	M25-Ja0027677	CP	%	93			75-125	Pass	
Chromium (filtered)	M25-Ja0027677	CP	%	95			75-125	Pass	
Copper (filtered)	M25-Ja0027677	CP	%	94			75-125	Pass	
Lead (filtered)	M25-Ja0027677	CP	%	89			75-125	Pass	
Mercury (filtered)	M25-Ja0027677	CP	%	93			75-125	Pass	
Nickel (filtered)	M25-Ja0027677	CP	%	93			75-125	Pass	
Zinc (filtered)	M25-Ja0027677	CP	%	96			75-125	Pass	
Spike - % Recovery									
				Result 1					
Ammonia (as N)	M25-Ja0027678	CP	%	88			70-130	Pass	
Spike - % Recovery									
				Result 1					
Calcium	M25-Ja0027678	CP	%	93			75-125	Pass	
Magnesium	M25-Ja0027678	CP	%	91			75-125	Pass	
Sodium	M25-Ja0027678	CP	%	88			75-125	Pass	
Spike - % Recovery									

Test	Lab Sample ID	QA Source	Units	Result 1			Acceptance Limits	Pass Limits	Qualifying Code
				Result 1					
Ammonia (as N)	M25-Ja0027684	CP	%	74			70-130	Pass	
Test	Lab Sample ID	QA Source	Units	Result 1			Acceptance Limits	Pass Limits	Qualifying Code
Duplicate									
				Result 1	Result 2	RPD			
Chloride	M25-Ja0025136	NCP	mg/L	5200	5200	<1	30%	Pass	
Conductivity (at 25 °C)	M25-Ja0024891	NCP	uS/cm	33	36	7.6	30%	Pass	
pH (at 25 °C)	M25-Ja0024891	NCP	pH Units	5.0	5.0	pass	30%	Pass	
Sulphate (as SO ₄)	M25-Ja0025136	NCP	mg/L	1200	1200	1.0	30%	Pass	
Total Dissolved Solids Dried at 180 °C ± 2 °C	M25-Ja0027677	CP	mg/L	100	130	25	30%	Pass	
Duplicate									
Heavy Metals				Result 1	Result 2	RPD			
Arsenic (filtered)	M25-Ja0027677	CP	mg/L	< 0.001	< 0.001	<1	30%	Pass	
Cadmium (filtered)	M25-Ja0027677	CP	mg/L	< 0.0002	< 0.0002	<1	30%	Pass	
Chromium (filtered)	M25-Ja0027677	CP	mg/L	< 0.001	< 0.001	<1	30%	Pass	
Copper (filtered)	M25-Ja0027677	CP	mg/L	0.004	0.005	3.0	30%	Pass	
Lead (filtered)	M25-Ja0027677	CP	mg/L	< 0.001	< 0.001	<1	30%	Pass	
Mercury (filtered)	M25-Ja0027677	CP	mg/L	< 0.0001	< 0.0001	<1	30%	Pass	
Nickel (filtered)	M25-Ja0027677	CP	mg/L	< 0.001	< 0.001	<1	30%	Pass	
Zinc (filtered)	M25-Ja0027677	CP	mg/L	0.008	0.009	6.0	30%	Pass	
Duplicate									
				Result 1	Result 2	RPD			
Fluoride	M25-Ja0027678	CP	mg/L	< 0.5	< 0.5	<1	30%	Pass	
Duplicate									
Alkali Metals				Result 1	Result 2	RPD			
Calcium	M25-Ja0027678	CP	mg/L	8.4	8.3	1.0	30%	Pass	
Magnesium	M25-Ja0027678	CP	mg/L	7.7	7.8	<1	30%	Pass	
Potassium	M25-Ja0027678	CP	mg/L	2.5	2.5	<1	30%	Pass	
Sodium	M25-Ja0027678	CP	mg/L	55	55	<1	30%	Pass	
Duplicate									
				Result 1	Result 2	RPD			
Fluoride	M25-Ja0027680	CP	mg/L	< 0.5	< 0.5	<1	30%	Pass	
Duplicate									
				Result 1	Result 2	RPD			
Ammonia (as N)	M25-Ja0027683	CP	mg/L	0.52	0.43	18	30%	Pass	

DRAFT

Environment Testing

Comments

Sample Integrity

Custody Seals Intact (if used)	N/A
Attempt to Chill was evident	Yes
Sample correctly preserved	Yes
Appropriate sample containers have been used	Yes
Sample containers for volatile analysis received with minimal headspace	Yes
Samples received within HoldingTime	Yes
Some samples have been subcontracted	No

Authorised by:

Karl Bulow	Analytical Services Manager
Mary Makarios	Senior Analyst-Inorganic
Vivian Wang	Senior Analyst-Metal

Irrelevant & Sensitive

Managing Director

Final Report – this report replaces any previously issued Report

- Indicates Not Requested

* Indicates NATA accreditation does not cover the performance of this service

Measurement uncertainty of test data is available on request or please [click here](#).

Eurofins shall not be liable for loss, cost, damages or expenses incurred by the client, or any other person or company, resulting from the use of any information or interpretation given in this report. In no case shall Eurofins be liable for consequential damages including, but not limited to, lost profits, damages for failure to meet deadlines and lost production arising from this report. This document shall not be reproduced except in full and relates only to the items tested. Unless indicated otherwise, the tests were performed on the samples as received.

Project Number: 68664 Project Name: Land Slide Water Quality Testing , 599 Point Nepean Road , PSM



DRAFT

	Metals & Metalloids								Non-Metallic Inorganics			Major Cations		
	Arsenic (filtered)	Cadmium (filtered)	Chromium (III+VI) (filtered)	Copper (filtered)	Lead (filtered)	Mercury (filtered)	Nickel (filtered)	Zinc (filtered)	Ammonia as N	Fluoride	Nitrate (as N)	Calcium	Potassium	Magnesium
	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	MG/L	mg/L	mg/L	mg/L
EQL	0.001	0.0002	0.001	0.001	0.001	0.0001	0.001	0.005	0.01	0.5	0.02	0.5	0.5	0.5

Location Code	Field ID	Date	Lab Report Number														
SW01	SW01	20 Jan 2025	1179041	<0.001	<0.0002	<0.001	0.004	<0.001	<0.0001	<0.001	0.008	0.02	<0.5	0.27	9.6	1.2	1.6
SW02	SW02	20 Jan 2025	1179041	<0.001	<0.0002	<0.001	0.006	<0.001	<0.0001	0.001	<0.005	0.79	<0.5	<0.02	8.4	2.5	7.7
SW03	SW03	20 Jan 2025	1179041	<0.001	<0.0002	<0.001	0.006	<0.001	<0.0001	0.001	<0.005	0.48	<0.5	<0.4	11	3.3	8.2
SW04	SW04	20 Jan 2025	1179041	<0.001	<0.0002	<0.001	0.005	<0.001	<0.0001	0.001	<0.005	0.62	<0.5	<0.4	10	2.8	7.6
SW05	SW05	20 Jan 2025	1179041	0.007	<0.0002	0.002	0.008	<0.001	<0.0001	0.002	0.009	0.42	<0.5	<0.4	41	14	21

DRAFT

Project Number: 68664 Project Name: Land Slide Water Quality Testing , 599 Point Nepean Road , PSM




	Arsenic (filtered)	Sodium	Alkalinity (Carbonate as CaCO3)	Major Anions			Ionic Balance		Other
				Alkalinity (Bicarbonate as CaCO3)	Chloride	Sulphate	Electrical Conductivity (Lab)	pH (Lab)	TDS
	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	µS/cm	pH Units	mg/L
EQL	0.001	0.5	10	20	1	5	10	0.1	10

Location Code	Field ID	Date	Lab Report Number									
SW01	SW01	20 Jan 2025	1179041	<0.001	11	<10	41	19	<5	140	6.8	100
SW02	SW02	20 Jan 2025	1179041	<0.001	55	<10	79	81	19	400	6.9	1,400
SW03	SW03	20 Jan 2025	1179041	<0.001	64	<10	95	90	27	480	7.2	1,400
SW04	SW04	20 Jan 2025	1179041	<0.001	57	<10	93	89	20	440	7.4	1,100
SW05	SW05	20 Jan 2025	1179041	0.007	160	<10	190	240	100	1,200	8.0	640


Appendix G

Piezometer Monitoring Results

Groundwater Monitoring BH01



Groundwater Monitoring BH02



Notes: 1. Daily rainfall data has been averaged from the daily rainfall available at Rosebud (Country Club) Station ID 86213 and Arthurs Seat Rain Gauge at Seawinds National Park Station ID 586202. This data is provided up to 24/03/2025.




Mornington Peninsula Shire Council
McCrae Landslide
Geotechnical Investigation
Groundwater Monitoring
BH01 and BH02


PSM5665-GFR

FIGURE G1

Groundwater Monitoring BH03 and BH03A



Groundwater Monitoring BH04



Notes: 1. Daily rainfall data has been averaged from the daily rainfall available at Rosebud (Country Club) Station ID 86213 and Arthurs Seat Rain Gauge at Seawinds National Park Station ID 586202. This data is provided up to 24/03/2025.




Mornington Peninsula Shire Council
McCrae Landslide
Geotechnical Investigation
Groundwater Monitoring
BH03, BH03A and BH04


PSM5665-GFR

FIGURE G2

Groundwater Monitoring BH05



Groundwater Monitoring NDT02



Notes: 1. Daily rainfall data has been averaged from the daily rainfall available at Rosebud (Country Club) Station ID 86213 and Arthurs Seat Rain Gauge at Seawinds National Park Station ID 586202. This data is provided up to 24/03/2025.



Mornington Peninsula Shire Council
McCrae Landslide
Geotechnical Investigation
Groundwater Monitoring
BH05 and NDT02

PSM5665-GFR

FIGURE G3